ACCESS CONTROL SCHEDULE

DOOR #	DOOR NAME	PLAN REF	DOOR FEATURES													SCHEDULE NOTES
			CARD READER - IN	CARD READER - OUT	LOCAL ANNUNCIATOR	ELECTRIC STRIKE	MAGNETIC LOCK	DOOR CONTACT SWITCH	DELAYED EGRESS LOCK	KEYSWITCH BYPASS	REX - MOTION DETECTOR	REX - PUSH BUTTON	REMOTE UNLOCK VIA PUSHBOTTON	REMOTE UNLOCK VIA FIRE COMMAND CENTER	(S)INGLE/(D)OUBLE /(A)UTOMATIC	
1C-1	MEDICATION PREP 1C02D-1	01TY102	X			X		X			X				S	
1C-2	OUTPATIENT PHARM. 1C02-1 SW	01TY102	X			X		X			X				S	
1C-5	OFFICE 1C02F-1	01TY102	X			X		X			X				S	
1C-6	OUTPATIENT PHARM. 1C02-1 NW	01TY102	X			X		X			X				S	
1C-9	OFFICE 1C05-1	01TY102	X			X		X			X				S	
1C-10	OFFICE 1C04-1	01TY102	X			X		X			X				S	
1C-11	DISPENSING AREA 1C03C	01TY102	X			X		X			X				S	
1C-12	PHARM. VAULT 1C02B-1	01TY102	X				X	X			X	X			S	2
1C-13	COUNSEL OFFICE 1C03B	01TY102	X			X		X			X				S	
53-2	INPATIENT PHARMACY BB-100	53TY100	X				X	X			X	X			D	2
53-3	VAULT BB-101	53TY100	X			X		X			X	X			S	
53-4	BB104	53TY100	X				X	X			X	X			D	2

NOTES:

1. DOORS WITH SMART CARD READER AND KEYPAD SHALL BE CONFIGURED AS DUAL AUTHENTICATION, REQUIRED VALID BADGE PRESENTATION AND VALID PIN
2 FOR DOORS WITH MORE THAN ONE LEAF WITH DOOR CONTACT SWITCHES, THE SWITCHES SHALL OPERATE INDEPENDENTLY, THEY SHALL NOT BE WIRED IN SERIES.

SCHEDULE NOTES:

1. DOOR OPEN SIGNAL SHALL BE TRANSMITTED TO SECURITY COMMAND CENTER AND ADJACENT AUDIBLE ANNUNCIATOR. SECURITY DEPARTMENT SHALL HAVE THE ABILITY TO BYPASS THE ALARM REMOTELY.
2. CONTRACTOR SHALL BE RESPONSIBLE FOR REQUIRED BRACKET(S) FOR PROPER ATTACHMENT OF MAGNETIC LOCK. BRACKETS SHALL BE FROM THE LOCK MANUFACTURER, THEY SHALL NOT BE CUSTOM MADE.
3. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION OF DOOR SEQUENCING AND ADA ACTUATOR ON ASSOCIATED AUTOMATIC DOOR. ADA ACTUATOR ON SECURED SIDE SHALL BE ACTIVE AT ALL TIMES. UNSECURED SIDE ADA ACTUATOR SHALL ONLY BE ACTIVE FOR 10 SECONDS AFTER A VALID CREDENTIAL HAS BEEN PRESENTED.
4. READER SHALL BE MOUNTED 60" A.F.F. TO CENTER, AND CABLING SHALL INCLUDE 4' OF COILED SLACK ABOVE THE CEILING.
5 ADJUSTABLE TIME FOR DOOR CONTACT SHUNT WHEN EXIT BUTTON IS ACTIVATED

ISSUED FOR CONSTRUCTION

No.	Description	Date

Revisions

Dept. of Veterans Affairs
Jack C. Montgomery
Medical Center
1011 Honor Height Drive
Muskogee, Oklahoma 74401

APPROVED:	APPROVED: President A.F.G.E. 2250	APPROVED: Energy Engineer	APPROVED: Medical Center Director
APPROVED:	APPROVED:	APPROVED: Safety Manager	APPROVED: Associate Director
APPROVED:	APPROVED:	APPROVED: Infection Control Nurse	APPROVED: Chief of Staff
APPROVED:	APPROVED:	APPROVED: Industrial Hygienist	APPROVED: Chief of Engineering Service

Drawing Title: TECHNOLOGY SCHEDULES

Project Title: REPLACE SURVEILLANCE SYSTEM

Scale: AS SHOWN

Building Number: SITE

Location: Jack C. Montgomery VA Medical Center - Muskogee, OK

Date: 08.23.13

Project No. 623.12.105

Approved:	Checked By:	Drawn By:
TWC - JCMVAMC	DAVLAR	KEIEVE

Drawing No. 00 TY502

Dwg. 14 of 25

Department of Veterans Affairs

VA FORM 08-6231 PRINTED ON: May 16, 2017 ORIGINAL SIZE OF SHEET IS 30" X 42"