



1ST FLOOR
SCALE: 1/16" = 1'

 DEPRESSED SLAB

- GENERAL NOTES**
- SEE APPENDIX "A" OF THE MASTER CONSTRUCTION SPECIFICATION (EQUIPMENT AND ACCESSORIES GUIDE LIST FOR CASEWORK & EQUIPMENT DESCRIPTIONS & QUANTITIES FOR EACH RM. TYPE/SEE DRWG 50-10 FOR RM. 5-10 EQUIP.)
 - SEE APPENDIX "B" OF THE MASTER CONSTRUCTION SPECIFICATION FOR WOOD TRIM DESCRIPTIONS AND COMBINATIONS.
 - BEAM & SLAB FIRE-PROOFING-UL ASSEMBLY 196C GYRO DR EQUIVALENT 1/2" FIBER FIRE-PROOFING SPRAY
 - COLUMN FIRE-PROOFING-UL ASSEMBLY 176A GYRO DR EQUIVALENT 1/2" FIBER FIRE-PROOFING SPRAY ± 3/16" THICK, SUCH AS XCEL.
 - ALL BASEMENT CORNER GUARDS ARE TO BE STAINLESS STEEL. SEE FINISH SCHEDULE AND FINISHES LIST IN 09050 OF THE MCS FOR OTHER BUMPER AND CORNER GUARD TYPES.
 - SEE ROOM FINISH SCHEDULE & FLOOR AND WALL PATTERN DRAWINGS IN 09050 OF THE MCS FOR CARPET AND TILE TYPES & LAYOUTS.
 - INCLUDE 6"x6" (16GA) HTL PLATES IN STUD WALL CONSTRUCTION (82"-6", 82"-0", 82"-8" AFF.) WHERE CASEWORK & SHELVING OCCUR.
 - THIS IS A FULLY SPRINKLERED BUILDING.

NO.	REVISION	DATE	BY
1	ISSUE FOR PERMITS	08/11/11	JR
2	FOR CONSTRUCTION	08/11/11	JR

REVISIONS

NO. REVISION DATE BY

1 ISSUE FOR PERMITS 08/11/11 JR

2 FOR CONSTRUCTION 08/11/11 JR

APPROVED FOR PERMITS AND CONSTRUCTION BY: 

DATE: 08/11/11

PROJECT NO.: 09-00000000

DATE: 08/11/11

Zelder Roberts Partnership Inc.
ARCHITECTS

BALTIMORE VA
REHAB & EXTENDED
CARE CENTER
BALTIMORE



Drawn: JR Date: 1/16" = 1'-0"
Checked: Date:
Title: FIRST FLOOR PLAN

RECORD DRAWING
THIS DRAWING, AS PREPARED BY THE CONTRACTOR OF RECORD, HAS BEEN REVIEWED FOR GENERAL CONTENT BY ZRPI AND SHOULD BE MADE PART OF THE OWNERS PERMANENT RECORDS.
ZELDER ROBERTS PARTNERSHIP, INC.