

**SECTION 09 06 00  
SCHEDULE FOR FINISHES**

**SECTION 09 06 00-SCHEDULE FOR FINISHES**

VAMC: Palo Alto Health Care System

Location: 3801 Miranda Avenue, Palo Alto, California, 94304

Project no. and Name: 640-12-124P Renovate Canteen Plaza

Submission100%CD

Date: May 16, 2014

RENOVATE CANTEEN PLAZA  
Palo Alto, CA  
VA Palo Alto Health Care System

DVA Project No. 640-12-124P

## **PART 1 – GENERAL**

### **1.01 DESCRIPTION**

- A. This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

### **1.02 MANUFACTURERS**

- A. Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer for finish requirements.

### **1.03 SUBMITALS**

- A. Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES-provide quadruplicate samples for color approval of materials and finishes specified in this section.

- B. DIGITAL COLOR PHOTOS-EXTERIOR VIEWS:

<b>Location</b>	<b>Item/View to be Photographed</b>
1.Upper Plaza	As viewed from the canteen

2.Upper Plaza	As viewed from the second floor of the B100/B101 bridge toward pavilions
3.Upper Plaza	View of Glass Sculpture/water feature
4.Rose Garden	View of "When you Wish" Sculpture from Patient drop-off near B100 looking toward Aquatic Building
5. Rose Garden	View of "You my Butterfly" Sculpture from path looking toward the Rose Garden
6. Lower Plaza (Sensory Garden)	View of the overall plaza as viewed from the patient drop-off of the polytrauma building looking toward the RecServices Buildings
7. Lower Plaza (Sensory Garden)	View of the bronze sculpture grouping-"Cone & Sphere"
8. Lower Plaza (Sensory Garden)	View of the bronze sculpture grouping- "Cone Measuring Sphere"
9. Lower Plaza (Sensory Garden)	View of the bronze sculpture grouping-"Kissing Couple"

#### 1.04 APPLICABLE PUBLICATIONS

- A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.
- B. MASTER PAINTING INSTITUTE: (MPI)  
2001 .....Architectural Painting Specification Manual

#### PART 2- PRODUCTS

##### 2.01 DIGITAL COLOR PHOTOS

- A. Size 24 x 35 mm.
- B. Labeled for:
  - 1. Location name.
  - 2. View orientation

##### 2.02 Division 32 - Site Improvements

- A. SECTION 32 05 23, CEMENT AND CONCRETE FOR EXTERIOR IMPROVEMENTS
  - 1. For Cement and Concrete for Exterior Improvements, Section 32 05 23 refer to specification section.

2222222 2222828739ehusdh;sedhf[yhw[408r2

2222222222222222 22221

B. SECTION 32 13 20, SITE CONCRETE

1. For Site Concrete, Section 32 13 20 refer to specification section.

**2.03 DIVISION 33 – SANITARY SEWER UTILITIES**

A. SECTION 33 30 00, SANITARY SEWER UTILITIES

1. For Sanitary Sewer Utilities, Section 33 30 00 refer to specification section.

**2.04 DIVISION 34 - SITE IMPROVEMENTS**

A. SECTION 34 40 00, STORM DRAIN UTILITIES

1. For Storm Drain Utilities, Section 34 40 00 refer to specification section.

**2.05 DIVISION 05 – METALS**

A. SECTION 05 12 00, STRUCTURAL STEEL FRAMING

Component	Finish	Color
Pavilion - Frames	Shop powder coated over HDG, Gloss Level 5 Semi-Gloss	Kelly Moore-Sierra White

B. SECTION 05 50 00, METAL FABRICATION

Item	Finish
Pavilion-Wire Mesh Frames, Panel Channel Units	Stainless Steel Type 304

RENOVATE CANTEEN PLAZA  
Palo Alto, CA  
VA Palo Alto Health Care System

DVA Project No. 640-12-124P

Pavilion Panels - Wire Mesh	Stainless Steel Type 304
-----------------------------	--------------------------

## 2.06 DIVISION 06 WOOD, PLASTICS, AND COMPOSITES

### A. SECTION 06 30 00, WOOD LOUVERS

WOOD LOUVERS	
Location	Finish
Upper Plaza Pavilions	lpe –prefinished penetrating oil all sides

## 2. 07 DIVISION 09 – FINISHES

### A. SECTION 09 91 00, PAINT AND COATINGS

#### 1. MPI Gloss and Sheen Standards

		Gloss @60	Sheen @85
Gloss Level 1	a traditional matte finish-flat	max 5 units, and	max 10 units
Gloss Level 2	a high side sheen flat-“a velvet-like” finish	max 10 units, and	10-35 units
Gloss Level 3	a traditional “egg-shell like” finish	10-25 units, and	10-35 units
Gloss Level 4	a “satin-like” finish	20-35 units, and	min. 35 units
Gloss Level 5	a traditional semi-gloss	35-70 units	
Gloss Level 6	a traditional gloss	70-85 units	
Gloss Level 7	a high gloss	more than 85 units	

## SCHEDULE FOR FINISHES

09 06 00 - 5



**2. 08 DIVISION 10 – SPECIALTIES**

A. SECTION 10 22 13.01 / 10 13 00 / 10 14 00

1. Refer to specific specification sections.

B. SECTION 10 22 13.01, WIRE MESH PANELS

Location	Finish
Upper Plaza-Pavilions	S.S. Type 304

**2. 09 DIVISION 12- FURNISHINGS**

A. SECTION 12 93 00, SITE FURNISHINGS

1. For site furnishings refer to specification Section 12 93 00

**2. 10 DIVISON 26 - ELECTRICAL**

**A. SECTION 26 56 00, SITE LIGHTING**

Type and Component	Exterior Finish	Manufacturer	Mfg. Name/No.
C, In-grade	Manufacturer's Polyester powder coat "Stealth Gray"	Kim	
D, Step Lights	Manufacturer's powder coated Aluminum "Silver"	Bega	Bega/2197
F, Pole Light and Pole	Manufacturers standard finish – Silver (SLV)	Bega	Pole Top Indirect Cutoff Optics-8309MH- Pole-916HR

**PART 3 EXECUTION**

**NOT USED**

**--- E N D OF SECTION---**

SCHEDULE FOR FINISHES

09 06 00 - 7