

RFP 36E77618R0017 TECHNICAL QUESTIONS AND VA RESPONSE TRACKING SHEET – GRAND ISLAND

ITEM NO.	DATE QUESTION RECEIVED	DATE QUESTION ANSWERED	QUESTION	GOVERNMENT RESPONSE
1.	11/30/2017	12/04/2017	Who is the Siemens Project Manager for Grand Island?	Angela Mulinix is the COR for the equipment contract. Chaz Williamson will be acting as the Technical Monitor for construction issues locally at the Grand Island site and Ron Rice will be acting as the Technical Monitor for the equipment issues locally at the Grand Island site.
2.	11/30/2017	12/14/2017	What are the normal working hours for contractors at Grand Island? Will nightwork be approved for the project?	Normal working hours are 7:00 a.m. – 5:30 p.m., M – F. Night and/or weekend work may be coordinated with the on-site technical representative (Chaz Williamson).
3.	11/30/2017	12/14/2017	What are the working hours of the clinic area where the project will take place?	Normal clinic hours are 7:00 a.m. – 4:30 p.m., M – F.
4.	11/30/2017	12/14/2017	Where is the laydown and staging areas for the site?	The contractor should make every effort to limit the amount of material and equipment needed to be stored on-site and, as much as possible, limit storage to the work area. Limited storage in the facility basement can be coordinated with the on-site technical representative.
5.	11/30/2017	12/14/2017	Is the work area noise sensitive?	Work will be conducted in a patient care area. In addition to strict dust and infectious control requirements for the work, work generating high noise levels and/or having the potential to transmit vibration through the facility structure shall be coordinate with the on-site technical representative and completed outside of clinic hours.
6.	11/30/2017	12/14/2017	Is there interstitial space?	No. There is a plenum between the acoustic ceiling and the deck above, with between 18” and 36” of clear space, depending on beam locations.

ITEM NO.	DATE QUESTION RECEIVED	DATE QUESTION ANSWERED	QUESTION	GOVERNMENT RESPONSE
7.	11/30/2017	12/04/2017	What is the lead time for the Siemens delivery of the equipment?	The turnaround time for Siemens is 6-8 weeks – but really the construction contractor will not be coordinating the delivery date with the vendor – the VA (Biomedical engineer rep from each site and Angela Mulinix) will be working with Siemens to secure the delivery date for the equipment once we have a confirmed construction schedule from the awarded contractor.
8.	11/30/2017	12/14/2017	How thick is the lead lining in the walls?	Lead shielding is 1/8” thick.
9.	11/30/2017	12/14/2017	Do the doors to the RF Room contain any sensors?	Yes, per construction drawings.
10.	11/30/2017	12/14/2017	Are contractors allowed to use the VA restrooms?	VA restrooms are available for contractor use, with the expectation that contractor employees will not soil the area.
11.	11/30/2017	12/14/2017	What parking is available on site?	Contractor employees shall use VA employee parking.
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				

23.				
-----	--	--	--	--

