

Statement of Work (12/18/2017)
Replace Flooring Bldg. 6 Project No: 623-17-004S

Statement & Scope of Work:

Contractor shall furnish all labor, equipment, materials and supervision to remove existing carpet square in building 6 and replace with new 16" X16" Solid Vinyl Tile (SVT) Cortina Grande—Johnsonite brand or equal. Contractor shall slide the new SVT under the existing wood base.

The area is approximately 1,740 SF, contractor to verify.

All work shall be performed and completed on weekends and in evenings. VA will temporary remove and relocate all furniture in the area before work start and will relocate back to its original location when the carpet replacement completed by the contractor. All work shall be completed as required per this Scope of Work and drawing.

Work shall be completed in 45 days from Notice to Proceed.

Contractor is to remove all carpet debris and demolition items completely off job site. All dimensions are approximate. Contractor shall verify all field dimensions and exact location.