



- SPECIAL NOTES**
1. MOUNT 48" AFF.
 2. 3P, 30A NFSS IN NEMA 1 ENCLOSURE.
 3. NOT USED.
 4. COMBINATION MOTOR STARTER NEMA SIZE 0 WITH 7A, 3P MCP RED AND GREEN LED INDICATOR ON 0 AND MANUAL CONTROL WITH THERMAL AND A.C. CONTROLS IN NEMA 1 ENCLOSURE.
 5. MOUNT EXPOSED ON WALL 8" AFF FOR SECURITY CAMERA.
 6. MOUNT EXPOSED ON COLUMN 7" AFF FOR SECURITY CAMERA.
 7. TO MAIN FIRE ALARM CONTROL PANEL VIA F.A.S.B. - PIC. SEE DWG. 1-E142.
 8. PROVIDE 3/4" C TO OPERATIONS ROOM #11100. STUB UP & ASME OPERATIONS ROOM CEILING ALID BUSH 2x12
 9. NOT USED.
 10. NOT USED.
 11. DUPLEX CONTROLLER. SEE MECHANICAL SPECIFICATION.
 12. SEE DWG. 1-E26 FOR CONTINUATION.
 13. SEE DWG. 1-E22 FOR CONTINUATION.
 14. WIRING AND CONDUIT SHALL BE RUN CONCEALED IN WALL. SEE SPECIFICATIONS AND DWG. 1-E142.

NOTE:

1. GROUND WIRES INDICATED FROM EACH SWITCHBOARD TO THE WALL MOUNTED GROUNDING BAR AND FROM SUBSTATION TO THE WALL MOUNTED GROUNDING BAR SHALL BE RUN IN 1" C. RUN CONDUIT MINIMUM OF 14" A.T.F.

AS BUILT
Revisions
6/24/94
Date

RECORD DRAWING
CORRECTED ON BASIS OF DATA
FURNISHED BY THE RESIDENT ENGINEER

NORTH

Key Plan

Seal

RTKL/CSD/HENRY ADAMS (LV)
ARCHITECTS AND ENGINEERS
400 E PRATT STREET
BALTIMORE, MARYLAND 21202

Project Title
324-BED REPLACEMENT HOSPITAL PHASE II

Drawing Title
1st PARKING FLOOR PLAN AREA C POWER & SIGNAL

Scale
1/8" = 1'-0"

Building Number
1

Location
VAMC - BALTIMORE, MD.

Project No.
511-001D

Date
9/1/89

DRAWING No.
1-E24

Dwg. 2 of 17

Veterans Administration

FULLY SPRINKLERED

FIRE ALARM SYSTEM ZONE CODE FOR DEVICES IN THIS QUADRANT SHALL BE 4-3-1

8-0-1-13B2

VA FORM 86-231 OCT 1978