



- SPECIAL NOTES
- 1 MOUNT 48" AFF.
 - 2 3P, 30A NESS IN NEMA 1 ENCLOSURE.
 - 3 NESS SHALL BE MOUNTED AT THE CEILING SPACE.
 - 4 NOT USED.
 - 5 COMBINATION MOTOR STARTER NEMA SIZE 1 WITH 30A NESS AND 30A MANUAL CONTROL LIGHT AND HORN. MANUAL CONTROL WITH TWO N.O. AND TWO N.C. CONTACTS IN NEMA 1 ENCLOSURE.
 - 6 MOUNT EXPOSED ON WALL 8" AFF FOR SECURITY CAMERA.
 - 7 MOUNT EXPOSED ON COLUMN 7" AFF FOR SECURITY CAMERA.
 - 8 MAKE CONNECTION TO BOOTH HEATER AND RECEPTACLE.
 - 9 1" CONDUIT CONTROL PANEL.
 - 10 TICKET PRINTER OR COIN RECEIVER.
 - 11 CARD UNIT.
 - 12 GATE OPERATOR.
 - 13 CONTROL PANEL.
 - 14 CO-MONITORING CONTROL UNIT BY MECH. SECTION.
 - 15 TO MAIN FIRE ALARM CONTROL PANEL VIA F.A.S.B. - FID. SEE DWG. 1-E142.
 - 16 CONTROLLER PROVIDED UNDER MECHANICAL DIVISION.
 - 17 3 #6 + #10 G.W. IN 1" C. TO 3P-70A CB.
 - 18 PROVIDE CONTROL WIRING IN 3/4" C. BETWEEN AC #1 AND CONDENSING UNIT #1.
 - 19 PROVIDE CONTROL WIRING IN 3/4" C. TO AC #2. SEE DWG. 1-E20.
 - 20 PROVIDE 3/4" C. TO OPERATIONS ROOM 1-E20. SUBSTATION CONTROLS AND BUS BAR. SEE DWG. 1-E26 FOR CONTINUATION.
 - 21 SEE DWG. 1-E20 FOR CONTINUATION.
 - 22 SEE DWG. 1-E24 FOR CONTINUATION.
 - 23 WIRING AND CONDUIT SHALL BE RUN CONCEALED IN WALL. SEE SPECIFICATIONS AND DWG. 1-E142.
 - 24 SEE DRAWING 1-E20 FOR CONTINUATION.
 - 25 PROVIDE 4-4" C. TO TELEPHONE EQUIPMENT.
 - 26 GROUND BAR SEE DETAIL 1-E123A

NOTE:
1. GROUND WIRES INDICATED FROM EACH SWITCHBOARD TO THE WALL MOUNTED GROUNDING BAR AND FROM SUBSTATION TO THE WALL MOUNTED GROUNDING BAR SHALL BE RUN IN 1" C. RUN CONDUIT MINIMUM OF 14" A.F.F.

FIRE ALARM SYSTEM ZONE CODE FOR DEVICES IN THIS QUADRANT SHALL BE 4-4-1

FULLY SPRINKLERED

8-O-1-1384

RECORD DRAWING CORRECTED ON BASIS OF DATA FURNISHED BY THE RESIDENT ENGINEER	RTKL/CSD/HENRY ADAMS (L) & ASSOCIATES ARCHITECTS AND ENGINEERS 100 E. FORT STREET BALTIMORE, MARYLAND 21202	Drawing Title 324 - BED REPLACEMENT HOSPITAL PHASE II	Date 9/1/88	Project No. 511-001D	Drawing No. 1-E26	Dwg. 28 of 77	Veterans Administration
Approved Project Director <i>Robert Miller</i>		Building Number 1	Location VAMC - BALTIMORE, MD.		H.A. 708 NO - V0022AO		
Key Plan		Scale 1/8" = 1'-0"	Checked		Date 6/24/94		