





- 1 ISOCENTER OF MAGNET. MAINTAIN LOCATION THROUGHOUT CONSTRUCTION.
- 2 EQUIPMENT SUPPLIED AND INSTALLED BY PHILIPS (NIC). SEE PHILIPS EQUIPMENT DRAWINGS FOR EQUIPMENT LIST.
- 3 NEW 24"x24" RAISED ACCESS FLOORING PANELS 12" HIGH. SUPPLY PERFORATED PANELS WHERE SHOWN AND GROMMET OPENINGS AS REQUIRED FOR EQUIPMENT.
- 4 NEW 24"x24" RAISED ACCESS FLOORING PANELS 12" HIGH. (NONFERROUS).
- 5 COPPER SHIELD AND R/F WINDOW, SUPPLIED AND INSTALLED BY RFSC.
- 6 PROVIDE END STUD WITH BACKER ROD AND CAULK TO FILL JOINT.
- 7 PROVIDE 1" EXPANSION JOINT. SEE DETAIL 1 ON SHEET A-6.
- 8 HOSPITAL GRADE, 4'-0" TALL, VINYL CORNER GUARD.
- 9 OAK, MINIMUM 4" WIDE CHAIR RAIL.
- 10 SEE ELEVATION C10 ON SHEET A-7 FOR DRESSING ROOM ELEVATIONS.
- 11 SEE ELEVATION 9 ON SHEET A-7 FOR RF COIL STORAGE CABINET ELEVATION.

PROJECT NAME:		MRI SUITE ADDITION VA IOWA CITY HEALTH CARE SYSTEM	
SHEET TITLE:		ARCHITECTURAL FLOOR AND EQUIPMENT PLAN	
DWG NO	A-1		
DATE			
PROJ NO	TW074833		
		6737 West Washington Street, Suite 3440 West Allis, Wisconsin 53214 (414)-291-8840 FAX 291-8841	
S:\Projects\1474833\DWG\A-1.dwg 1/14/2006 10:00 AM		6737 West Washington Street, Suite 3440 West Allis, Wisconsin 53214 (414)-291-8840 FAX 291-8841	
SITE LOCATION: 601 HIGHWAY 6 WEST IOWA CITY, IA 52246		DESIGNED BY: HFB/PJR	
PLANNING • ARCHITECTURAL/ENGINEERING DESIGN & DEVELOPMENT CONSTRUCTION MANAGEMENT • GENERAL CONTRACTING • BIDDING SERVICES FACILITY ENGINEERING • SYSTEM OPERATIONS • COMMISSIONING		DRAWN BY: WDS	
CHECKED BY: MAL		12/11/2007 3 9/6/2006 2 7/5/2006 1 6/26/2006	
APPROVED BY: MAL		RECORD DRAWINGS GENERAL REVISIONS APPENDUM #1 OWNER COMMENTS 100% CONSTRUCTION SET REVISION	
NO		DATE	
BY		APVD	