

SECTION 09 06 00
SCHEDULE FOR FINISHES

PART I - GENERAL

1.1 DESCRIPTION

This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

1.2 MANUFACTURERS

Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer for finish requirements.

1.3 SUBMITALS

Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES—provide quadruplicate samples for color approval of materials and finishes specified in this section.

1. COLOR SLIDES-INTERIOR VIEWS:

Room Number and Name	Item/View to be Photographed
1. Rendering: Site Plan View	
2. Rendering: Exterior View Looking North/East	
3. Rendering: View of East Vestibule	
4. Rendering: Director's Suite Third Floor	

BUILDING 1A SEISMIC CORRECTIONS
VA SIERRA NEVADA HEALTH CARE SYSTEM
RBB PROJECT #1013700

VA PROJECT #654-336
VA CONTRACT #VA 261-P-0888
SOLICITATION #: VA261-12-R-0544

BUILDING 1A SEISMIC CORRECTIONS
VA SIERRA NEVADA HEALTH CARE SYSTEM
RBB PROJECT #1013700

VA PROJECT #654-336
VA CONTRACT #VA 261-P-0888
SOLICITATION #: VA261-12-R-0544

BUILDING 1A SEISMIC CORRECTIONS
VA SIERRA NEVADA HEALTH CARE SYSTEM
RBB PROJECT #1013700

VA PROJECT #654-336
VA CONTRACT #VA 261-P-0888
SOLICITATION #: VA261-12-R-0544

1.4 APPLICABLE PUBLICATIONS

A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.

B. MASTER PAINTING INSTITUTE: (MPI)

2001.....Architectural Painting Specification Manual

PART 2- PRODUCTS

2.1 DIVISION 05 - METALS

A. SECTION 05 05 00, ADHESIVE AND MECHANICAL FASTENERS

Item:	Manufacturer:	Product:
Adhesives for use in Concrete	Hilti	HIT RE-500-SD (ICC ESR 2322)
	Simpson Strong-Tie	SET-XP (ICC ESR 2508)
Adhesives for use in Masonry	Hilti	HY 150 MAX (ICC ESR 1967)
	Simpson Strong-Tie	Epoxy-Tie SET (ICC ESR 1772)
Mechanical Wedge Anchors in Concrete	Hilti	Kwik Bolt TZ (KB-TZ) (ICC ESR 1917)
	Simpson Strong-Tie	Strong-Bolt (ICC ESR 1771)
Mechanical Wedge Anchors in Masonry	Hilti	Kwik Bolt 3 (KB-3) (ICC ESR 1385)
	Simpson Strong-Tie	Wedge-All (ICC ESR 1396)

B. SECTION 05 36 00, COMPOSITE METAL DECKING

Manufacturer:
Verco Manufacturing, Co.
ASC Profiles
Deck West, Co.

Note: Deck and shear resistant angle manufacturer to be the same.

C. SECTION 05 40 00, COLD-FORMED METAL FRAMING

METAL FRAMING, CONNECTORS, AND ACCESSORIES:
Manufacturer:
Dietrich Metal Framing
The Steel Network, Inc.
Cemco
Simpson Strong-Tie

SELF-DRILLING, SELF-TAPPING SCREWS, BOLTS, NUTS AND WASHERS:	
Manufacturer:	Product:
Grabber Construction Products	Grabber
ITW Buildex	TEKS
Compass International	DARTS

D. SECTION 05 52 13, PIPE AND TUBE RAILINGS, SECTION 05 73 16, DECORATIVE METAL RAILING

LEGEND	Location	Manufacturer:	Size / Finish
HR-01	Exterior Ramps		1 ½" dia. Satin, Brushed, Stainless Steel
HR-02	At South Stair Bridge	Match Existing	Match Existing, Paint to match
HR-03	At Patio	Wagner Industries	1 ½" dia. Satin, Brushed, Stainless Steel
HR-04	At Spiral Stairs	(Spiral stairs) - Per Stair Manuf. Assembly to be	Handrails to be 1 ½" dia.

		complete with handrails, railings and extended platforms and landings	Painted steel
HR-05	At Stairs to Penthouse	Match Existing	Match Existing, Paint to match
HR-06	At North Stairs - Handrail	Diamond Perforated Metal Co.	1" I.D. (1.315" O.D.) Extra Strong Steel Pipe Brushed Stainless Steel
GR-01	At North Stairs - Guardrail	Diamond Perforated Metal Co.	NO. 625-875 SQ Brushed Stainless Steel

2.2 DIVISION 07 - THERMAL AND MOISTURE PROTECTION

A. SECTION 07 13 52, MODIFIED BITUMINOUS SHEET WATERPOOFING; 07 46 16 COLD FLUID APPLIED WATERPROOFING

Type	Location	Manufacturer	Mfg. Product Name/No.
	Vertical and horizontal at face of wall at patio w/protection course	W.R. GRACE	Bituminous W.P. Membrane
	Above slab at Patio below geocomposite- drainage sheet below self-leveling pavers	W.R. GRACE	Procur
	Below slab and footings	W.R. GRACE	Preprufe 300r

B. SECTION 07 18 13, PEDESTRIAN TRAFFIC COATING

Type	Location	Manufacturer	Mfg. Color Name/No.
Pedestrian Traffic Coating	Existing exterior concrete steps over basement	Dex-o-tex	Weatherwear color #3301 Olivewood

C. SECTION 07 40 00, SIDING PANELS

Type	Shape	Ext. Finish	Int. Finish	Manufacturer	Mfg. Color Name/No.
Composite Metal Panels	Horizontal Bands	Kynar Finish	Not applicable	Elward System	Kynar - Duranar XL Coating UC51568XL Champagne Gold

D. SECTION 07 42 13, WALL PANELS

Type	Shape	Ext. Finish	Int. Finish	Manufacturer	Mfg. Color Name/No.
Existing metal panels	Linear Bands	Match existing	Not applicable	Match Existing	Match Existing

E. SECTION 07 57 13, SPRAYED POLYURETHANE FOAM ROOFING

Coating Material	Color	Manufacturer	Mfg. Color Name/No.
Match Existing	Match Existing		Match Existing
Silicone Rubber Elastomeric Protective Coating 2-coat			
Ceramic Granules			

F. SECTION 07 60 00, FLASHING AND SHEET METAL

Item	Material	Finish
Copings	Aluminum	Match existing
	Galvanized	
Hanging Gutters and Downspouts	Aluminum	Match Kynar - Duranar XL Coating UC51568XL Champagne Gold at the Entry Vestibule
	Galvanized	
Roof Insulated Expansion Joint Covers	Vinyl sheet	Match existing as occurs at concrete to concrete joints/Match

		adjacent finish color of metal panels where occurs
Scuppers	Concrete	Match Arch Finished Conc.
Overflow	Cow Tongue - Overflow termination escutcheon	Nickel Bronze Finish

G. SECTION 07 71 00 / 07 72 00, ROOF SPECIALITIES AND ACCESSORIES

Item	Material	Finish	Manufacturer	Manufacturer/Color Name/Number.
Roof Hatch	Aluminum	Mill		N/A
Equipment Support	Galv. Steel	Paint		
Gravity Ventilators	Aluminum	Mill		
Grating Walkway	Galv Steel			
Copings	Extruded Aluminum			
Gravel Stops and Fascia System	Extruded Aluminum			
Fascia Systems	Extruded Aluminum			
Roof Expansion Joint Covers	Extruded Aluminum	Mill		

H. SECTION 07 76 16 PRECAST CONCRETE PAVERS

Item	Material	Finish	Manufacturer	Manufacturer/Color Name/Number.
PCPT-01	Precast Concrete Paver Tile	Precast Concrete	Wausau Tile, Inc.	Uniface, TRV 7008 23 13/16" x 23 13/16" x2"
PCPT-02	Precast Concrete	Precast Concrete	Wausau Tile, Inc.	Uniface, TRV 7008

	Paver Tile			Custom size for patio border tile
PCPT-03	Precast Concrete Paver Tile	Precast Concrete	Wausau Tile, Inc.	Uniface, TRV 7008 Custom size for existing condition at sill adj. to patio

I. SECTION 07 87 00, SMOKE CONTAINMENT SYSTEM

Item	Location	Manufacturer	Mfg. Color Name/No.
Smoke Screen	Elevator Lobby	Smoke Guard	Smoke Guard M600

J. SECTION 07 92 00, JOINT SEALANTS

Location	Color	Manufacturer	Manufacturer Color
Masonry Expansion Joints	Match Existing		
CMU Control Joints	Match Existing		
Precast Concrete Panels	Match Existing, Paint to match wall		
New to Existing Walls	Paint to match existing U.O.N.		
Building Expansion Joints	Match Existing		
Masonry Sealed Joints	Match Existing		
Stone Sealed Joints	Grey		

K. SECTION 07 95 13, EXPANSION JOINT COVER ASSEMBLIES

	Material	Finish	Manufacturer	Mfg. Color Name/No.
--	----------	--------	--------------	---------------------

Floor Component Cover Plate Frame Casket or Sealant (interior only)			Construction Specialties	Construction Specialties Model GFST w/2" RFX-2F at rated floor (seismic joint varies at Bridge to South Stair and at Vestibule Entry, adjust size accordingly)
Wall Component Cover Plate Frame Casket or Sealant (interior only)			Construction Specialties	Construction Specialties Model FWF 200 2" (seismic joint varies at Bridge to South Stair and at Vestibule Entry, adjust size accordingly)
Ceiling Component Cover Plate, Gasket or Sealant (interior only)	Match Existing	Match Existing	Construction Specialties	Construction Specialties Model FWF 200 2" (seismic joint varies at Bridge to South Stair and at Vestibule Entry, adjust size accordingly)
Exterior Wall Cover Plate Frame Thermoplastic Joint	Match Existing	Match Existing	Construction Specialties	
Garage Floor Steel			Construction Specialties	

2.3 DIVISION 08 - OPENINGS

A. SECTION 08 11 13, HOLLOW METAL DOORS AND FRAMES

Paint both sides of door and frames same color including ferrous metal louvers, and hardware attached to door	
Component	Color of Paint Type and Gloss
Door	Paint to match adjacent wall
Frame	Paint to match adjacent wall
Window frame	N/A

B. SECTION 08 14 00, WOOD DOORS

Component	Finish/Color
Doors	Quartersawn sliced white maple wood veneer with clear satin finish
Frames	Hollow Metal Door Frames painted to match adjacent wall paint color

C. SECTION 08 31 13, ACCESS DOORS AND FRAMES

Material	Finish/Color
Steel	Paint to match adjacent finish

D. SECTION 08 33 13, COILING COUNTER DOORS

Location	Material	Finish	Manufacturer	Manufacturer Color Name/No.
Rooms D1444, D2446, D3453	Stainless Steel/Steel	Stainless Steel	Cookson Door Mfg.	Stainless Steel #4, Type CD10-2M Motor Operated Counter Door, Phantom

				feather edge
--	--	--	--	--------------

E. SECTION 08 41 13, ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

Material	Finish	Manufacturer / Model	Manufacturer Color Name/No.
Aluminum Storefront Mullion System	70% Kynar - Duranar XL	OldCastleBe Series 6000 Multiplane	Kynar - Duranar XL Coating UC51568XL Champagne Gold
Aluminum Entry Doors	70% Kynar - Duranar XL	Old Castle / Alum swing MS 375 doors w/ 1" glass	Kynar - Duranar XL Coating UC51568XL Champagne Gold
Aluminum Top and Bottom Rail	70% Kynar - Duranar XL	CR Laurence Co. Inc. SR10SSA12240	Kynar - Duranar XL Coating UC51568XL Champagne Gold
HARDWARE - CRL brushed stainless 12" glass mounted curved pull handles	Brushed Stainless	CR Laurence Co. Inc. CC12X12BS	Brushed Stainless

F. SECTION 08 42 29, SLIDING AUTOMATIC ENTRANCES

Material	Finish	Manufacturer / Model	Manufacturer Color Name/No.
Aluminum	70% Kynar - Duranar XL	Horton O-SX 2000 TYPE 110 Single slider, breakaway, surface mounted	Kynar - Duranar XL Coating UC51568XL Champagne Gold
Aluminum	70% Kynar - Duranar XL	Horton / O-SX P 2000 TYPE 110 Single slider /fixed panel, breakaway, between jamb mounted	Kynar - Duranar XL Coating UC51568XL Champagne Gold

G. SECTION 08 51 13, ALUMINUM WINDOWS

Type	Finish	Glazing	Manufacturer	Mfg. Color Name/No.
Double Fixed	70% Kynar - Duranar XL	Clear/Spandrel/Translucent	OldcastleBE (Winco/Waussau)	Model: Singature Series PL Color: Kynar - Duranar XL Coating UC51568XL Champagne Gold
Fixed	70% Kynar - Duranar XL	Clear/Spandrel/Translucent	OldCastleBE (Winco/Waussau)	Model: Singature Series PL Color: Kynar - Duranar XL Coating UC51568XL Champagne Gold

H. SECTION 08 71 00, BUILDERS HARDWARE

Item	Material	Finish
Hinges	Steel and stainless steel	652 & 630
Door Closers	Cast Iron	652
Floor Closers	Steel	626
Floor Pivot Sets	Bronze	626
Closer/ Holder	Cast Iron	652
Floor Stops	Wrought steel	626
Door Holders	Steel	626
Lock/ Latches	Bronze	626
Key Cabinet	Steel	
Armor Plates	Stainless steel	630
Kick Mop Plates	Stainless steel	630
Door Edging	Stainless steel	630
Exit Device	Aluminum	628

Flush Bolts	Steel	626
Door Pulls	Stainless steel	630
Push Plates	Stainless steel	630
Combination Push Pull Plate	Stainless steel	630
Coordinators	Steel	600
Light Proof Seals	Aluminum with silicone	AL
Weather Strip	Silicone	
Threshold	Aluminum	AL

I. SECTION 08 80 00, GLAZING

Glazing Type	Manufacturer	Mfg. Color Name/No.
GL-1		Vision Glass - 1/4" Clear, Tempered
GL-2	Not Used	Not Used
GL-3	Fire Lite	Vision panel - FireLite Plus Premium Grade, Clear - 90 Min Fire Rating -
GL-4	OldcastleBE /Stackwall System	Full Ht. Glass, 1/2" Clear Tempered
GL-5	Fire Lite	120 Min Fire rated FireLite Pyrostop Premium Grade, Clear
GL-6	Horton	Clear vision Glass at sliding door - 3/4" Laminated & Tempered
GL-7	Not Used	Not Used
GL-8	Custom Glass Medallion Pulp Studios Debbie Salmon (310) 864-4303	CUSTOM clear tempered glass, low iron 3/4" thick Microfrosted and etched 1/16" to 1/8" VA logo on backside for frosted visual effect; Holes for standoffs 36" diameter, polished edge

Glass Medallion Standoffs	Standoff Systems, Todd McMillan (775) 829-7272	(6) SO-1 1-1/4"d. x 1"long barrel. Tap 5/16-18 all thru. Clear Anodize Aluminum. (6) SO-CAP3 1-1/4"d. x 1/2"deep cap. Internal tap.5/16-18. Clear Anodize Aluminum (6) HD-S23 5/16-18 x 1-3/4" cup point socket set screw : s.s. (6) HD-WHS4 5/16-18 x 2-1/2" overall wood mount hangar screw. Machine Thread length 1". Zinc Plated (6) HD-WHSD1 Wood Hanger Screw-Stud Driver for 10-24 thread
Glass Medallion Image	Artwork CAD File to be formatted by Glass Manufacturer	VA Logo CAD file to be provided by RBB Architects, Inc.
GL-9	Guardian Industries	DBL Layer Pilkington 3/4" Clear, Heat Strengthened, Tempered and Laminated Structural Glazing
VG-1	Guardian Industries	Guardian SunGuard SN 54 - Vision Glass - 1" Insulated
VG-2	Guardian Industries	Guardian SunGuard SN 54 - Vision Glass - 1" Insulated
VG-3	Guardian Industries	Guardian SunGuard SN 54 - Vision Glass - 1" Insulated / Tempered
VG-4	Guardian Industries	Guardian SunGuard SN 54 - Vision Glass - 1" Tempered
VG-5	Guardian Industries	Guardian SunGuard SN 54 - Vision Glass - 1" Tempered
SG-1	Guardian Industries	Guardian SunGuard SN 54 on #2 surface; Clear w/ICD OPACI-Coat Warm

		Gray 3-0070 #4 surface - 1" Insulated
TG-1	Guardian Industries	Guardian SunGuard SN 54 on #2 surface; Guardian Satin Deco (Translucent Acid Etched Glass) w/ Acid Etch on #3 surface - 1" Insulated

2.4 DIVISION 09 - FINISHES

A. SECTION 09 30 13, CERAMIC TILING

1. CERAMIC MOSAIC TILE (FT)					
Code	Color		Pattern	Manufacturer	Mfg. Color Name/No.
MT-01	Burlywood Pearl		HP Mini Brick	Tile Emporium Inc. (800) 393-0499, Charles Zohoury	Spacers: Rubber Thinset: Versabond Grout: Polyblend sanded Joint: 1/8" Mounting: Paperface; buttermount to make flush with adjacent tiles
Grout				Custom Building Products	#10 Antique White Polyblend Sanded w/MT-01

2. SECTION 09 30 13, CERAMIC TILING		
Finish Code	Manufacturer	Mfg. Color Name/No
PT-01	Caesar, distributed by Spec Ceramics, Will Stapp-714-231-4798	Style: Emotions, Warm Beige, 12"x 24"x 3/8"
PT-02	Caesar, distributed by Spec Ceramics, Will Stapp-714-231-4798	Style: Emotions, Sandy White, 12"x 24"x 3/8"
PT-03	Not Used	Not Used

PT-04	Caesar, distributed by Spec Ceramics, Will Stapp- 714-231-4798	Style: Emotions, Deep Brown, 12"x 24"x 3/8"
PTB-01	Caesar, distributed by Spec Ceramics, Will Stapp- 714-231-4798	Style: Emotions, Warm Beige CUSTOM bullnose, 6"x 24"
Grout	Mapei	02 Pewter w/PT-01, PT-02 and PT-03 09 Gray w/PT-04
Transition to Carpet	Schluter	SCHIENE AE100
Transition to Elevator Cab	Schluter	Reno-Ramp; Setting material to bond with metal
Transition to Tile (toilets)	Schluter	SCHIENE (Model # TBD on the field)
Transition to Resilient Flooring	4"W	Johnsonite (Model #TBD in the field Color: Fawn)

B. SECTION 09 51 13, ACOUSTICAL CEILINGS

Finish Code	Component	Color Pattern	Manufacturer	Mfg Name/No.
	Exposed Suspension System	- - -	Armstrong	Prelude XL, 15/16" Exposed Tee
ACT-01	Type III	White	Armstrong	Cirrus # 572 15/16" Angled Tegular

C. SECTION 09 65 19, RESILIENT TILE FLOORING

Finish Code	Size	Material/Component	Manufacturer	Mfg Name/No.
VT-01	18" x 18"	VT	Amtico	Amtico / Fiber Gold, FB77, beveled, 2.5mm thick

VT-02	18" x 18"	VT	Shaw Floors, LG Hausys	Shaw Floors /0011V Decostone, 05926
Transition to Carpet	See CPT			
Transition to Concrete	1/8" Material to Subfloor			Refer to door schedule

D. SECTION 09 65 13, RESILIENT BASE STAIR TREADS AND ACCESSORIES

Finish Code	Item	Size	Manufacturer	Mfg Name/No.
RB-01	Rubber Base (RB)	6" High	Johnsonite	Johnsonite; Millwork Reveal 6", MM-XX-F6, Color:Fawn
RB-02	Rubber Base (RB)	6" High	Johnsonite	Johnsonite; Recess Wallbase, RWDC-XX, Color: Fawn
RST-01	Resilient Stair Treads (RST) VIHT-29-SQ	V.I.F. Top stair landing & bottom stair only	Johnsonite	Johnsonite; Safe-T- Rib square Nose / Visually Impaired (VIHT) - Color 29 Moon Rock WG; CUSTOM SIZE, FIELD VERIFY TREAD DEPTH
RST-01	Visually Impaired Strip	2" Wide	Johnsonite	Johnsonite; CO- EXTRUDED VINYL INSERT 40 BLACK
RST-01	Resilient Stair Treads (RST) HT-29-SQ	V.I.F. All stairs except top landing & bottom stair	Johnsonite	Johnsonite; Safe-T- Rib Square Nose - Color 29 Moon Rock WG; CUSTOM SIZE, FIELD VERIFY TREAD DEPTH
RST-01	Resilient Stair Risers (RST)	V.I.F.	Johnsonite	Johnsonite; Color 29 Moon Rock WG; CUSTOM SIZE, FIELD VERIFY

				RISER HEIGHT

E. SECTION 09 68 00, CARPET MODULES (CPT)

Finish Code	Size	Pattern direction	Manufacturer	Mfg. Color Name/No.
CPT-01	6' x 2'	See installation instructions	Tandus, Style: Meristem 03310 Powerbond RS Vinyl Cushion	13206 Shagbark
CPT-02	6' x 2'	See installation instructions	Tandus, Style: Meristem 03310 Powerbond RS Vinyl Cushion	13209 Applewood
Transition to Resilient Flooring	4"W; 1/4" material to 1/8" material		Johnsonite	CTA-XX-HL, Color: Fawn
Transition to Concrete	4"W; 1/4" material to subfloor		Johnsonite	CTA-XX-JL, Color: Fawn

F. SECTION 09 91 00, PAINT AND COATINGS

1. MPI Gloss and Sheen Standards

		Gloss @60	Sheen @85
Gloss Level 1	a traditional matte finish-flat	max 5 units, and	max 10 units
Gloss Level 2	a high side sheen flat-"a velvet-like" finish	max 10 units, and	10-35 units
Gloss Level 3	a traditional "egg-shell like" finish	10-25 units, and	10-35 units
Gloss Level 4	a "satin-like" finish	20-35 units, and	min. 35 units
Gloss Level 5	a traditional semi-gloss	35-70 units	
Gloss Level 6	a traditional gloss	70-85 units	

Gloss level 7 a high gloss

more than 85 units

2. Paint Code	Gloss	Manufacturer	Mfg. Color Name/No.
INTERIOR PAINT			
PTE-01	Eggshell Level 3	Kelly-Moore	Country Cotton, OW2024-1
PTE-02	Eggshell Level 3	Kelly-Moore	Snip of Tannin, 41
PTE-03	Eggshell Level 3	Kelly-Moore	Zanzibar, KM3932-2
PTE-04	Eggshell Level 3	Kelly-Moore	Song of Nature, KM3892-2
PTE-05	Eggshell Level 3	Kelly-Moore	Vintage Find, KM3890-1
PTE-06	Eggshell Level 3	Kelly-Moore	Bravado, 160
PTE-07	Eggshell Level 3	Kelly-Moore	Melon Sorbet, KM3596-1
PTE-08	Eggshell Level 3	Kelly-Moore	Federalist, KM3806-2
Door Frames	Semi-Gloss Level 5	Kelly-Moore	Door frames to match adjacent wall paint color
PTS-01	Semi-gloss Level 5	Kelly-Moore	Country Cotton, OW204-1
PTS-02	Semi-gloss Level 5	Kelly-Moore	Grey Matters, KM3829-2
EXTERIOR PAINT			
PT-11	Matte Level 2	Kelly-Moore	Custom Field Color to Match Existing, Refer to elevations for locations
PT-12	Matte Level 2	Kelly-Moore	Custom Accent Color to Match Existing, Refer to elevations for locations
PT-13	Matte Level 2	Kelly-Moore	Custom Accent Color to Match Existing, Refer to elevations for locations
PT-14	High Gloss Level 7	Kelly-Moore	Custom Color to match PT-12,

			Finish - High Gloss

G. SECTION 10 21 13, TOILET PARTITIONS

Finish Code	Manufacturer	Mfg. Color Name/No.
	Thrislington Cubicles	K32 Icon Leisure Phenolic Finish: F5278 Matte 58, Dogbone Earth

H. SECTION 10 26 00, WALL GUARDS AND CORNER GUARDS

Item	Material	Manufacturer	Mfg. Color Name/No.
High Impact Wall Covering, HIC-01	Rigid Vinyl Sheet	InPro Corporation	Elements 5Z112 peblette, 3' x 8', .40" thick Install horizontally to minimize vertical seams. Butt joint at all vertical seams and inside corner seams.
Corner Guards, CG-01	Textured Tape On	InPro Corporation	To match wall guard 11248, 535 Heavy-duty adhesive.
Chair Rail, CHR-01	Natural Maple	C/S Acrovyn	FRW-260

I. SECTION 10 13 00 / 10 14 00, EXTERIOR SIGNS

BUILDING 1A SEISMIC CORRECTIONS
 VA SIERRA NEVADA HEALTH CARE SYSTEM
 RBB PROJECT #1013700

VA PROJECT #654-336
 VA CONTRACT #VA 261-P-0888

Component	Finish	Manufacturer	Mfg. Color Name/No.
VA Medallion	Bronze		

J. SECTION 10 13 00 / 10 14 00, INTERIOR SIGNS

Sign Type	Component	Manufacturer	Mfg. Color Name/No.

K. SECTION 10 44 13, FIRE EXTNGUISHER CABINETS

Component	Material	Finish
Fully recessed mounted FEC w/5/16" flat trim	"Vertical DUO" - Stainless Steel #4 clear acrylic door	Stainless Steel #4, Larsen Mfg., with Larsen LOC, size for both 4A 60 BC and 2A10 BC Extinguishers

L. SECTION 10 28 00, TOILET, BATH, AND LAUNDRY ACCESSORIES

Item	Material	Manufacturer	Mfg. Color Name/No.
36"x1¼" Horizontal Grab Bar	Stainless Steel	Bobrick	Bobrick B-5806x36
42"x1¼" Horizontal Grab Bar	Stainless Steel	Bobrick	Bobrick B-5806x42
Toilet Tissue Dispenser	Plastic	San Jamar Ocean	Twin 9, Translucent Black Pearl, 094-R4090TBK
Toilet Mounted Seat Cover Dispenser	Steel	Georgia Pacific	SAFE-T-GARD ¼ Fold by Georgia Pacific, Model 57726-00 white
Fold Down Shelf	Stainless Steel	Bobrick	B-287, Folding Utility Shelf,

			Type 304 stainless steel satin finish
Coat Hook w/Bumper	Stainless Steel	Thrislington Cubicles	Thrislington Cubicles, per manufacturer
Round closet rod		Hafele	Hafele Synergy Elite Wardrobe Rail
Mirror	Brushed Nickel	Minka Lavery, distributed by CSN Mirrors	1430-84- Paradox Mirror, 33"H x 24"W x 1.5"D
Shelf by Mirror	Stainless Steel	Bobrick	B-296 6" x 18", 304 stainless steel satin finish
Soap dispenser	Plastic	Metrex	Metrex dispenser MRX-10-1399; 80 ml deluxe
Paper Towel Dispenser	Plastic	Kimberly-Clark	Kimberly-Clark 09746-20
Shelf w/mop rack	Stainless Steel	Bobrick	Bobrick B-239 shelf w/mop and broom holders and hooks 18 gauge S.S. Type 304 34"Lx13"Hx8"C

2.6 DIVISION 12- FURNISHINGS

A. SECTION 12 21 13, HORIZONTAL BLINDS (DEDUCTIVE ALTERNATE)

Item/ Type	Finish	Manufacturer	Mfg. Color Name/No.
Horizontal Blinds	065 Brushed Aluminum	Hunter Douglas	CE81, Perforated Slat, 1"

B. SECTION 12 32 00, WOOD CASEWORK

Item Type	Location	Finish/Color
SSM-03, Solid Surface	Reception Countertop	Corian, Tumbleweed, Satin/Matte, 1/2"
SSM-05, Solid Surface	Reception Transaction Top,	Style: Studio Collection

	Avonite, Lisa Meenan (310) 372-0644	Color: Antique Glass, K3-8455 Thickness: 1/2" Backpaint white, Seam blocks
WV-01	Casework	Quartersawn sliced white maple with clear satin finish, Match: Book, Room: Blueprint

C. SECTION 12 36 61, COUNTERTOPS AND ACCESSORIES

Type	Finish/Color
Solid Surface toilet countertop with integral sink 816 and 4" backsplash & sidesplash, eased edge	SSM-01 Corian Countertop Ecru, Satin/Matte; SSM-02 Corian Sink Bowl Glacier White, Satin/Matte
Solid Surface kitchen countertop with 4" backsplash, eased edge, stainless steel sink (see equipment)	SSM-04 Corian countertop, Cottage Lane, Satin/Matte

D. SECTION 12 48 16, ENTRANCE FLOOR GRILLES

Component	Material	Manufacturer	Mfg. Color Name/No.
EFG-01, Entrance Floor Grille	Stainless steel with aluminum pan	C/S	Floorometry 101, standard pattern

2.7 DIVISION 14 - CONVEYING EQUIPMENT

A. SECTION 14 24 00, HYDRAULIC ELEVATORS

Item/ Type	Finish	Manufacturer	Mfg. Color Name/No.
Door Frame	Stainless Steel	TBD	Match Elevator Door Finish, frame must meet requirements as an auxiliary rail for the

			elevator smoke screen
--	--	--	-----------------------

2.8 DIVISION 22 - PLUMBING

A. SECTION 22 40 00, PLUMBING FIXTURES AND TRIM

Item	Color
Water Closet	White
Urinal	White
Lavatories	White
Service Sink Corner	Stainless Steel
Pantry Sink	Stainless Steel
Drinking Fountain	Stainless Steel

2.9 DIVISION 26 - ELECTRICAL

A. SECTION 26 51 00, BUILDING LIGHTING INTERIOR

Fixture Type	Exterior Finish	Color
F1,F2,F3,F4,F5,F6,F8,F9,F10,F11	WHITE PAINT ON EXPOSED TRIM	WHITE
F7,F12	CLEAR ALZAK MATTE DIFFUSE TRIM	CLEAR ALZAK
X1,X2,X3	BRUSHED ALUM. FACEPLATE-MATTE BLACK TRIM	BRUSHED ALUM. FACEPLATE-MATTE BLACK TRIM

B. SECTION 26 56 00, SITE LIGHTING

Type and Component	Exterior Finish	Manufacturer	Mfg. Name/No.
L2,L3,L4,L5,L6	BRONZE	BETALED	SEE FIXTURE SCHEDULE SHEET E002
L1, L7	CLEAR ALZAK MATTE DIFFUSE	GOTHAM	SEE FIXTURE SCHEDULE SHEET

BUILDING 1A SEISMIC CORRECTIONS
VA SIERRA NEVADA HEALTH CARE SYSTEM
RBB PROJECT #1013700

VA PROJECT #654-336
VA CONTRACT #VA 261-P-0888

	TRIM		E002
--	------	--	------

PART III EXECUTION

3.1 FINISH SCHEDULES & MISCELLANEOUS ABBREVIATIONS

FINISH SCHEDULE & MISCELLANEOUS ABBREVIATIONS	
Term	Abbreviation
Access Flooring	AF
Accordion Folding Partition	AFP
Acoustical Ceiling	ACT
Acoustical Ceiling, Special Faced	AT (SP)
Acoustical Metal Pan Ceiling	AMP
Acoustical Wall Panel	AWP
Acoustical Wall Treatment	AWT
Acoustical Wallcovering	AWF
Anodized Aluminum Colored	AAC
Anodized Aluminum Natural Finish	AA
Baked On Enamel	BE
Brick Face	BR
Brick Flooring	BF
Brick Paving	BP
Carpet	CP
Carpet Athletic Flooring	CAF
Carpet Module Tile	CPT
Ceramic Glazed Facing Brick	CGFB
Ceramic Mosaic Tile	FTCT
Chair Rail	CHR
Concrete	C
Concrete Masonry Unit	CMU
Corner Guard	CG
Divider Strips Marble	DS MB

Entrance Floor Grille	EFG
Epoxy Coating	EC
Epoxy Resin Flooring	ERF
Existing	E
Exposed Divider Strips	EXP
Exterior	EXT
Exterior Finish System	EFS
Exterior Paint	EXT-P
Exterior Stain	EXT-ST
Fabric Wallcovering	WF
Facing Tile	SCT
Feature Strips	FS
Floor Mats & Frames	FM
Floor Tile, Mosaic	FT
Fluorocarbon	FC
Folding Panel Partition	FP
Foot Grille	FG
Glass	GL
Glass Masonry Unit	GUMU
Glazed Face CMU	GCMU
Glazed Structural Facing Tile	SFTU
Granite	GT
Guard Rail	GR
Gypsum Wallboard	GWB
Hand Rail	HR
High Glazed Coating	SC
Latex Mastic Flooring	LM
Linear Metal Ceiling	LMC
Linear Wood Ceiling	LWC
Marble	MB
Material	MAT
Mortar	M
Mosaic Tile	MT
Multi-Color Coating	MC
Natural Finish	NF
Paint	P
Paint Eggshell	PTE

Paint Semi-gloss	PTS
Paver Tile	PVT
Perforated Metal Facing (Tile or Panels)	PMF
Plaster	PL
Plaster High Strength	HSPL
Plaster Keene Cement	KC
Plastic Laminate	HPDL
Polypropylene Fabric Wallcovering	PFW
Porcelain Paver Tile	PPT
Porcelain Tile	PT
Porcelain Tile Base	PTB
Precast Concrete Paver Tile	PCPT
Quarry Tile	QT
Radiant Ceiling Panel System	RCP
Resilient Stair Tread	RST
Rubber Base	RB
Rubber Tile Flooring	RT
Solid Surface Material	SSM
Spandrel Glass	SLG
Stain	ST
Stone Flooring	SF
Structural Clay	SC

Suspension Decorative Grids	SDG
Terrazzo Portland Cement	PCT
Terrazzo Tile	TT
Terrazzo, Thin Set	
Textured Gypsum Ceiling Panel	TGC
Textured Metal Ceiling Panel	TMC
Thin set Terrazzo	TST
Top Cap	TC
Veneer Plaster	VP
Vinyl Base	VTB
Vinyl Coated Fabric Wallcovering	W
Vinyl Composition Tile	VCT
Vinyl Sheet Flooring	VSF
Vinyl Sheet Flooring (Welded Seams)	WSF
Vinyl Tile	VT
Wall Border	WB
Wood	WD
Wood Veneer	WV

3.2 ROOM FINISH SCHEDULE

A. Refer to Drawings.

--- E N D ---