



Legend

GRADING	
---	ROAD CENTERLINE
100+00	ROAD CENTERLINE STATIONING
[Hatched]	FULL-DEPTH ASPHALT PAVEMENT
[Dotted]	PARTIAL-DEPTH ASPHALT PAVEMENT
[Grid]	HEAVY DUTY CONCRETE PAVEMENT
[Pattern]	CONCRETE SIDEWALK
[Line]	SAWCUT
[Line]	MOUNTABLE CURB & GUTTER
[Line]	DEPRESSED CURB & GUTTER
[Line]	PARKING STRIPING
[Line]	SOIL BORING / PAVEMENT CORING
[Line]	SITE WALL
[Circle]	FLOWER WATERING STATION
[Square]	TRASH RECEPTACLE
[Dot]	BOLLARD
[Triangle]	SIGN
[Line]	EXISTING BURIALS
[Line]	EXISTING PROPERTY FENCE
[Line]	EXISTING TREE LINE
[Circle]	EXISTING TREE - CONIFEROUS

- GENERAL NOTES:**
- SURVEY BACKGROUND OBTAINED FROM SURVEY DATED SEPTEMBER 27, 2011 PREPARED BY SMITHGROUPJJR AND SIGNED BY JOHN K. PIATT, RLS FOR MEMPHIS NATIONAL CEMETERY. BELOW GROUND RECORD UTILITY INFORMATION WAS PROVIDED BY THE VA AND WAS NOT SURVEYED BY SMITHGROUPJJR. AS SUCH SMITHGROUPJJR MAKES NO GUARANTEE NOR ASSUMES ANY LIABILITY AS TO THE COMPLETENESS AND/OR ACCURACY OF THE BELOW GROUND UTILITY INFORMATION AS RECORD DRAWINGS WERE SUPPLIED BY THE GOVERNMENT FOR USE AS THE UTILITY SURVEY BASE. UTILITIES WITHIN OPERATIONS YARD ARE BASED ON SMITHGROUPJJR PLANS, DATED MAY 31, 2013.
 - THE LAYOUT OF FACILITIES SHOWN ON THIS DRAWING ARE BASED ON THE HORIZONTAL AND VERTICAL CONTROL SYSTEM DESCRIBED ON THE SURVEY DRAWING. SURVEY PROVIDED BY SMITHGROUPJJR, SEPTEMBER 27, 2011.
 - SITE COORDINATES ARE SHOWN FOR CONSTRUCTION BASELINES AND KEY FEATURES ONLY. AN ELECTRONIC COPY OF AN AUTOCAD 2010 DRAWING FILE WILL BE PROVIDED FOR LAYOUT OF PROPOSED FACILITIES DESIGNED BY SMITHGROUPJJR AND SHOULD BE USED ONLY FOR THOSE FACILITIES. NO GUARANTEE IS MADE BY SMITHGROUPJJR FOR THE ACCURACY OF WORK PROVIDED BY OTHERS.
 - SEE SITE SURVEY DRAWINGS FOR LEGEND OF EXISTING FEATURES.
 - BEFORE ANY EXCAVATION ON THE SITE, CONTACT TENNESSEE ONE-CALL SYSTEM, INC. (PHONE 800-351-1111; ALTERNATE: 615-366-1870) TO LOCATE ANY EXISTING UTILITIES ON THE SITE. THE CONTRACTOR SHALL BECOME FAMILIAR WITH THE LOCATION OF ALL BURIED UTILITIES IN THE AREAS OF WORK BEFORE STARTING OPERATIONS. THE CONTRACTOR SHALL REPAIR OR REPLACE ANY BURIED CONDUIT, CABLES, OR PIPING DAMAGED DURING THE INSTALLATION OF THIS WORK. CONTRACTOR TO CONFIRM LOCATION OF ALL UNDERGROUND UTILITIES PRIOR TO START OF CONSTRUCTION. ALL UTILITIES SHALL BE FIELD LOCATED A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DISCREPANCIES WITH THIS DRAWING SHALL BE REPORTED IN WRITING TO THE CONTRACTING OFFICER'S TECHNICAL REPRESENTATIVE (COTR) AND CEMETERY DIRECTOR IMMEDIATELY.
 - IN THE EVENT OF ANY DISCREPANCIES BETWEEN THESE CONTRACT DOCUMENTS AND THE ELECTRONIC FILES, THE DRAWINGS WILL CONTROL. NOTIFY THE COTR AND CEMETERY DIRECTOR IMMEDIATELY WHEN ANY DISCREPANCY IS NOTED.
 - ALL CONTROL OF TRAFFIC REQUIRED TO PERFORM THE WORK SHALL BE THE CONTRACTOR'S RESPONSIBILITY IN ACCORDANCE WITH TDOT STANDARDS AND SPECIFICATIONS. CONTRACTOR SHALL COORDINATE ALL TRAFFIC CONTROL MEASURES WITH THE COTR AND CEMETERY DIRECTOR PRIOR TO INSTALLATION.
 - THE WALKWAYS AND ACCESS TO OCCUPIED BUILDINGS MUST REMAIN OPEN TO PEDESTRIANS AT ALL TIMES.
 - ABSOLUTELY NO DEMOLITION OR CONSTRUCTION SHALL OCCUR OVER GRAVES/EXISTING BURIALS.

- LAYOUT NOTES**
- CURB DIMENSIONS ARE TO BACK OF CURB, UNLESS OTHERWISE NOTED.
 - CONTRACTOR SHALL MAKE ADJUSTMENTS TO THE LAYOUT AS DIRECTED BY THE COTR AND CEMETERY DIRECTOR TO ENSURE PROPER CONNECTION TO EXISTING FACILITIES AND SITE AMENITIES.
 - PROPOSED CURBS TO BE FIELD STAKED FOR APPROVAL OF THE COTR AND CEMETERY DIRECTOR PRIOR TO INSTALLATION.
 - HATCH PATTERNS ARE FOR REFERENCE ONLY. HATCHES DO NOT REPRESENT DIRECTIONAL LAYOUT OR PATTERN OF MATERIALS.
 - CONTRACTOR SHALL SET AUXILIARY BENCHMARKS AS REQUIRED TO LAYOUT AND CONSTRUCT WORK.
 - SITE FURNISHING LOCATIONS SHALL BE APPROVED BY THE COTR AND CEMETERY DIRECTOR PRIOR TO INSTALLATION.
 - INSTALL EXPANSION JOINTS AT ALL CURBS/SIDEWALK, BUILDINGS/SIDEWALK OR PAVEMENT, WALL/SIDEWALK OR PAVEMENT AND SLAB ON GRADE/PAVEMENT INTERFACES AND AT ALL FIXED OBJECTS TO REMAIN (EXISTING BUILDING, WALLS, PAVEMENT, ETC.)
 - CONTRACTOR TO VERIFY WORK IN ADMINISTRATION/PUBLIC INFORMATION CENTER BUILDING THAT REMAINS TO BE COMPLETED. REFER TO ARCHITECTURAL DRAWINGS.

three inches = one foot
 one and one half inches = one foot
 one inch = one foot
 three quarters inch = one foot
 one half inch = one foot
 one quarter inch = one foot
 one eighth inch = one foot
 one sixteenth inch = one foot

CONSULTANTS: SECURITY the PROTECTION ENGINEERING GROUP ARCHITECTURE/STRUC-MECH-ELEC-PLUMB ENG SMITHGROUP JJR 901 K STREET NW SUITE 400 WASHINGTON, DC 20001 202.842.2100 www.smithgroupjir.com		LAND. ARCH/CIVIL ENG: SMITHGROUP JJR 201 DEPOT STREET ANN ARBOR, MI 48104 734.662.4457 www.smithgroupjir.com		Drawing Title LAYOUT - ADMIN + MAINTENANCE AREA Approved: OFFICE OF DESIGN AND CONSTRUCTION		Project Title MEMPHIS NATIONAL CEMETERY - PIC/ADMIN AND MAINT. BLDGS, AND SITE IMPROVEMENTS Location MEMPHIS, TENNESSEE Date 2017/06/02 Checked JY Drawn ST		Project Number 860CM307C Drawing Reference Number 008 Drawing Number C1.02		Office of Construction and Facilities Management Department of Veterans Affairs	
Bid Documents Revisions 6/2/17 Date		VA FORM 08-6231									