



### GENERAL NOTES

- REFER TO SPECIFICATIONS DIVISION 01 GENERAL REQUIREMENTS.
- REFER TO SPECIFICATIONS DIVISION 26 ELECTRICAL, DIVISION 27 COMMUNICATIONS AND DIVISION 28 ELECTRONIC SAFETY AND SECURITY FOR PROJECT SPECIFICATIONS AND REQUIREMENTS.
- REFER TO DRAWING G-004 FOR PROJECT CONSTRUCTION PHASING NOTES.
- REFER TO DRAWING S-515, DETAIL 1-TYPICAL P/C TEE DETAIL FOR DOUBLE TEE STEM BLOCKOUT LOCATIONS AND QUANTITIES FOR CONDUIT ROUTING.
- REFER TO DRAWING E-001 FOR GENERAL ELECTRICAL NOTES, ELECTRICAL SYMBOLS LIST AND ABBREVIATIONS.
- REFER TO DRAWINGS ED-101 FOR ELECTRICAL DEMOLITION PLANS.
- REFER TO DRAWINGS E-101 THROUGH E-105 FOR ELECTRICAL LIGHTING AND POWER SYSTEM PLANS.
- CONDUIT ROUTING IS SHOWN DIAGRAMMATICALLY ON FLOOR PLANS. CONTRACTOR WILL PROVIDE SHOP DRAWING INDICATING ROUTING OF ALL CONDUIT SYSTEMS PRIOR TO INSTALLATION. REFER TO DETAIL 1 ON S-515 FOR THE LOCATION AND QUANTITIES OF BLOCKOUTS AT THE PRECAST DOUBLE TEE MEMBERS.

### FIRE ALARM PLAN NOTES

- FIRE ALARM PULL STATION.
- FIRE ALARM AUDIO/VISUAL DEVICE.
- SUSPENDED SECURITY CAMERA LOCATION.
- EMERGENCY COMMUNICATION CONDUIT/CABLE UP TO ECS-1 PEDESTAL MOUNTED AT LEVEL DD.
- SUSPENDED SECURITY CAMERA SYSTEM. IT SHOULD BE CIRCUITED TO PANEL 29 ER2-02.
- CONTRACTOR WILL NOTE THAT EXISTING SECURITY SYSTEM CONDUITS AND ASSOCIATED JUNCTION BOXES ARE CURRENTLY INSTALLED WITHIN EXISTING PARKING GARAGE. THESE CONDUITS, JUNCTION BOXES AND ALL ASSOCIATED HANGERS AND ANCHOR ASSEMBLIES WILL BE REMOVED.
- CONTRACTOR WILL REMOVE EXISTING SECURITY SYSTEM RISER CONDUITS THAT ARE ROUTED TO LEVEL B. CONDUIT RISERS ARE INSTALLED AT COLUMN LINES C-15 AND D-15. ABANDONED DECK OPENINGS WILL BE PROVIDED WITH A SEALANT SYSTEM.
- ALL FIRE ALARM SYSTEM CONDUITS WILL BE PROVIDED IN PREFINISHED COLOR, RED. CONDUITS WILL BE MINIMUM 3/4" (19MM) DIAMETER.

PLAN NORTH

1

LEVEL C - COMMUNICATION, SURVEILLANCE AND FIRE ALARM

3/32"=1'-0"

<div>100% FINAL BID DOCUMENTS 08-18-2017</div> <div>100% BID DOCUMENTS-NOT FOR CONSTRUCTION 07-24-2017</div> <div>95% CONSTRUCTION DOCUMENTS SUBMISSION 06-15-2017</div> <div>65% DESIGN DEVELOPMENT SUBMISSION 04-19-2017</div> <div>35% SCHEMATIC DESIGN SUBMISSION 03-06-2017</div> <div>Revisions</div>		<div>CONSULTANTS:</div> <div><div><div></div><div>WALKER PARKING CONSULTANTS</div></div><div><div></div><div>MIDWESTERN CONSULTING</div></div></div> <div>3815 Plaza Drive Ann Arbor, Michigan 48108 (734) 995-0200 • www.midwesternconsulting.com Land Development • Land Survey • Institutional • Municipal Wireless Communications • Transportation • Landfill Services</div>		<div>KEYPLAN</div> <div>ARCHITECT + ENGINEERS:</div> <div><div><div></div><div>Bancroft Architects + Engineers</div></div><div>700 Nicholas Blvd., Suite 300 Elk Grove Village, IL 60007 Telephone : 847.952.9342 www.bancroft-ae.com Bancroft-AE Project No. 14-121</div></div> <div>VA CONTRACT NO. VA250-17-C-0008</div>		<div>Drawing Title</div> <div>LEVEL C - COMMUNICATION, SURVEILLANCE AND FIRE ALARM PLAN</div> <div>Approved Project Director</div>		<div>Project Title</div> <div>CONSTRUCT NORTH PARKING STRUCTURE</div> <div>Location</div> <div>ANN ARBOR, MICHIGAN</div> <div>Date</div> <div>08-18-2017</div> <div>Checked</div> <div>LF</div> <div>Drawn</div> <div>YY AG</div>		<div>Project Number</div> <div>506-331</div> <div>Building Number</div> <div>29</div> <div>Drawing Number</div> <div>EC-103</div>		<div>Office of Construction and Facilities Management</div> <div>Department of Veterans Affairs</div>	
---	--	--	--	---	--	--	--	---	--	---	--	---	--