



Only one OR may be shut down at a time. All work to be performed between 8pm and 5am Mon - Fri. or on Weekends / Holiday.

Demo 40" metal Base Cabinet. Install New 40" SS Base Cabinet, Patch walls and sheet vinyl floor to match existing.

Remove existing sheet flooring, patch subfloor and install new resinous flooring in these areas. Two floor colors are required in shown areas. Run flooring material up wall 6" and cap with metal to create intergal cove base.

Demo Cabinetry in these areas. Patch and paint walls to match existing. Patch subfloor to accept new flooring.

Move SS Shelf to new location as directed by COR. Patch and paint walls to match existing.

Remove sink. Cut and cap lines in wall. Patch and paint wall to match existing.

Demo 3' Metal Base Cabinet. Install New 3' SS Base Cabinet. Patch walls and sheet vinyl floor to match existing.

Demo 4' Upper Wall Cabinet and replace with New 4' SS Wall Cabinet. Patch and paint walls to match existing.

Revisions	Date	Professional Seal
<p>Drawing Title: THIRD FLOOR PLAN ARCHITECTURAL</p> <p>Project Title: OR Floor Replacement</p> <p>Building Number: CA</p> <p>Location: VAMC, CLARKSBURG</p> <p>Date: 11-28-2017</p> <p>Project No: 540-18-003S</p> <p>Drawing No: []</p>		
Approved:	Checked:	Drawn:
Approved:	Checked:	Drawn:
VA Department of Veterans Affairs		

VA FORM 08-6231, OCT 1978