DOOR SCHEDULE

DOOR NO.	DOOR WIDTH	DOOR HEIGHT	DOOR THK	No. LEAFS	DOOR TYPE	DOOR MATERIAL	FRAME TYPE	FRAME MATERIAL	FIRE RATING	HDWR. GRP.	REMARKS	REVISION
LEVEL ONE												
1500.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1500.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH2.2	SHARED BATHROOM	
1501.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1501.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH2.1	SINGLE BATHROOM	
1502.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1502.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH2.2	SHARED BATHROOM	
1503	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	5D	HAC	
1504.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1504.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH2.2	SHARED BATHROOM	
1506.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1506.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
1507.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1507.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
1508.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1508.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
1509.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1509.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
1510.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1510.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
1511.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1511.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
1512.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1512.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
1513.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1513.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
1516.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1516.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
1515.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1515.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
1517.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
1517.2	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.1	SINGLE BATHROOM	
1518	3' - 6"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.1	STORAGE	
1553	3' - 6"	7' - 0"	1 3/4"	1	6	HM	A	HM	NA	SH-3B	COMM	
1555	3' - 6"	7' - 0"	1 3/4"	2	5	WD	A	HM	NA	N/A	LOUNGE	
1558.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH1	RESIDENCE ROOM	
1558.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH2.1	SINGLE BATHROOM	
1560	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	5D	CLEAN STORAGE	
LEVEL TWO												
5C22	5' - 8"	7' - 0"	1 3/4"	2	1	WD/GL	C	HM	20 min.	SH-11	CROSS CORRIDOR	
5C26	5' - 8"	7' - 0"	1 3/4"	2	1	WD/GL	C	HM	45 min.	SH-11	CROSS CORRIDOR	
2500.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2500.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2501.2	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2501.1	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2502.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2502.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2504.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2504.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2505	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	45 min.	SH-3C	CRASH CART	
2506.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2506.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2507.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2507.2	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2508.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2508.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2509.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2509.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2510.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2510.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2511.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2511.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2512.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2512.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2513.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2513.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2514.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2514.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2520	3' - 6"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2520A	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.1	SINGLE BATHROOM	
2522	3' - 6"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2522A	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.1	SINGLE BATHROOM	
2524	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2524A	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.1	SINGLE BATHROOM	
2526	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2526A	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.1	SINGLE BATHROOM	
2528	3' - 6"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2528A	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.1	SINGLE BATHROOM	
2532	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2532A	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2534.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2534.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2535	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	SH-3C	STORAGE	
2536.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2536.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2537	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2537A	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2538.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2538.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2539.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2539.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2540.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2540.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2541.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2541.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2542.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2542.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2544.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	RESIDENCE ROOM	
2544.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	SHARED BATHROOM	
2546	3' - 6"	7' - 0"	1 3/4"	1	3	WD	A	HM	20 min.	5D	LAUNDRY ROOM	
2548.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	20 min.	MH1	STAFF LOUNGE	
2548.2	2' - 10"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2.2	STAFF BATHROOM	
2550	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	3B	STORAGE	
2550.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	3B	STORAGE	
2552.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	4K	NURSE STATION	
2552.2	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	4K	NURSE STATION	
2553	3' - 0"	7' - 0"	1 3/4"	1	6	HM	A	HM	NA	SH-3B	COMM	
2555	3' - 6"	7' - 0"	1 3/4"	2	3	WD/GL	A	HM	NA	N/A	LOUNGE	
2554	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	SH-3D	MEDICATION	
2556.1	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH1B	EXAM ROOM	
2556.2	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2A	EXAM TOILET	
2557	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	3B	OFFICE	
2558	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	NA	MH2A	EXAM TOILET	
2559	3' - 0"	7' - 0"	1 3/4"	1	5	WD	A	HM	45 min.	5D	HAC CLOSET	
LEVEL THREE												
3553	3' - 0"	7' - 0"	1 3/4"	1	6	HM	A	HM	NA	SH-3B	COMM	

NOTE:
ALL ENTRY BEDROOMS DOORS TO BE 1/3 HR RATED.

FULLY SPRINKLED

100% CD NOVEMBER 8, 2017

No.	Revisions	Date

CONSULTANTS:

ARCHITECT/ENGINEERS:

Drawing Title: DOOR SCHEDULE

Approved: Project Director

Project Title: COMPLETE CONSTRUCTION 1ST & 2ND FLOOR B405

Location: VA MEDICAL CENTER TOMAH, WI

Date: 07/25/2017 | Checked: VAS | Drawn: JE/BH

Project Number: 676-18-107

Building Number: 405

Drawing Number: 405 AS920

Dwg. 21 of 92

Office of Construction and Facilities Management

Department of Veterans Affairs