



FLOOR PLAN LEGEND

NOT ALL SYMBOLS/NOTES APPEAR ON EVERY SHEET

WHERE SYMBOL REFERENCES ANOTHER DRAWING SERIES, SYMBOL IS SHOWN FOR DESIGN/COORDINATION ONLY. REFERENCE THE ENGINEERING DRAWINGS FOR FULL SCOPE OF DEVICE LOCATIONS & ASSOCIATED SPECIFICATIONS.

GENERAL FLOOR PLAN ANNOTATION

10123
REF XXXX

ROOM NUMBER

REFERENCE ROOM NUMBER

REFERENCE ROOM NUMBER INDICATES ROOM TO REFERENCE FOR TYPICAL MEDICAL EQUIPMENT LAYOUT, INTERIOR ELEVATION TAGS, GENERAL ANNOTATION AND DIMENSIONS UNLESS OTHERWISE NOTED.

INTERIOR ELEVATION REFERENCE:

A
B
C
D

INTERIOR ELEVATION CALLOUT

SHEET ON WHICH ELEVATION IS DRAWN

XAI10X
XAI10Y

MATCHLINE REFERENCE

CENTERLINE TAG

EL: +10'-0"

SPOT ELEVATION

XXXX

PARTITION TYPE TAG - REF PARTITION SCHEDULE SHT 0A1002

RELITE TAG - REF FRAME SCHEDULE SHEET 0A1000

XXXXX

DOOR TAG - REF DOOR SCHEDULES A1000 SERIES

FLOOR SYMBOLS

FD

FLOOR DRAIN - REF PLUMBING DWGS

WHERE DRAIN IS NOT SET IN DEPRESSIONED SLAB/SLOPED FLOOR SYSTEM, SET DRAIN 1/2" BELOW FINISH FLOOR LEVEL AND TAPER CONC. AND FLOORING TO FLUSH W/ DRAIN STRAINER IN A 2' RADIUS FROM CENTER OF DRAIN

FLOOR OUTLET - REF ELECTRICAL DWGS

FCO

FLOOR CLEAN OUT - REF PLUMBING DWGS

WALL DEVICE/CABINET SYMBOLS

CR

CARD READER - REF LOW VOLTAGE DWGS

DP

DOOR PUSH PLATE - REF LOW VOLTAGE DWGS

PB

PANIC ALARM BUTTON - REF LOW VOLTAGE DWGS

IA

INFORMATION ASSIST CALL BOX - REF LOW VOLTAGE DWGS

FA/PS

FIRE ALARM PULL STATION - REF FIRE ALARM DWGS

10.44.13 - FIRE EXTINGUISHER CABINETS

FEC

RECESSED CABINET SIZED TO HOLD 10# ABC EXTINGUISHER

FEC.20

RECESSED CABINET SIZED TO HOLD 20# CO2 EXTINGUISHER

FEW

WALL MOUNTED EXTINGUISHER ELECTRICAL

HVC

FIRE DEPARTMENT HOSE VALVE CABINET - REF FIRE PROT. DWGS

MISCELLANEOUS

EXX-X

07.95.13 - INTERIOR EXPANSION JOINT COVER ASSEMBLY - "XX" LETTER DESIGNATION INDICATES COVER TYPE PER SHEET 0A1517. REFERENCE FIRE/SMOKE RATED CONDITIONS AS INDICATED BY ASSOCIATED PTN TYPES ON THE FLOOR PLANS.

LKR-XX

LOCKERS: "XX" DESIGNATION INDICATES TYPE:

2A - 10.51.13 - DBL TIER METAL LOCKERS, SLOPED TOP

12" W X 15" D X 60" H

LOCKERS PAINTED TO MATCH ADJ WALL

REF DTL D20A532

2A.1 - 10.51.13 - DBL TIER METAL LOCKERS, SLOPED TOP

12" W X 15" D X 60" H

LOCKERS PAINTED TO MATCH ADJ WALL

REF DTL D20A532

2B - 10.51.23 - DBL TIER "Z" PLAM LOCKERS, W/ PLAM SOFFIT

12" W X 15" D X 80" H

FINISH: PLAM-10

REF DTL D20A532

TOPS OF LOCKERS TO ALIGN AT 7'-0" AFF.

FOR REFERENCE ONLY - GENERAL LOCATION OF OPEN OFFICE FURNITURE - SEE FURNITURE DWGS FOR EXACT TYPES AND LOCATIONS.

SHIELDING

SEE SHIELDING DETAILS/SCHEDULES ON SHEET 0A1514

LEAD

LEAD SHIELDING

RF

RADIOFREQUENCY SHIELDING

EMI

ELECTROMAGNETIC INTERFERENCE SHIELDING

MAG

MAGNETIC SHIELDING

MEDICAL EQUIPMENT/OFFICE EQUIPMENT

XX1234

X1234

DASHED OBJECTS WITH EQUIPMENT TAG INDICATE MEDICAL/OFFICE EQUIPMENT. REFERENCE EQUIPMENT ACTIVATION REPORT - SEE SPECIFICATIONS SECTION 01.11.10 FOR LOCATION OF REPORT.

TOILET GRAB BAR CONFIGURATIONS

TOILET WITH WALL MOUNTED GRAB BARS

10.28.00

SEE SHEET 0A1001 FOR GRAB BAR MOUNTING HEIGHTS AND DIMENSIONAL LAYOUT

TOILET WITH WALL MOUNTED UP-SWING GRAB BARS

10.28.00

SEE SHEET 0A1001 FOR GRAB BAR MOUNTING HEIGHTS AND DIMENSIONAL LAYOUT

GENERAL FLOOR PLAN NOTES

- REFER TO SHEET 0A1002 FOR PARTITION SCHEDULE AND GENERAL PARTITION TYPE NOTES.
- REFER TO A1000 SERIES FOR ENLARGED FLOOR PLAN VIEWS INCLUDING MEDICAL EQUIPMENT NOT SHOWN IN A1000 SERIES PLANS.
- REFER TO LIFESAFETY DRAWINGS (LS SERIES) FOR CAMPUS-WIDE SCOPE OF RATED WALL CONSTRUCTION, SMOKE PARTITIONS, SUITE DESIGNATIONS AND EXIT DISCHARGE INFORMATION.
- PARTITION TYPES AS NOTED BY THE SYMBOL CONTINUE BETWEEN ROOM/SPACE CORNERS OR ANY INTERSECTING PARTITION.
- DIFFERING PARTITION TYPES SHALL ALIGN SO THAT WALL PLANES CONTINUE UNBROKEN WITHIN CROSS ROOMS AND/OR SPACES.
- UNLESS OTHERWISE NOTED, DIMENSIONS ARE TO FINISH FACE.
- REFER TO A1000 SERIES DRAWINGS FOR DOOR & RELITE SCHEDULES.
- DISTANCE FROM HINGE SIDE OF DOOR TO INTERSECTING STUD WALL SHALL BE 4" UNLESS NOTED OR DETAILLED OTHERWISE (MEASURED FROM OUTSIDE OF FRAME).
- CONTRACTOR SHALL VERIFY ALL DIMENSIONS NOTED AS "CLEAR" OR "MIN". DIMENSIONS NOTED AS "HOLD" ARE CRITICAL TO COORDINATE OTHER WORK (E.G. CEILING GRIDS, LIGHTING, FINISHES).
- CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO INITIATING CONSTRUCTION AND REPORT DISCREPANCIES TO ARCHITECT PRIOR TO COMMENCING WORK.
- CONTRACTOR SHALL PROVIDE ALL BLOCKING REQUIRED TO ANCHOR ALL WALL AND CLS MOUNTED ITEMS, INCLUDING BUT NOT LIMITED TO TOILET ROOM ACCESSORIES, MILLWORK, CASEWORK, HANDRAILS, DOOR STOPS ETC....
- FIRE STOPPING SYSTEMS - REFER TO SPEC SECTION 07.94.00 FOR INFO REGARDING PENETRATIONS OF ALL RATED ASSEMBLIES (BOTH SINGLE AND DOUBLE MEMBRANE PENETRATIONS) INCLUDING BUT NOT LIMITED TO PENETRATIONS FOR DUCTWORK, CONDUIT, PIPING AND SUPPORT FOR WALL MOUNTED EQUIPMENT, CABINETS AND COUNTERTOPS.
- UP-SWING GRAB BAR/WALL SUPPORT - SEE DTL'S C2 AND A3 SHEET 0A1006 FOR TUBE STEEL BACKING AT ALL UP-SWING GRAB BARS.
- SEE DETAIL A30A1516 FOR COLUMN BASE WATERPROOFING AT EXPOSED COLUMNS IN SERVICE BAYS & MECHANICAL ROOMS.
- SHIELDING REQUIREMENTS - VERIFY ALL SHIELDING REQUIREMENTS WITH FINAL EQUIPMENT SELECTIONS AND A VA APPROVED REGISTERED PHYSICIST PRIOR TO COMMENCING WORK IN SHIELDED-ROOM AREAS.
- HOUSEKEEPING AND COPY ROOMS - ALL PARTITIONS TO BE FULL HEIGHT TO UNDERSIDE OF DECK/INTERSTITIAL ABOVE. SEE PARTITION TYPE NOTES SHEET 0A1002.

FLOOR PLAN SHEET NOTES

FLOOR PLAN SHEET NOTE SERIES BEGINS WITH NOTE 100

NOT ALL SHEET NOTES APPEAR ON EVERY SHEET

- SLAB OPENING - REF STRUCTURAL DWGS
- ALIGN PARTITIONS
- LINE OF CURTAIN WALL SILL - REF EXTERIOR SERIES DWGS.
- LINE OF HOISTWAY BELOW
- AIR HANDLER UNIT - REF MECHANICAL DWGS
- STEEL BRACING - REF STRUCTURAL DWGS
- CONCRETE HOUSEKEEPING PAD - REF STRUCTURAL DWGS
- ACCORDIAN FIRE DOOR - REF DOOR SCHEDULE
- ADD ALL & 01: 14.92.00 PNEUMATIC TUBE STATION - REF DETAILS C4 & C50A1507.
- 08.31.13 FLOOR VAULT DOOR - 36" X 36" - REF DTL E10A1516
- ROOF/OVERFLOW DRAIN LEADER - REF PLUMBING DWGS
- ELECTRICAL PANEL - REF ELECTRICAL DWGS
- MEDICAL GAS ZONE VALVE BOX/MEDICAL GAS ALARM PANEL - REF MED GAS DWGS
- SLOPE FLOORING IN SHOWER/TOILET ROOM TO DRAIN
- SLAB RECESS FOR HIGH DENSITY SHELVING TRACK - VFY RECESS DIMENSION W/ SHELVING MANUFACTURER.
- 14.91.34 TRASH/INCHEN CHUTE & STATION: SEE DETAILS E60A1507
- 14.91.34 TRASH/INCHEN CHUTE: NO LOADING STATION
- 14.91.34 TRASH/INCHEN CHUTE: PROVIDE SLEEVES @ LEVEL 01 FLOOR
- SLAB PENETRATION - SEE DETAILS E60A1507
- 08.31.13 3-HOUR FIRE RATED ACCESS PANEL - 24" X 48"
- ELECTRICAL RISERS - SEE PLAN DETS ON F50A1512 - REF ELEC DWGS
- CONCRETE ENCASED ELECTRICAL FEEDERS ABOVE - REF STRUCTURAL & ELEC DWGS
- 09.27.02 GLASS FIBER REINFORCED GYPSUM COLUMN COVER - 36" O.D. UON.
- BOLD DASHED LINE INDICATES ROUTE OF STRUCTURAL EXPANSION JOINT - REF STRUCTURAL DWGS. REFERENCE FLOOR FINISH SCHEDULE FOR INTERIOR EXPANSION JOINT COVER ASSEMBLY INFORMATION.
- 10.11.00 MARKER BOARD REF INTERIOR ELEV SHEET NOTE 207.
- 10.11.00 TACK BOARD REF INTERIOR ELEV SHEET NOTE 208.
- 10.28.00 FOLD-DOWN BENCH
- 10.28.00 FOLD-DOWN SHOWER SEAT
- SLAB RECESS FOR WALK-OFF GRILLE - VFY RECESS DIMENSION W/ GRILLE MANUFACTURER. SEE FLOOR FINISH PLANS FOR EXTENTS.
- PLUMBING ROUGH-IN FOR FLOOR SINK - REF PLUMBING DWGS
- BENT PLATE W/ TRAFFIC COATING WRAP @ WALL BASE - REF B30A1516
- LINE OF 2-HR RATED SHAFT ABOVE - REF DETAILS E1 & E3 SHT 0A1507
- 05.05.00 ACCESS LADDER
- 10.33.13 WIRE MESH PARTITION
- 05.02.13 PIPE AND TUBE RAILING
- 11.13.00 MANUAL DOCK LEVELER AND BUMPERS
- 13.44.00 MODULAR MEZZANINES INCL. STAIRS & WIRE MESH PTNS.
- 05.50.00 METAL GRATE CATWALK
- WALL MOUNTED HAND SINK - REF PLUMBING DWGS
- RECESSED EMERGENCY SHOWER AND EXPOSED STAINLESS STEEL SHOWER HEAD - REF PLUMBING DWGS
- 08.39.19 FLOOD BARRIERS: FLOOD PLANK SYSTEM - REF D50A1511
- CONC. WALLS @ 01.11 ELEV SHAFTS - REF STRUCT DWGS & DTL E10A1507
- BENT PLATE W/ PEDESTRIAN TRAFFIC COATING WRAP - REF C30A1516
- PLENUM SYSTEM - SEE EXTERIOR DRAWINGS
- CENTER PARTITION ON GRIDLINE
- CENTER PARTITION ON MULLION
- 10.21.13 TOILET PARTITIONS
- TOP OF SHAFT LID ASSEMBLY - REF DETAIL B40A1507
- CONC CURB W/ PEDESTRIAN TRAFFIC COATING WRAP - REF D30A1516
- LIGHTING INVERTER CABINET - REF ELEC DWGS
- ELEVATOR PUMP CONTROL PANEL - REF PLUMB DWGS

KEY PLAN

CONSTRUCTION DOCUMENTS 1 FULLY SPRINKLERED

BLDG 1 FIRST FLOOR PLAN - AREA C1

SCALE: 1/8" = 1'-0"

CONSULTANTS:

DESMAN ASSOCIATES / PARKING
CODE CONSULTANTS, INC. / CODE CONSULTANT
THE SEXTANT GROUP / AV & ACOUSTICAL
HAMMER DESIGN ASSOCIATES / FOOD SERVICE
PYBURN & ODOM / ABATEMENT
TATA & HOWARD / TANK CONSULTANT
I.S.C. GROUP, INC. / IRRIGATION
DAN EUSER WATER ARCHITECTURE, INC. / WATER FEATURE

ARCHITECT/ENGINEERS:

studio **NOVA**
SCHRENK & PETERSON CONSULTING ENGINEERS / CIVIL
KORDA/NEMETH ENGINEERING / STRUCTURAL
BR+A CONSULTING ENGINEERS / MECH. ELECT, PLUMBING, LOW VOLTAGE
ARCHITECTURAL ENGINEERING / PLUMBING
SCALES ASSOCIATES / FIRE PROTECTION

DRAWING TITLE
BLDG 1 FIRST FLOOR PLAN - AREA C1

APPROVED: PROJECT DIRECTOR

PROJECT TITLE
SLVHCS REPLACEMENT MEDICAL CENTER PROJECT

LOCATION
NEW ORLEANS, LOUISIANA

DATE
February 29, 2012

CHECKED
ML

DRAWN
AG/DMK

PROJECT NUMBER
629-HS2-401

BUILDING NUMBER
01

DOCUMENT SET PACKAGE
WP_08

DRAWING NUMBER

OFFICE OF CONSTRUCTION AND FACILITIES MANAGEMENT

Department of Veterans Affairs

REVISIONS:	DATE
23 BULL 021	1/31/2014
12 BULL 015A - VE	7/26/2013
11 BULL 015A - PRE-AWARD	7/26/2013

VA FORM 08-6231