

Overton Brooks VAMC Infection Control Precautions for Class II Projects

Based on the Infection Control Risk Assessment of this construction/remodel project, the following activities are required.

PROJECT: BE1-Precautiona

	During Construction Project	Upon Completion of Project
Class II	<ol style="list-style-type: none"> 1. Provide active means to reduce airborne dust from dispersing into atmosphere. 2. Water mist work surfaces to control dust while cutting. 3. Seal unused doors with duct tape. 4. Block off and seal air vents if the HVAC system is removed or isolated. 5. Place dust mat at entrance and exit of work area 6. Remove or isolate HVAC system in areas where work is being performed if required to prevent contamination of adjacent areas. 7. Contain construction waste before transport in tightly covered containers. 	<ol style="list-style-type: none"> 1. Wipe work surfaces with cleaner/disinfectant. 2. Contain construction waste before transport in tightly covered containers. 3. Wet mop and/or vacuum with HEPA filtered vacuum before leaving work area. 4. Upon completion, restore HVAC system where work was performed. 5. Schedule EMS Terminal Clean once work is complete

Maintain control measures until ALL Work is completed. Exceptions must be approved by Infection Prevention on a case by case basis.

Preliminary

1/26/2018

X Vickie L. Moore

Vickie L. Moore
Infection Prevention Program Manager
Signed by: VICKIE L. MOORE 193380

Final

X

Vickie L. Moore MA, CIC, VHA-CM
Infection Prevention Program Manager