

STI SP001 Monthly Inspection Checklist

General Inspection Information:

Inspection Date: _____	Retain Until Date: _____ (36 months from inspection date)
Prior Inspection Date: _____	Inspector Name: _____
Tanks Inspected (ID #'s): _____	

Inspection Guidance:

- For equipment not included in this Standard, follow the manufacturer recommended inspection/testing schedules and procedures.
- The periodic AST Inspection is intended for monitoring the external AST condition and its containment structure. This visual inspection does not require a Certified Inspector. It shall be performed by an owner's inspector who is familiar with the site and can identify changes and developing problems.
- Upon discovery of water in the primary tank, secondary containment area, interstice, or spill container, remove promptly or take other corrective action. Before discharge to the environment, inspect the liquid for regulated products or other contaminants and disposed of it properly.
- (*) designates an item in a non-conformance status. This indicates that action is required to address a problem.
- Non-conforming items important to tank or containment integrity require evaluation by an engineer experienced in AST design, a Certified Inspector, or a tank manufacturer who will determine the corrective action. Note the non-conformance and corresponding corrective action in the comment section.
- Retain the completed checklists for 36 months.
- **In the event of severe weather (snow, ice, wind storms) or maintenance (such as painting) that could affect the operation of critical components (normal and emergency vents, valves), an inspection of these components is required as soon as the equipment is safely accessible after the event.**

Item	Task	Status	Comments
1.0 Tank Containment			
1.1 Containment structure	Check for water, debris, cracks or fire hazard	<input type="checkbox"/> Yes* <input type="checkbox"/> No <input type="checkbox"/> N/A	
1.2 Primary tank	Check for water	<input type="checkbox"/> Yes* <input type="checkbox"/> No	
1.3 Containment drain valves	Operable and in a closed position	<input type="checkbox"/> Yes <input type="checkbox"/> No* <input type="checkbox"/> N/A	
1.4 Pathways and entry	Clear and gates/doors operable	<input type="checkbox"/> Yes <input type="checkbox"/> No* <input type="checkbox"/> N/A	
2.0 Leak Detection			
2.1 Tank	Visible signs of leakage	<input type="checkbox"/> Yes* <input type="checkbox"/> No	
2.2 Secondary Containment	Visible signs of leakage from tank into secondary containment	<input type="checkbox"/> Yes* <input type="checkbox"/> No	
2.3 Surrounding soil	Visible signs of leakage	<input type="checkbox"/> Yes* <input type="checkbox"/> No <input type="checkbox"/> N/A	
2.4 Interstice	Visible signs of leakage	<input type="checkbox"/> Yes* <input type="checkbox"/> No <input type="checkbox"/> N/A	

Item	Task	Status	Comments
3.0 Tank Equipment			
3.1 Valves	a. Check for leaks.	<input type="checkbox"/> Yes* <input type="checkbox"/> No <input type="checkbox"/> N/A	
	b. Tank drain valves must be kept locked.	<input type="checkbox"/> Yes* <input type="checkbox"/> No <input type="checkbox"/> N/A	
3.2 Spill containment boxes on fill pipe	a. Inspect for debris, residue, and water in the box and remove.	<input type="checkbox"/> Yes* <input type="checkbox"/> No <input type="checkbox"/> N/A	
	b. Drain valves must be operable and closed.	<input type="checkbox"/> Yes* <input type="checkbox"/> No <input type="checkbox"/> N/A	
3.3 Liquid level equipment	a. Both visual and mechanical devices must be inspected for physical damage.	<input type="checkbox"/> Yes <input type="checkbox"/> No* <input type="checkbox"/> N/A	
	b. Check that the device is easily readable	<input type="checkbox"/> Yes <input type="checkbox"/> No* <input type="checkbox"/> N/A	
3.4 Overfill equipment	a. If equipped with a "test" button, activate the audible horn or light to confirm operation. This could be battery powered. Replace the battery if needed	<input type="checkbox"/> Yes <input type="checkbox"/> No* <input type="checkbox"/> N/A	
	b. If overfill valve is equipped with a mechanical test mechanism, actuate the mechanism to confirm operation.	<input type="checkbox"/> Yes <input type="checkbox"/> No* <input type="checkbox"/> N/A	
3.5 Piping connections	Check for leaks, corrosion and damage	<input type="checkbox"/> Yes* <input type="checkbox"/> No	
4.0 Tank Attachments and Appurtenances			
4.1 Ladder and platform structure	Secure with no sign of severe corrosion or damage?	<input type="checkbox"/> Yes <input type="checkbox"/> No* <input type="checkbox"/> N/A	
5.0 Other Conditions			
5.1	Are there other conditions that should be addressed for continued safe operation or that may affect the site spill prevention plan?	<input type="checkbox"/> Yes* <input type="checkbox"/> No	

[illegible]