

Department 1

Name: Administration

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required (per Station/Room)	Additional space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
Director (OFM02)	115	1	1	1	0	150	0	150	1.25	187.5	1	0	1	2	1	Y	40	0	1	N	
Associate Director (OFA02)	113	1	1	1	0	150	0	150	1.25	187.5	1	0	1	2	1	Y	40	0	1	N	
Vacant Office	111	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	N		0	1	N	
National CMOP Office	112	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	N		0	1	N	
Admin Support (SEC01)	114	1	1	1	0	56	0	56	1.3	72.8	1	0	1	2	0	Y	40	0	0	N	Should be located directly adjacent to Director's office
Reception (RECP1)	108	1	1	0	1	75	0	75	1.3	97.5	1	0	1	2	0	N		0	0	N	Visual connection to entrance, counter
Program Specialist 1 (HR)	104	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	Y	40	0	1	Y	
Program Specialist 2 (HR)	105	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	Y	40	0	1	Y	
PIV Room	109	0	1	1	0	100	0	100	1.25	125	1	1	1	1	0	N		0	1	Y	Finger printing, badges, near Program Specialist Handbook 0730 - Up & Over Protection, Card Reader
Record Files Storage	118	0	1	0	0	275	0	275	1.25	343.75	0	1	0	0	0	N		0	0	Y	Handbook 0730 - Up & Over Protection, Card Reader
TOTAL		8				1206		1206		1514	9	2	9	17	2			0	7		

Notes:

Key:

Sound Insulation: Space has a STC factor rating. Details in Section 7.4 of the SFO.

Secure Area: Space has special requirements in Handbook 0730, or specific needs from customer. Leavenworth wants card readers on all doors. Room details in Schedule B, E, and Doors.

Department 2

Name: Quality Management

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required (per Station/Room)	Additional space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
Facility QA Mgr	134	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	Y	40	0	1	N	Admin suite
Head QA Pharmacist	133	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	Y	40	0	1	N	Admin suite
Health System Specialist	132	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	N		0	1	N	Near training room
QA Pharmacists (shared open office)	129	5	5	1	5	56	0	280	1.3	364	5	0	5	10	0	N		0	1	N	Near production floor
Training Room	130	0	13	0	13	25	100	425	1.25	506	1	14	13	13	2	Y	40	0	1	N	Training room with 12 workstations (testing stations), 1 workstation for test administrator, 1 projector, 1 smart board
Training Room Storage	131	0	1	0	0	40	0	40	1.25	50	0	0	0	0	0	N		0	0	N	
TOTAL		8						1045		1295	9	14	21	29	2			0	5		

Notes:

Key:

Sound Insulation: Space has a STC factor rating. Details in Section 7.4 of the SFO.

Secure Area: Space has special requirements in Handbook 0730, or specific needs from customer. Leavenworth wants card readers on all doors. Room details in Schedule B, E, and Doors.

Department 3 Name: Logistics

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required (per Station/Room)	Additional space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
Supervisor Inventory Mgt Specialist	101	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	Y	40	0	1	N	
Inventory Mgt Specialist	102	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	N		0	1	N	
Inventory Mgt Specialists (Shared/Open Office)	179	6	6	0	6	56	300	636	1.3	737	6	1	6	12	0	N		1	0	N	Additional space for lateral files, misc storage.
COTR Program Specialist	103	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	N		0	1	N	
TOTAL		9						936		1112	9	1	9	18	0			1	3		

Notes:

Key:
Sound Insulation: Space has a STC factor rating. Details in Section 7.4 of the SFO.
Secure Area: Space has special requirements in Handbook 0730, or specific needs from customer. Leavenworth wants card readers on all doors. Room details in Schedule B, E, and Doors.

Department 4 Name: Facility Management

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required (per Station/Room)	Additional space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
Supervisory Facility Operations Specialist Manager	120	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	Y	40	0	1	N	Admin suite, access to production floor
Housekeeping Supervisor	121	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	Y	40	0	1	N	Admin suite, access to production floor
Supervisory General Engineer	122	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	Y	40	0	1	N	Adjacent to engineering technicians and production floor
Engineering Technicians	151	4	4	0	1	56	300	356	1.3	372.8	4	0	4	8	0	N		0	1	N	Provide additional space for large steel cabinets (Vidmar) and miscellaneous storage of parts and equipment
Maintenance Shop	150	0	1	0	1	700	0	700	1	700	1	0	0	0	0	Y	45	0	0	N	Provide space and utilities for: drill press, welding station (electric and gas welding), bench grinder/sander, table saw, band saw, milling machine, sheet metal brake
Maintenance Storage	153	0	1	0	1	700	0	700	1	700	0	1	0	0	0	Y	45	0	0	N	Adjacent to maintenance shop
Housekeeping	166	5	1	1	0	100	0	100	1.25	125	0	1	1	1	0	N		0	0	N	Adjacent to shipping
Housekeeping Storage		0	1	0	0	80	0	80	1.25	100	0	0	0	0	0	N		0	0	N	Adjacent to Housekeeping
TOTAL		12						2236		2373	8	2	8	15	0			0	4		

Notes:

Key:

Sound Insulation: Space has a STC factor rating. Details in Section 7.4 of the SFO.

Secure Area: Space has special requirements in Handbook 0730, or specific needs from customer. Leavenworth wants card readers on all doors. Room details in Schedule B, E, and Doors.

Department 5

Name: Fiscal

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required (per Station/Room)	Additional space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
Financial Manager (OFA02)	110	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	Y	40	0	1	N	
Accountants (shared office)	119	3	3	0	3	56	0	168	1.3	218.4	3	0	3	6	0	N		0	1	N	
TOTAL		4						268		343	4	0	4	8	0			0	2		

Notes:

Key:

Sound Insulation: Space has a STC factor rating. Details in Section 7.4 of the SFO.

Secure Area: Space has special requirements in Handbook 0730, or specific needs from customer. Leavenworth wants card readers on all doors. Room details in Schedule B, E, and Doors.

Department 6

Name: IT

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required (per Station/Room)	Additional space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
IT Manager (OFC01)	128	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	Y	40	0	1	Y	Card Reader
IT Specialists (OFA03)	127	4	4	0	4	56	150	374	1.3	441.2	4	0	4	8	0	N		0	1	Y	<ul style="list-style-type: none"> One office with four workstations. Provide space for large format plotter. Card Reader
IT Storage (SRE01)	123	0	1	0	0	600	0	600	1.25	750	0	0	0	0	0	N		0	0	Y	<ul style="list-style-type: none"> Secure space for IT work space and storage of IT equipment. Provide secured (lockable) access, rack storage. Card Reader
Process Equipment Server Room	149	0	1	0	0	500	0	500	1.25	625	0	0	0	0	0	Y	45	0	0	Y	<ul style="list-style-type: none"> Locate server equipment, security system control and video storage, misc IT storage, under-floor air, under-floor cabling. Provide data outlets as required to accommodate data and telecommunications systems. Handbook 0730 - Up & Over Protection, CCTV, and Card Reader
TOTAL		5						1574		1941	5	0	5	10	0			0	2		

Notes:

Key:

Sound Insulation: Space has a STC factor rating. Details in Section 7.4 of the SFO.

Secure Area: Space has special requirements in Handbook 0730, or specific needs from customer. Leavenworth wants card readers on all doors. Room details in Schedule B, E, and Doors.

Department 7

Name: Administrative Support

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required (per Station/Room)	Additional space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
Conference Room (CRA02)	124	20	1	0	0	500	0	500	1.25	625	1	10	1	1	2	Y	40	0	0	N	<ul style="list-style-type: none"> • Projection, smart board capabilities, 20 seating w/ table • Floor mounted data & electrical for conference table
Admin Copy/ Work Room	117	0	1	0	0	200	0	200	1.25	250	1	0	0	0	0	N		1	0	N	<ul style="list-style-type: none"> • Base/wall cabinets/countertop for storage • Adjacent to Logistics • Large multi-function (printer/fax/scanner/copier)
Admin Break Area	116	0	1	0	0	200	0	200	1.25	250	0	1	0	0	0	N		0	0	N	Base/wall cabinets/countertop for storage. Provide space and utilities for full size refrigerator (2), microwave (4) and commercial coffee maker (1).
Admin Men's Toilet	125	0	1	0	0	200	0	200	1.25	250	0	0	0	0	0	Y	45	0	0	N	
Admin Women's Toilet	126	0	1	0	0	200	0	200	1.25	250	0	0	0	0	0	Y	45	0	0	N	
Admin Housekeeping Closet (HAC)	152	0	1	0	0	75	0	75	1.25	93.75	0	0	0	0	0	N		0	0	N	Card Reader
Admin Electrical (subpanel)	180	0	1	0	0	80	0	80	1.25	100	1	0	0	0	0	N		0	0	N	Local Panelboard for Admin, Card Reader
Open Conference Area	177	0	1	0	0	320	0	320	1.25	400	1	5	1	1	0	N		0	0	N	<ul style="list-style-type: none"> • Adjacent to Director's Office • Projection, smart board capabilities, 8 seating w/table • Floor mounted data & electrical for conference table
Waiting	106	0	1	0	0	100	0	100	1.25	125	0	1	0	0	0	Y	45	0	0	N	Adjacent to Reception
Entry Vestibule	107	0	1	0	0	100	0	100	1.25	125	0	0	0	0	0	N		0	0	N	Security glass
TOTAL		20						1975		2469	4	17	2	2	2			1	0		

Notes:

Key:

Sound Insulation: Space has a STC factor rating. Details in Section 7.4 of the SFO.

Secure Area: Space has special requirements in Handbook 0730, or specific needs from customer. Leavenworth wants card readers on all doors. Room details in Schedule B, E, and Doors.

Department 8

Name: Production

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required (per Station/Room)	Additional space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
Main Process Floor	178	70	1	0	20	43000	0	43073	1	43073	5	150	25	25	0	N		0	0	Y	<ul style="list-style-type: none"> Data and power outlets to be provided as required for selected production equipment. Plan for 20 Pharmacist verification workstations as well as 130 special systems connections for the equipment, and workstations for training. Card Readers on all doors entering the Main Floor
Cumulative UUA	176																				Space allocation included in Main Process Floor line above.
Cumulative Puck Packing	174																				
Cumulative Tote/Bulk Packing																					
Cumulative TCA Area	175																				Freezer planned for 400 SF. Allocated in Main Process Floor.
Refrigerator/Freezer	171																				
Intermediate Comm Closet	TBD																			Y	Planned for 100 SF. Allocated in Main Process Floor. Handbook 0730.
Forklift Charging/storage	159	0	1	1	0	250	0	250	1	250	0	0	0	0	0	N		0	0	N	
Returns	170	0	1	1	0	575	0	575	1	575	1	0	1	1	0	N		0	1	N	
Supervisory Program Specialists	141	3	3	0	3	56	0	168	1.3	218.4	3	0	3	3	0	N		0	1	Y	"Cubicle" workstations located on production floor
Supervisory Pharmacist	142	1	1	1	0	100	0	100	1.25	125	1	0	1	2	0	Y	40	0	1	Y	Card Reader
Third Party Contractor	143	2	1	0	2	100	0	100	1.25	125	2	0	2	2	0	Y	40	0	1	Y	<ul style="list-style-type: none"> One office with two workstations. Locate near the Supervisory Pharmacists' offices. Non-VA Network
TCA Supervisor	181	1	1	0	1	56	0	56	1.3	72.8	1	0	1	2	0	N		0	1	N	Single private "cubicle" workstation located on production floor
Offline Replenishment Supervisor	182	1	1	0	1	56	0	56	1.3	72.8	1	0	1	2	0	N		0	0	N	Single private "cubicle" workstation located on production floor
Packing Supervisor	183	1	1	0	1	56	0	56	1.3	72.8	1	0	1	2	0	N		0	0	N	Single private "cubicle" workstation located on production floor
UUA/Manual Pick Supervisor	184	1	1	0	1	56	0	56	1.3	72.8	1	0	1	2	0	N		0	0	N	Single private "cubicle" workstation located on production floor
TOTAL		80						44490		44658	16	150	36	41	0			0	5		

Notes:

Key:

Sound Insulation: Space has a STC factor rating. Details in Section 7.4 of the SFO.

Secure Area: Space has special requirements in Handbook 0730, or specific needs from customer. Leavenworth wants card readers on all doors. Room details in Schedule B, E, and Doors.

Department 9 Name: Receiving

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required (per Station/Room)	Additional space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
Receiving	154	3	1	0	3	2900	0	2900	1	2900	3	0	3	3	0	N		0	1	Y	Card Reader
TOTAL		3						2900		2900	3	0	3	3	0			0	1		

Notes:

Key:
Sound Insulation: Space has a STC factor rating. Details in Section 7.4 of the SFO.
Secure Area: Space has special requirements in Handbook 0730, or specific needs from customer. Leavenworth wants card readers on all doors. Room details in Schedule B, E, and Doors.

Department 10 Name: Shipping

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required (per Station/Room)	Additional space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
Shipping Container Storage/ Staging	168	0	30	0	30	20	0	600	1	600	0	0	0	0	0	N		0	0	Y	Card Reader
Shipping	169	1	1	0	1	3050	0	3050	1	3050	1	0	0	0	0	N		0	1	Y	Card Reader
TOTAL		1						3650		3650	1	0	0	0	0			0	1		

Notes:

Key:
Sound Insulation: Space has a STC factor rating. Details in Section 7.4 of the SFO.
Secure Area: Space has special requirements in Handbook 0730, or specific needs from customer. Leavenworth wants card readers on all doors. Room details in Schedule B, E, and Doors.

Department 11

Name: Replenishment

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required (per Station/Room)	Additional space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
Replenishment	156	20	1	0	16	3000	0	3000	1	3000	2	16	16	16	0	N		0	1	Y	Card Reader
TOTAL		20						3000		3000	2	16	16	16	0			0	1		

Notes:

Key:

Sound Insulation: Space has a STC factor rating. Details in Section 7.4 of the SFO.
Secure Area: Space has special requirements in Handbook 0730, or specific needs from customer. Leavenworth wants card readers on all doors. Room details in Schedule B, E, and Doors.

Department 12 Name: Warehouse

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required (per Station/Room)	Additional Space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
Bulk Storage Warehouse	155	5	1	0	5	8190	0	8190	1	8190	5	0	5	5	0	N		0	1	N	
TOTAL		5						8190		8190	5	0	5	5	0			0	1		

Department 13

Name: **Production Support**

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required	Additional space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
Main Men's Toilet	144	0	1	0	0	550	0	550	1.25	687.5	0	0	0	0	0	N		0	0	N	
Main Women's Toilet	145	0	1	0	0	1000	0	1000	1.25	1250	0	0	0	0	0	N		0	0	N	
Production Housekeeping Closet	146	0	1	0	0	100	0	100	1.25	125	0	0	0	0	0	N		0	0	N	
Satellite Unisex Toilet	157	0	1	0	0	70	0	70	1.25	87.5	0	0	0	0	0	N		0	0	N	
Satellite Unisex Toilet	158	0	1	0	0	70	0	70	1.25	87.5	0	0	0	0	0	N		0	0	N	
Mechanical Room	165	0	1	0	0	500	0	500	1.25	625	0	1	0	0	0	Y	45	0	0	N	Includes hydronic boiler, pumps, air separation, expansion tank, domestic water heating
Electrical	163	0	1	0	0	350	0	350	1.25	437.5	0	1	0	0	0	N		0	0	N	
Comm Demarc Room	147	0	1	0	0	100	0	100	1.25	125	1	0	0	0	0	N		0	0	Y	Handbook 0730
Bldg Comm Room	148	0	1	0	0	150	0	150	1.25	187.5	0	0	0	0	0	N		0	0	Y	Handbook 0730
Satellite Comm Room	160	0	1	0	0	100	0	100	1.25	125	0	0	0	0	0	N		0	0	Y	Handbook 0730
Compressor Room	162	0	1	0	0	200	0	200	1.25	250	0	1	0	0	0	Y	45	0	0	N	
Trash/Recycling	167	0	1	0	0	900	0	900	1.25	1125	0	0	0	0	0	N		0	0	N	Includes shredder/chipper, cardboard bailer, loading area, temporary storage of baled materials
UPS Room	161	0	1	0	0	300	0	300	1.25	375	0	1	0	0	0	Y	45	0	0	Y	Card Reader
Riser Room	164	0	1	0	0	80	0	80	1.25	100	0	0	0	0	0	N		0	0	N	
Break/Cafeteria/Meeting Room	135	150	1	0	0	3600	0	3600	1.25	4500	1	5	1	1	2	Y	45	0	0	Y	<ul style="list-style-type: none"> • Provide area for large number of microwaves, large refrigerators, counter top, base and wall cabinets. • Provide infrastructure for A/V for occasional meetings of 150.
Men's Lockers/Shower	137	0	1	0	0	500	0	500	1.25	625	0	0	0	0	0	Y	45	0	0	N	Provide 1 locker per floor worker per shift. Lockers are 2-tier. Inshower areas only, provide PT floor and CT wall tile.
Women's Lockers/Shower	138	0	1	0	0	500	0	500	1.25	625	0	0	0	0	0	Y	45	0	0	N	Provide 1 locker per floor worker per shift. Lockers are 2-tier. Inshower areas only, provide PT floor and CT wall tile.
Lactation Room	140	0	1	0	0	100	0	100	1.25	125	1	0	0	0	0	N		0	0	Y	<ul style="list-style-type: none"> • Provide wall-mounted sink. • Card Reader
Smoking Pavilion		0	1	0	0	200	0	200	1	200	0	0	0	0	0	N		0	0	N	Not included in building footprint. Near Break Room.
Union Representative's Office	139	1	1	0	0	100	0	100	1.25	125	1	0	1	2	0	Y	40	0	1	N	
Staff Entry Vestibule	136	0	1	0	0	100	0	100	1.25	125	1	4	0	0	0	Y	45	0	0	N	
Total		151						9370		11713	5	13	2	3	2			0	1		

Notes:

Key:

Sound Insulation: Space has a STC factor rating. Details in Section 7.4 of the SFO.

Secure Area: Space has special requirements in Handbook 0730, or specific needs from customer. Leavenworth wants card readers on all doors. Room details in Schedule B, E, and Doors.

Department 14 Name: Controlled Substances

Stations or Space Required	Space Identification #	Number of Occupants	Proposed # of Stations/Rooms	Station Type		Area Required (per Station/Room)	Additional space	Total Area	Circulation Factor	Total Area	High Density TCO	Std Density TCO	# of computers	# of monitors	Cable	Sound Insulation	STC Rating	Multi-Function Device	Printer	Secure Area	Notes: Include any special finishes, acoustical requirements, HVAC requirements, lighting, adjacent requirements, casework, security requirements, special equipment, etc.
				PO/A	WS																
Controlled Substances, Bulk Storage and Replenishment	CS	5	1	1	5	6650	0	6650	1	6650	2	10	5	5	0	N	0	N	1	Y	Handbook 0730
TOTAL		5						6650		6650	2	10	5	5	0	0			1		

Notes:

Key:
Sound Insulation: Space has a STC factor rating. Details in Section 7.4 of the SFO.
Secure Area: Space has special requirements in Handbook 0730, or specific needs from customer. Leavenworth wants card readers on all doors. Room details in Schedule B, E, and Doors.