

DEMOLITION PLAN LEGEND

- EXISTING PARTITION TO REMAIN
- EXISTING PARTITION TO BE REMOVED
- EXISTING DOOR & FRAME TO REMAIN
- EXISTING DOOR, FRAME & PARTITION TO BE REMOVED
- EXISTING DOOR & FRAME TO BE REMOVED
- EXISTING MILLWORK TO REMAIN
- EXISTING MILLWORK TO BE REMOVED
- EXISTING WINDOW TO REMAIN
- EXISTING WINDOW TO BE REMOVED
- EXISTING FIXTURES TO REMAIN
- EXISTING FIXTURES TO BE REMOVED
- DESCRIPTIVE NOTE FOR AREA TO BE REMOVED
- AREA NOT IN CONTRACT


NOTE: ALL SYMBOLS MAY NOT BE USED

GENERAL DEMOLITION PLAN NOTES

- A. CONTRACTOR SHALL COORDINATE DEMOLITION WORK WITH ALL TRADES, FOR ITEMS SHOWN TO BE REMOVED ON THIS PLAN. GENERAL CONTRACTOR SHALL ALSO COORDINATE WITH ALL TRADES, THE REMOVAL REINSTALLATION, AND/OR REWORKING OF THE EXISTING FINISHES AS REQUIRED FOR THE ROUTING OF EXISTING/NEW SERVICES INTO THE PROJECT AREA.
- B. PRIOR TO THE START OF DEMOLITION, CONTRACTOR SHALL WALK TO SPACE WITH THE ARCHITECT AND C.O.R. TO IDENTIFY ANY ITEMS TO BE TURNED OVER TO THE GOVERNMENT.
- C. CONTRACTOR SHALL REMOVE ALL WINDOW COVERING AND ACCESSORIES COMPLETE.
- D. ANY ITEMS DAMAGED BY THE CONTRACTOR OR BY PERSONS UNDER THE SUPERVISION OF THE CONTRACTOR THAT ARE NOT INDICATED TO BE REMOVED OR DEMOLISHED SHALL BE REPAIRED/REPLACED TO LIKE NEW CONDITION AT THE CONTRACTORS EXPENSE.
- E. SEE CEILING DEMOLITION PLANS (IF APPLICABLE) AND MEP DRAWINGS FOR ADDITIONAL INFORMATION.
- F. CONTRACTOR SHALL PROVIDE NEGATIVE AIR PRESSURE IN THE AREA BEING MODIFIED TO PREVENT THE SPREAD OF AIRBORNE DUST/PARTICLES TO OTHER OCCUPIED AREAS OF THE MEDICAL CENTER, SEE SPECIFICATIONS.
- G. GENERAL CONTRACTOR SHALL PROVIDE CONSTRUCTION AND WARNING SIGNS AS PER THE SPECIFICATIONS.
- H. CONTRACTOR SHALL MAINTAIN THE EXISTING BUILDING IN A WATERTIGHT STATE THROUGHOUT CONSTRUCTION. ANY DAMAGE CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO BE LIKE NEW AND SHALL MATCH NEW CONSTRUCTION.
- I. CONTRACTOR SHALL MAINTAIN A FULLY SEALED ENTRY POINTS TO THE ROOMS AND/OR AREAS BEING RENOVATED. ROOMS MUST BE SEALED TO PREVENT THE TRANSFER OF DUST AND DEBRIS TO ADJACENT SPACES.
- J. GENERAL CONTRACTOR SHALL MAINTAIN WALK-OFF (STICKY) MATS ON BOTH SIDES OF THE ENTRY POINTS TO THE ROOMS AND/OR AREAS BEING RENOVATED. CHANGE MATS REGULARLY AND AS DIRECTED BY THE VA INFECTION CONTROL STAFF TO PREVENT THE TRANSFER OF FOOT TRAFFIC DUST AND DEBRIS.
- K. EXISTING SPRINKLER SYSTEM SHALL REMAIN LIVE AND FUNCTIONAL DURING ALL PHASES OF CONSTRUCTION. CONTRACTOR SHALL TAKE GREAT CARE TO NOT DAMAGE ANY EXISTING HEADS OR PIPING, UNLESS OTHERWISE INDICATED ON FIRE PROTECTION DRAWINGS.
- L. CONTRACTOR SHALL SALVAGE ALL AUTOMATIC PAPER TOWEL DISPENSERS, SOAP DISPENSERS AND TURN OVER TO THE OWNER.

DEMOLITION PLAN NOTES 1

- 1. REMOVAL OF CEILING IN THIS AREA, IN PART OR IN WHOLE. REPAIR/REPLACE CEILING AS REQUIRED TO PERFORM WORK ABOVE CEILING.



F1 FIRST FLOOR DEMOLITION PLAN  
1/8" = 1'-0"

FULLY SPRINKLERED  
BID DOCUMENTS (PART B)

<div>ISSUED FOR BID</div> <div>Revisions</div>	<div>09-07-17</div> <div>Date</div>	<div>VA WESTERN NEW YORK HEALTHCARE SYSTEM</div> <div>3495 BAILEY AVENUE</div> <div>BUFFALO, NEW YORK 14215</div>	<div>paradigm</div> <div>Architecture   Engineering   Design-Build</div> <div>200 Envoy Circle, Suite 201 Louisville, KY 40299</div> <div>www.paradigmusa.com</div>	<div>7 Feb 2018</div> <div>STATE OF KENTUCKY</div> <div>BLAINE CAMIEL</div> <div>VAN GANSBEKE</div> <div>24788</div> <div>PROFESSIONAL ENGINEER</div>	<div>CARDIOLOGY MANAGER</div> <div>DATE</div>	<div>ENGINEERING MANAGER</div> <div>DATE</div>	<div>Drawing Title</div> <div>FIRST FLOOR DEMOLITION PLAN</div>	<div>Project Title</div> <div>BUFFALO GU AHU</div>	<div>Date</div> <div>09-07-2017</div>	<div>Office of Facilities</div> <div>Department of Veterans Affairs</div>
	<div>INFECTION CONTROL</div> <div>DATE</div>				<div>CARELINE MANAGER</div> <div>DATE</div>	<div>MEDICAL CENTER DIRECTOR</div> <div>DATE</div>	<div>Building Number</div> <div>1</div>	<div>Checked</div> <div>KLP</div>	<div>Drawn</div> <div>BLM</div>	
					<div>SAFETY OFFICER</div> <div>DATE</div>	<div>CHIEF OF STAFF</div> <div>DATE</div>	<div>ASSOCIATE MEDICAL CENTER DIRECTOR</div> <div>DATE</div>	<div>Location</div> <div>V.A.M.C. BUFFALO, NEW YORK</div>		