

three inches = one foot
one and one-half inch = one foot
one inch = one foot
three-quarters inch = one foot
one-half inch = one foot
three-eighths inch = one foot
one-quarter inch = one foot
one-eighth inch = one foot

NOTES

- A. REFER TO DWG. M-001 FOR MECHANICAL ABBREVIATIONS, SYMBOLS, AND GENERAL NOTES RELATED TO THIS SHEET.
- B. ALL EXISTING PIPING, DUCTWORK, SPRINKLERS, CONDUIT, LIGHTING OR OTHER CONSTRUCTION SHALL BE RELOCATED AS REQUIRED FOR ALL DEMOLITION AND INSTALLATION WORK.

ROOM AIR BALANCE SCHEDULE																					
ROOM NO.	ROOM NAME	ROOM S.F.	INDIVIDUAL ROOM TEMP. CONTROL	SUPPLY					RETURN					ROOM AIR FLOW	ROOM AIR BALANCE	NET INFILTRATION	NET EXFILTRATION	REMARKS			
				REQUIRED		FINAL NEW DESIGN	CURRENT /ACTUAL DESIGN	ORIGINAL DESIGN	# OF AIR DEVICES	REHEAT COIL	SUPPLY FAN	RETURN OR EXHAUST [R/E]	ROOM AIR FLOW						# OF DEVICES	AIR DEVICE MARK	RETURN OR EXHAUST FAN
				CFM	AC	CFM	CFM	CFM					CFM								
200C-1	CORRIDOR	657	N	394	4/2	---	0	0		—	AH-1	E	335		EF-___	X	+		59		
200C-2	CORRIDOR	300	N	180	4/2	---	0	0		—	AH-1	E	153		EF-___	X	+		17		
200C-3	CORRIDOR	243	N	146	4/2	---	0	0		—	AH-1	E	124		EF-___	X	+		18		
203	STORAGE	113	N	68	4/-	70	0	0		—	AH-1	E	58		EF-___	X	+		10		
204	STORAGE	110	N	66	4/-	70	0	300		RH-17	AH-1	E	56		EF-___	X	+		10		
205	OFFICE	202	Y	121	4/2	125**	394	0		RH-12	AH-1	E	121		EF-___	X	0				
206	OFFICE	213	Y	128	4/2	130**	0	0		—	AH-1	E	128		EF-___	X	0				
208	MECHANICAL	284	N	—	—	170	172	250		RH-17	AH-1	E	—		EF-___	X	0				
209	PATIENT CHECK-IN	127	Y	98	6/2	120	68	280		RH-18	AH-1	E	115		EF-___	X	—	17			
210	WAITING	341	Y	260	6/2	475	316	845		RH-19	AH-1	E	307		EF-___	X	—	47			
21	BREAK ROOM	401	Y	205	4/2	265	0	0		—	AH-1	E	241		EF-___	X	—	36			
210-1	CLEAN STORAGE	18	N	10	4/-	---	0	0		—	AH-1	E	8		EF-___	X	+				
210-2	CHANGING	31	Y	19	4/-	---	0	0		—	AH-1	E	19		EF-___	X	0				
210-3	RESTROOM	43	N	55	10/-	---	0	0		—	AH-1	E	65		EF-___	X	—	10			
211C	PROCEDURE	243	Y	607	15/3	610	519	845		RH-19	AH-1	E	515		EF-___	X	+		92		
211C-1	WORK ROOM	185	Y	111	4/2	155	268	845		RH-19	AH-1	E	111		EF-___	X	0				
212	OFFICE	252	Y	151	4/2	270	252	450		RH-19	AH-1	E	151		EF-___	X	0				
213	OFFICE	208	Y	125	4/2	125	404	415		RH-16	AH-1	E	125		EF-___	X	0				
214	CYSTO	283	Y	658	15/3	660	305	450		RH-15	AH-1	E	559		EF-___	X	+		99		
214-2	CLEAN CORRIDOR	78	N	70	6/2	80	165	550		RH-15	AH-1	E	60		EF-___	X	+		15		
214-3	SCRUB	126	Y	151	8/2	155	122	230		RH-14	AH-1	E	106		EF-___	X	++		45		
215	CYSTO	296	Y	740	15/3	740	325	450		RH-14	AH-1	E	629		EF-___	X	+		111		
215C-3	PROFUSION	97	Y	74	6/2	90	0	200		RH-13	AH-1	E	88		EF-___	X	—		14		
231	WAITING	345	Y	264	6/2	310	131	0		RH-12	AH-1	E	310		EF-___	X	—		46		
TOTAL CFM				4701		4620(5000)	3441	6110	TOTAL CFM				4384	TOTAL CFM				170	476		

NOTES:

- * CURRENT AHU PROVIDES 5,580 CFM FROM SUPPLY DISCHARGE (38% DUCT LOSS).
- ** CONFIRM AIRFLOW/DUCT TO THESE SPACES.
- *** AREAS NOT INCLUDED IN FINAL DESIGN AS NOT SERVICED WITH DISTRIBUTION DUCTWORK CURRENTLY.

AIR HANDLING UNIT SCHEDULE																	
MARK	LOCATION	AREA AND/OR BLDG SERVED	TYPE	AIR FLOW	AIR FLOW			SUPPLY FAN MARK	RETURN OR RELIEF FAN MARK	EXHAUST FAN MARK	PREFILTER MARK	AFTER FILTER MARK	FINAL FILTER MARK	HEAT RECOVERY MARK	PRE-HEAT COIL MARK	CHILLED WATER COIL MARK	REDUNDANT COOLING COIL MARK
					SUPPLY CFM	MIN OA CFM	RETURN CFM										
AH-1	AH-1	GU	AH-1	CV	5,500	5,500	0	SF1, SF2	N/A	N/A	PF-1&PF-2	AF-1	--	--	HC-1	CC-1	--
NOTES:														SOUND DATA			
1. BASIS OF DESIGN IS HUNT-AIR.														63	125	250	500
														89	81	79	88

FAN SCHEDULE																							
MARK	LOCATION	AREA AND/OR BLDG SERVED	SYSTEM AND/OR SERVICE	AIR FLOW	TSP	FAN								MOTOR ELECTRICAL					CONTROL SEQUENCE	REMARKS			
						CFM	IN. W.C.	FAN	WHEEL	CLASS	ARRANGEMENT, ROTATION, AND DISCHARGE	DIAMETER	MIN. % EFF	DRIVE	FAN MAX. RPM	NOMINAL POWER		PHASE			VOLT	RPM	SPEED CONTROL
																BHP	HP						
SF-1	AH-1	GU	SUPPLY	2,756	7.5	PLENUM	16.5	CLASS H		16.5	64	DIR	3946	4.71	5	3	208	2986	VSD	MH502	NOTE 1, 2		
SF-2	AH-1	GU	SUPPLY	2,756	7.5	PLENUM	16	CLASS H		16	64	DIR	3946	4.71	5	3	208	2986	VSD	MH502	NOTE 1, 2		

NOTES:

1. (2) FAN ARRAY.
2. VSD FACTORY INSTALLED.

AIR FILTER SCHEDULE											
MARK	LOCATION	AREA AND/OR BLDG SERVED	SYSTEM AND/OR SERVICE	MERV RATING	AIR FLOW	APD		HOUSING TYPE	CARTRIDGES		REMARKS
						INITIAL	CHANGEOVER		#	SIZE	
										ARRANGEMENT	
					CFM	IN	IN		IN		
PF-1	AH-1	GU	SUPPLY	7	5,500	0.2	0.4	FRAME		MANUFACTURER	
PF-2	AH-1	GU	SUPPLY	11	5,500	0.2	0.6	FRAME		MANUFACTURER	
AF-1	AH-1	GU	SUPPLY	14	5,500	0.2	0.75	FRAME		MANUFACTURER	


AIR DEVICE SCHEDULE									
MARK	TYPE	AIR FLOW		MAX APD	MOUNTING	PANEL/FRAME SIZE	NECK SIZE	NC	DAMPER
		MIN. CFM	MAX. CFM						
		CFM	CFM	IN WG		IN x IN	IN		
CD-1	SUPPLY	100	800	0.15	LAY-IN	24 x 24	VARIES	<35	YES

HVAC DESIGN DATA						
DESIGN CONDITIONS	SUMMER			WINTER		
	TEMP	WET BULB TEMP	% HUMIDITY	TEMP	DEWPOINT TEMP	% HUMIDITY
	*F	*F		*F	*F	
BUFFALO	92	75	48%	-10	18.7	--

ISSUED FOR BID	9-7-2017
Revisions	Date

VA WESTERN NEW YORK HEALTHCARE SYSTEM
3495 BAILEY AVENUE
BUFFALO, NEW YORK 14215

paradigm
Architecture | Engineering | Design-Build
200 Envoy Circle, Suite 201 Louisville, KY 40299
www.paradigmusa.com



MANAGER	DATE	ENGINEERING MANAGER	DATE
INFECTION CONTROL	DATE	MANAGER	DATE
SAFETY OFFICER	DATE	CHIEF OF STAFF	DATE

Drawing Title	Project Title
MECHANICAL HVAC SCHEDULES	BUFFALO GU AHU
MEDICAL CENTER DIRECTOR	Building Number 1
ASSOCIATE MEDICAL CENTER DIRECTOR	Location V.A.M.C. BUFFALO, NEW YORK

Date	09-07-2017
Station No.	528
Checked KLP	Drawn JDM
17-S06-MH601	

FULLY SPRINKLERED
BID DOCUMENTS
FOR CONSTRUCTION

