

RFI # 3

1. In going through the door schedule vs. the hardware schedule. I found that there is no hardware set listed on the door schedule for opening numbers 1F122, 1F123 and 1F125 nor do those openings appear in the hardware schedule. Also, openings 1F122C and 1F124C are shown on the door schedule as receiving hollow metal frames. I'm not sure that these sliding doors require a hollow metal frame. If they do, it would only be a cased opening frame. Would you please clarify?

HW for DOOR 1F122 is SET #6.

HW for DOOR 1F123 is SET #5.

HW for DOOR 1F125 is SET #5, but substitute "*Mechanical Key Pad Lock*" – for "*Office/entry Lock*" shown. Provide Simplex L1011 (or equal) Push Button Combination Lock, Heavy Duty with integral manual key override. Doors 1F122C and 1F124C delete reference to new hollow metal frame for these openings. Contractor Attention is drawn to the following:

SECTION 08 42 43, SLIDING GLASS DOORS, Article 2.3, SLIDING DOOR ASSEMBLIES, Para. 'A'.
General: *Provide manufacturer's standard factory-glazed ICU/CCU entrances including door leaves, sidelites, framing, headers, carrier assemblies, roller tracks, and accessories required for a complete installation.*