

Salient Characteristics

Artwork Prints on Acrylic Panels, ZSports Inc, or Equal

1. General

Art work printed on acrylic panels, mounted to wall with decorative aluminum stand-offs, in entire campus.

2. Warranty Requirements

- a. Manufacturer must offer a minimum 1 year warranty that product is free from defects in materials and workmanship (includes shipping, parts and labor for the repair or replacement of defective item.)

3. Dimensions and Features

- a. Images: photographs of nature and other subjects suitable for a healthcare environment
- b. Height: varies from about 32" - 34"
- c. Width: varies from about 40" - 42" and 62" – 66"
- d. Depth: About 1-1/2", including stand-offs
- e. Acrylic must be a minimum of 1/4" thick, flawless clear, with no flecks or specks
- f. Aluminum stand-offs must be a minimum of 1" in diameter and height, with a brushed silver finish, and include appropriate anchors for drywall. Stand-offs have 3/8" diameter screws and holes, and caps are 3/8" in height

4. Construction Method

- a. Acrylic panels printed with Fuji Crystal Archive process for archival reproductions: the Light Jet digital photo process exposes the Fuji Crystal Archive photo paper using lasers, and is processed to create a high quality archival print. The image is then face mounted to acrylic using UV optically clear adhesive, creating a crystal clear image on the acrylic. The edges of the acrylic are diamond polished.
- b. Panels have pre-drilled holes, sized to match stand-off hardware, at four corners

5. Surface Materials

- a. Flawless acrylic imprinted with image as described above, with aluminum stand-offs

6. Packing for Shipping

- a. Corrugated cardboard is used to cover mounting hardware to protect adjacent artwork in packing and transport. Each piece of art is bagged separately with 2mm thick bags. Art is packed with shrink wrap for additional protection. Cardboard corners are used to keep art separate and avoid damage during shipping.