



- REFLECTED CEILING PLAN
DEMOLITION NOTES**
1. SEE DWG. AR-101, DEMOLITION PLAN, FOR FURTHER NOTES
 2. AT AREAS SHOWN, REMOVE ENTIRE EXISTING IN ITS ENTIRETY.
 3. REMOVE EXISTING LIGHT FIXTURES.
 4. REMOVE EXISTING SUSPENDED CEILING GRID AND TILE.
 5. EXISTING SPRINKLER HEADS TO REMAIN AND BE RELOCATED TO NEW CEILING HEIGHTS.
 6. EXISTING SUPPLY DIFFUSERS TO BE REMOVED. EXISTING HVAC DUCTWORK TO REMAIN. SEE DWG. MH-101 FOR EXTENT OF NEW HVAC WORK.
 7. REMOVE EXISTING GYPSUM BOARD SOFFITS AND FACIAS.
 8. EXIST WIFI SYSTEM, CURRENTLY INSTALLED ABOVE THE EXISTING SUSP. CLG., SHALL REMAIN AND/OR REMOVE & REINSTALLED AFTER NEW CEILING IS IN PLACE.
 9. SEE ELECTRICAL DRAWINGS FOR THE EXTENT OF ELECTRICAL ITEMS TO REMAIN

REFLECTED CEILING PLAN LEGEND	
	EXISTING 2'x4' ACOUSTIC CEILING TILE TO REMAIN
	EXISTING 2'x4' RECESSED FLUORESCENT LIGHTING TO REMAIN
	EXISTING 2'x2' RECESSED FLUORESCENT LIGHTING TO REMAIN
	EXISTING SUPPLY DIFFUSER TO REMAIN
	EXISTING RETURN GRILL TO REMAIN
	EXISTING RECESSED DOWNLIGHTING TO REMAIN
	EXISTING CEILING HEIGHT, A.F.F.
	SMOKE DETECTOR TO BE REMOVED AND REINSTALLED
	SPRINKLER HEAD SEE FP PLANS
	HATCHED AREA INDICATES EXISTING CEILING CONST TO BE REMOVED. ALL CEILING ELEMENTS (I.E. LT FIXTURES, DIFFUSERS, REGISTERS, SPRINKLER HEADS) TO BE REMOVED AND STORED FOR REUSE.
	ACOUSTIC CEILING TILE TO BE REMOVED
	2'x4' RECESSED FLUORESCENT LIGHTING TO BE REMOVED
	SUPPLY DIFFUSER TO BE REMOVED
	EXIT SIGN TO BE REMOVED
	SPEAKER TO BE REMOVED AND REINSTALLED
	WIFI STATION TO BE REMOVED AND REINSTALLED

DEMOLITION REFLECTED CEILING PLAN
SCALE: 1/4" = 1'-0"

Revisions		Date		Professional Seal		DCS INFRASTRUCTURE, LLC DESIGN & CONSTRUCTION SERVICES 33 GRANT STREET MT. HOLLY, N.J. 08060 609-351-1486 3239 ROUTE 112 BLDG. 8, STE. 48 MEDFORD, N.Y. 11763 631-320-1706		Drawing Title DEMOLITION REFLECTED CEILING PLAN Approved: _____ Approved: _____		Project Title VAMC WILMINGTON, DE RENOVATE CLINICAL ADDITION and 1st FLOOR ELEVATOR LOBBIES Building Number 01 Checked TK Drawn CW Location WILMINGTON, DE		Date 31 MARCH 2011 Project No. 460-10-010 Drawing No. AR-102 Dwg. 6 of 14		100% SUBMISSION WILMINGTON VAMC Department of Veterans Affairs	
------------------	--	-------------	--	--------------------------	--	---	--	--	--	--	--	--	--	---	--