

## KEYNOTES

- 3.003 EXISTING CONCRETE SLAB.
- 3.004 EXISTING CONCRETE DECK.
- 3.009 EXISTING PRECAST CONCRETE PLANKS.
  
- 5.001 EXISTING STRUCTURAL STEEL FRAMING MEMBER.
- 5.010 STRUCTURAL STEEL: FRAMING MEMBER; REFER TO STRUCTURAL DRAWINGS.
  
- 5.801 EXISTING EXPANSION JOINT COVER ASSEMBLY.
  
- 6.002 WOOD BLOCKING: DIMENSIONAL LUMBER; SIZE AS REQUIRED; REFER TO SCHEDULE FOR TREATMENT.
  
- 7.001 EXISTING ROOF CONSTRUCTION.
- 7.840 FIRESTOPPING: PACKING MATERIAL; REFER TO SPECIFICATIONS
- 7.841 FIRESTOPPING: SEALANT; REFER TO SPECIFICATIONS.
- 7.900 JOINT SEALANT: REFER TO SCHEDULE; PROVIDE BACKER ROD OR BOND BREAKER.
  
- 9.101 METAL STUD FRAMING: 1-5/8" STUD; 16" O.C. SPACING; 20 GAUGE UNLESS NOTED OTHERWISE; ANCHORAGE TO SUIT APPLICATION.
- 9.102 METAL STUD FRAMING: 2-1/2" STUD; 16" O.C. SPACING; 20 GAUGE UNLESS NOTED OTHERWISE; ANCHORAGE TO SUIT APPLICATION.
- 9.103 METAL STUD FRAMING: 3-5/8" STUD; 16" O.C. SPACING; 20 GAUGE UNLESS NOTED OTHERWISE; ANCHORAGE TO SUIT APPLICATION.
- 9.105 METAL STUD FRAMING: SEE FLOOR PLAN AND PARTITION TYPES FOR METAL STUD SIZE.
- 9.106 METAL STUD FRAMING: 6" STUD; 16" O.C. SPACING; 20 GAUGE UNLESS NOTED OTHERWISE; ANCHORAGE TO SUIT APPLICATION.
- 9.112 METAL STUD FRAMING: SHAFTWALL "J" TRACK.
- 9.116 METAL STUD FRAMING: HEADER; (2) - 6" - 18 GA. HEADER WITH 4" - 20 GA. RUNNERS TOP AND BOTTOM. PROVIDE PLYWOOD BLOCKING BETWEEN METAL STUDS AS REQUIRED.
- 9.120 METAL STUD FRAMING: STUD RUNNER: SIZE TO MATCH METAL STUDS.
- 9.121 METAL STUD FRAMING: DOUBLE STUD RUNNER: FOR DEFLECTION RELIEF.
- 9.131 METAL STUD FRAMING: CLIP ANGLE; CONNECT HEADER TO NEW LIGHT GAUGE MEMBER EA. END W/ LIGHT GAUGE CLIP ANGLES PER MANUFACTURER'S RECOMMENDATIONS.
- 9.132 METAL STUD FRAMING: CLIP ANGLE; CONNECT HEADER TO EXISTING STEEL BEAM WEB AT EACH END W/ LIGHT GAUGE CLIP ANGLES PER MANUFACTURER'S RECOMMENDATIONS.
- 9.143 METAL STUD FRAMING: LATERAL BRACING STRAP; 14 GA. GALVANIZED; 6" WIDE AT 24" O.C..
- 9.250 GYPSUM BOARD: 5/8" THICK; TYPE "X".
- 9.253 GYPSUM BOARD: 1" THICK; SHAFT LINER PANEL.
- 9.260 GYPSUM BOARD ACCESSORY: ACOUSTICAL SEALANT.
- 9.261 GYPSUM BOARD ACCESSORY: ACOUSTICAL INSULATION: SOUND ATTENUATION BATTS; THICKNESS AS SPECIFIED.
- 9.263 GYPSUM BOARD ACCESSORY: CORNER BEAD.
- 9.510 ACOUSTICAL CEILING PANELS AND GRID.
  
- 10.650 FOLDING PANEL PARTITION AND TRACK ASSEMBLY. PROVIDE ANCHOR SPACING TO STEEL CONTRACTOR.