

### **Ramada Sample Illustration and Specifications Below**

Contractor shall provide all the labor, material, equipment and supervision necessary for the following:

Contractor shall provide all the labor, material, equipment and supervision necessary to purchase and install a 20'L x 20'W x 10'H Wood Ramada pre specification provided. Ramada shall be install on a 21'x 21' x 6" poured in place concrete pad with a 12" x 12" toe down continuous on all sides of pad. The toe down shall have 4 runs of #3 rebar stacked and evenly spaced in the center of the toe down. The concrete pad shall be 3000 PSI concrete, with # 3 rebar in both directions placed 18" On Center, the sub-base shall be 2 ea 3" lift of ABC compacted to 95% density

### **Sample Illustration and Specifications Below:**



### **Basic Specifications:**

- Product Type: Pavilion
- Style: Savannah (Rectangle)
- Roof: Single Roof
- Material: Wood
- Size: 20' x 20'
- Height: 126 in.
- Approx. Area: 400 Sq. Ft.

**Basic Features:**

- Glue Laminated Pitch & Tapered Curved Beams
- Treated Glue Laminated Columns
- 2 x 8 Tongue and Groove Roof Decking
- #1 Grade 2x6 Treated SYP Fascia
- Prime Painted Steel Connection Plates
- 3:12 Roof Pitch
- Engineered to Local Code

**Sample of Site Area Below (Not to Scaled and Informational Only):**

