

Section 2 - Salient Characteristics

Shower Curtains with Shower Shield & Shower Curtain Roller Rings , or Equal

1. General

Shower Shield shower curtains without mesh are fabricated flat with grommets at the heading spaced every 6" & Roller Rings in student shower rooms and apartment living shower rooms at BLDG 500 – Polytrauma Rehabilitation and Blind Center.

2. Warranty Requirements

a. Manufacturer must offer a one-year warranty that product is free from defects in materials and workmanship (includes shipping, parts and labor for the repair or replacement of defective item.)

3. Technical Specification and Code Requirements

a. Meets NFPA 701 & MVSS-302 Fire Retardant Tests.

4. Environmental Features

a. Product must be designed and constructed of materials that do not present a significant environmental and human health risk.

5. Dimensions and Features

a. Shower Curtain

i. Dimensions

- QTY: 1 - Type A Track Length: 59"
- Type A Curtain Finished Length: 90"
- QTY: 14 - Type B Track Length: 94"
- Type B Curtain Finished Length: 90"
- QTY: 14 - Type C Track Length: 89"
- Type C Curtain Finished Length: 90"
- QTY: 2 - Type D Track Length: 61"
- Type D Curtain Finished Length: 90"
- QTY: 2 - Type E Track Length: 94"
- Type E Curtain Finished Length: 102"
- QTY: 1 - Type F Track Length: 94.5"
- Type F Curtain Finished Length: 90"
- QTY: 4 - Type G Track Length: 93.5"
- Type G Curtain Finished Length: 90"
- QTY: 1 - Type H Track Length: 96"
- Type H Curtain Finished Length: 90"
- QTY: 6 - Type I Track Length: 88"
- Type I Curtain Finished Length: 90"

ii. Features

- Superior Stain and Odor Release Properties
- Fire Retardant
- Antimicrobial
- Specially formulated to resist mildew growth on the surface
- 100% Polyester, water repellant
- Piece dyed and dual-sided prints
- Pattern – Weave (Dobby)

b. Shower Curtain Roller Rings

- Dimensions: 1.52" w x 2.8"L x .09"D
- Finishes: Polished Chrome
- Roller balls and ring are composed of iron.
- Designer 5 Ball Nickel Plated Shower Rings
- Designed to accommodate up to a standard 1" rod. – verify compatibility with installed shower curtain rods and hardware before ordering.

6. **Construction Method**

- a. Finished length of curtain should be about 1" off floor
- b. Fullness shall be approximately 15%
- c. ½" nickel plated brass, rust resistant metal grommets spaced 6" on center. Color: Silver
- d. Shower curtain top hem to be triple-turned hem over nylon tape for rugged wear.
- e. Vertical striped patterns are sewn railroaded to ensure the integrity of the design
- f. All stitching is performed with lock stitching sewing machines.
- g. Shower curtain are to be seamless when possible with sanitary "no scum" side and bottom edges.

7. **Surface Materials**

- a. Curtains available in a variety of minimum 8 colors and nature-inspired patterns which coordinate with building interiors

8. **Miscellaneous**

- a. Cleaning: Machine Washable to 160F, but do not use chlorine bleach or fabric softener. Tumble dry to 140F.