



EXISTING PARTIAL PLAN  
SCALE: 1/4" = 1'-0"

# DEMOLITION NOTES: ARCHITECTURAL

1. REMOVE DOOR AND HARDWARE, HM DOOR FRAME TO REMAIN
2. REMOVE METAL WALL AND BASE CABINETS
3. REMOVE GYPSUM BOARD SOFFIT
4. REMOVE ACOUSTICAL TILE CEILING AND GRID
5. REMOVE VINYL COMPOSITION TILE FLOORING
6. REMOVE COVE BASE

## PLUMBING

1. DISCONNECT AND REMOVE BASE CABINET SINK, INCLUDING SUPPLY AND WASTE PIPING
2. DISCONNECT AND REMOVE SERVICE SINK AND ELEVATED PLATFORM, INCLUDING SUPPLY AND WASTE PIPING
3. REMOVE CW AND HW PIPE BACK TO EXISTING MOP SINK THAT IS TO REMAIN. SO AS NOT TO CREATE DEAD LEGS, DO NOT CAP PIPE IN PLACE, INSTEAD REMOVE AND INSTALL NEW PIPE AND FITTINGS ON SUPPLY PIPING TO RECONNECT MOP SINK.
4. REMOVE SW PIPE FROM SINK CABINET OVER TO MOP SINK THAT IS TO REMAIN. REMOVE BRANCH FITTINGS FOR CABINET SINK AND UTILITY SINK. INSTALL NEW PIPE AND FITTINGS TO RECONNECT MOP SINK VENT.

## HVAC

1. REMOVE EGGRATE EXHAUST GRILLE. SEE NEW PLAN FOR RELOCATION.

## ELECTRICAL

1. REMOVE 2X4 LIGHT TROFFER
2. REMOVE TOGGLE SWITCH