



NEW WORK PARTIAL PLAN
SCALE: 1/4" = 1'-0"

GENERAL NOTES:

1. NEW DOOR 3'-0"x7'-0" C-LABEL SOLID CORE WOOD DOOR, ROTARY CUT RED OAK, CLEAR FINISH
2. HARDWARE:
 - A. BEST LEVER STYLE MORTISE LOCKSET, PRIVACY FUNCTION, WITH OCCUPANCY INDICATOR 45H-0-L-3-R-626-LH-VIN
 - B. BALANCE OF HARDWARE TO MATCH EXISTING. OMIT CLOSER.
3. 24"X72"X1/4" TEMPERED GLASS MIRROR WITH STAINLESS STEEL CHANNEL FRAME
4. PLASTIC LAMINATED WALL CABINET WITH STORAGE SEATING:
 - A. WILSONART 7054-60 WILD CHERRY, WITH COLOR MATCHED PVC EDGE BANDING ON DOORS AND DRAWERS
 - B. ARRAY FROST A901 SOLID SURFACE MATERIAL STORAGE SEATING TOP 2" OVERALL THICKNESS AND BACK AND SIDE SPLASH 1/2" THICKNESS.
 - C. ADA RECESSED PULLS ON DOORS AND DRAWERS
 - D. FULL EXTENSION BALL BEARING SLIDES ON DRAWERS
 - E. CONCEALED HINGES ON DOORS, MINIMUM 3 ON EACH
 - F. KEYED TUMBLER LOCK ON DOORS, KEYED SEPARATE
5. PAINT FINISH ON WALLS EGGSHELL, WITH COLOR TO BE DETERMINED. PAINT FINISH ON TRIM SATIN, WITH COLOR TO BE DETERMINED. PAINT FINISH ON BOTTOM OF SOFFIT FLAT, CEILING WHITE.
6. 4" FLEXCO ZEPHYR COVE BASE.
7. VINYL PLANK FLOORING MANNINGTON NATURE'S PATH 3" HERITAGE CHERRY 12103
8. SOFFIT - 5/8" TYPE X GYPSUM BOARD ON 3 5/8" 22 GAUGE METAL STUD ON 16" CENTERS
9. ACOUSTICAL CEILING PANEL USG 2110 RADAR
10. SUSPENSION SYSTEM USG DONN HEAVY DUTY DX/DXL26, SEISMIC MOUNTING