

SECTION 09 06 00  
SCHEDULE FOR FINISHES

SECTION 09 06 00 - SCHEDULE FOR FINISHES

VAMC:	STRATTON V.A. MEDICAL CENTER
Location:	ALBANY, NEW YORK
Project no. and Name:	VA 528-809 NEW EMERGENCY DEPARTMENT
Submission:	100% SUBMISSION - FINAL DESIGN
Date:	<del>June 13, 2011</del> (Addendum 3 - July 31, 2012)

SECTION 09 06 00  
SCHEDULE FOR FINISHES

**PART 1 - GENERAL**

**1.1 DESCRIPTION**

This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

**1.2 MANUFACTURERS**

Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer for finish requirements.

**1.3 SUBMITALS**

Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES. Provide quadruplicate samples for color approval of materials and finishes specified in this section.

**1.4 APPLICABLE PUBLICATIONS**

- A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.
- B. MASTER PAINTING INSTITUTE: (MPI)  
2001.....Architectural Painting Specification Manual

**PART 2 - PRODUCTS****2.1 NOT USED****2.2 DIVISION 31 - EARTHWORK****A. SECTION 32 17 23, PAVEMENT MARKINGS.**

Color	Manufacturer	MFG. Color Name/No.
Yellow	-	Conform to MPI No. 97
White	-	Conform to MPI No. 97

**B. BOLLARDS**

Material	Finish	Style Name/ No.	Manufacturer	Mfg. Color Name/No.
Fiberglass Decorative Sleeve & Fiberglass Decorative Lid	Sleeve Metal: Black Sleeve Body: Warm Gray Concrete/ Resin	DSC650	Delta Scientific Corporation	Black

**C. SITE AND STREET FURNISHINGS**

Item	Style Name/No.	Finish	Manufacture	Mfg. Color Name/No.
Benches	Gretchen	Cast aluminum, powder-coated	Landscapeforms	Metal: Black Polysite: Bark
Trash Receptacles	Gretchen	Hot dipped galvanized before powder-coated	Landscapeforms	Metal: Black Polysite: Bark

**2.3 DIVISION 03 - CONCRETE****A. SECTION 03 30 00, CAST IN PLACE CONCRETE**

Surface	Finish Description
---------	--------------------

Exposed	Smooth - form
---------	---------------

## B. SECTION 03 45 00, PRECAST ARCHITECTURAL CONCRETE

Finish Color	Texture	Finish	Manufacturer	Mfg. Color Name/No.
N/A	N/A	N/A	N/A	N/A

## 2.4 DIVISION 04 - MASONRY

## A. Section 04 05 13, MASONRY MORTARING and Section 04 05 16, MASONRY GROUTING

Finish Code	Manufacturer	Mfg. Color Name
N/A	Sika Corporation USA	Warm Medium Grey

## B. Section 04 20 00, UNIT MASONRY

1. FACE BLOCK (FB)				
Finish Code	Size	Pattern	Manufacturer	Mfg. Color Name/No.
Architectural Concrete Block	16" x 24"	Ground Face Polish	Westbrook Concrete Block Co - Connecticut or Equal	GFP-351 or Equal

3. CONCRETE MASONRY UNIT (CMU)				
Type	Size	Pattern	Finish	Mfg. Color Name/No.
CMU Standard	8 x 4 x 16	N/A	N/A	-

## C. STONE MASONRY

Material	Size	Color, Texture, Finish, Grain	Pattern	Stone Source
N/A	N/A	N/A	N/A	N/A

## D. STONE FACING

Name of Stone	Color, Texture, Finish	Stone Source
N/A	N/A	N/A

## 2.5 DIVISION 05 - METALS

## A. SECTION 05 50 00, METAL FABRICATION

Item	Finish
Frames for Lead Lined Doors	Coronado Industrial Coating DTM, Semi-Gloss, "Great Plains Gold" #1077

## B. SECTION 05 51 00, METAL STAIRS:

Component	Finish	Number/Color
Newel Posts	Coronado Industrial Coating, Corotech DTM Semi Gloss Paint	984 Stone Hearth
Guard Rails	Coronado Industrial Coating, Corotech DTM Semi Gloss Paint	984 Stone Hearth
Handrails	Coronado Industrial Coating, Corotech DTM Semi Gloss Paint	984 Stone Hearth
Stringers	Coronado Industrial Coating, Corotech DTM Semi Gloss Paint	984 Stone Hearth
Risers	Coronado Industrial Coating, Corotech DTM Semi Gloss Paint	984 Stone Hearth
Underside	Coronado Industrial Coating, Corotech DTM Semi Gloss Paint	984 Stone Hearth

## C. SECTION 07 95 13, EXPANSION JOINT COVER ASSEMBLIES

	Material	Finish	Manufacturer	Model/Number
Wall Component Cover Plate Frame Gasket or Sealant (interior only)	Elastomer Seal	Custom Color	MM Systems	VSW-400 (at flat wall) VSWL-400 (at 90 degree corner)
Ceiling Component Cover Plate, Gasket or Sealant (interior only)	Elastomer Seal	White	MM Systems	VSW-400 (at GWB) VSG-400 (at AT)
Exterior Wall Cover Plate Frame Thermoplastic Joint	Aluminum	Custom Color	MM Systems	VSS 400
Floor Component	Aluminum	Clear Anodized	MM Systems	LASB-NBR-4-4-.25

## 2.6 DIVISION 06 WOOD, PLASTICS, AND COMPOSITES

## A. SECTION 06 10 00, ROUGH CARPENTRY

Item	Finish	Color
Wood Blocking and Sheathing	Fire Retardant Plywood	Natural Finish

## B. SECTION 06 20 00, FINISH CARPENTRY

1. LOBBY - ALCOVE				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E101a LOBBY	Countertop	Solid Surface Material	Corian	"Acorn"
	Countertop Supports	Solid Metal	Rakks	#EH-1818, 18"x18", 2"x2"T, ¼" Gauge
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

## 2. LOBBY - BACKSPLASH BEHIND WATER FOUNTAIN

Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E101a LOBBY	Backsplash	Solid Surface Material	Corian	Cottage Lane, 5'-4"w x 5'-0" h (V.I.F.)

### 3. RECEPTION & VITAL SIGNS COUNTER PUBLIC/PATIENT SIDE

Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E101 LOBBY, E102 WAITING	Vertical Surface	Porcelain Tile	Best Tile	Glazed, Style, Tabacco, 13"x13"
	Transaction top	Solid Surface	Corian	"Acorn"
	Porcelain Tile Trim	Metal Edges at Tile	Basis of Design: Schluter - Rondec	Satin Anod. Aluminum (AE), 3/8"
	Window Trim	Wood	-	Maple - Clear Stain
	Glazing	Tempered Glass	Clear	-
	Fin Tube Enclosure	Plastic Laminate	Nevamar	"Ochre Tempera" #TM2001T

### 4. RECEPTION COUNTER STAFF SIDE

Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E103 Reception	Transaction top	Solid Surface	Corian	"Acorn"
	Tackable Wall Panel	Fabric	CF Stinson	"Linea, lin #12, Angle"
	Wood	Stained	-	Maple Honey
	Work surface Countertop	Plastic Laminate	Wilsonart	"Crisp Zephyr" #4858-60
	Vertical Open Cabinets	Plastic Laminate	Wilsonart	"Crisp Zephyr" #4858-60
	Countertop Trim (Bullnose Edging)	Wood	-	Maple - Clear Stain

	Counter Supports	Solid Metal	Lyman Associates	Powder Coated Black - 18" x 24" with ¼" mounting holes
	Grommets for Cable Pass thru countertops	Molded-Plastic	Doug Mockett & Company, Inc.	"VG Series"/Black 3 1/2" Outside Diameter/with matching caps
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

5. POLICE WORK STATION				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E103a POLICE	Vertical Surface(s)	Plastic Laminate	Wilsonart	"Spiced Zephyr" #4859-60
	Tackable Wall Panel	Fabric	CF Stinson	"Linea, lin #12, Angle"
	Shelving	Plastic Laminate	Wilsonart	"Spiced Zephyr" #4859-60
	Work surface Countertop	Plastic Laminate	Wilsonart	"Crisp Zephyr" #4858-60
	Countertop Trim (Bullnose Edging)	Wood	-	Maple - Clear Stain
	Counter Supports	Solid Metal	Lyman Associates	Powder Coated Black - 18" x 24" with ¼" mounting holes
	Grommets for Cable Pass thru countertops	Molded-Plastic	Doug Mockett & Company, Inc.	"VG Series"/Black 3 1/2" Outside Diameter/with matching caps
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

6. VITAL SIGNS - STAFF SIDE				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
	Tackable Wall Panel	Fabric	CF Stinson	"Linea, lin #12, Angle"
	Work surface Countertop	Plastic Laminate	Wilsonart	"Crisp Zephyr" #4858-60



	Countertop Trim (Bullnose Edging)	Wood	-	Maple - Clear Stain
	Counter Supports	Solid Metal	Lyman Associates	Powder Coated Black - 18" x 24" with ¼" mounting holes
	Grommets for Cable Pass thru countertops	Molded-Plastic	Doug Mockett & Company, Inc.	"VG Series"/Black 3 1/2" Outside Diameter/with matching caps
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

7. MAIL/COPY ROOM				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E118 MAIL/COPY	Vertical Surface Mailboxes	Plastic Laminate	Wilsonart	"Crisp Zephyr" #4858-60
	Horizontal Surface Mailboxes	Plastic Laminate	Wilsonart	"Crisp Zephyr" #4858-60
	Work surface Countertop	Plastic Laminate	Wilsonart	"Crisp Zephyr" #4858-60
	Shelf Label Holder	White Plastic	Demco	C-Channel Adhesive, #WS14874370
	Countertop Trim (Bullnose Edging)	Wood	-	Maple - Clear Stain
	Shelving	Plastic Laminate	Wilsonart	"Crisp Zephyr" #4858-60
	Counter Supports	Solid Metal	Lyman Associates	Powder Coated Black - 18" x 24" with ¼" mounting holes
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

8. Offices - Nurse Manager, Physician's & Shared MD				
Room No.	Component	Material	Manufacturer	Finish/Style/Color/Size

and Name				
E122, E123, E124	Window Sill	Solid Surface	Corian	"Night Sky"

9. CONFERENCE ROOM				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E125 Conference Room	Vertical Surfaces/Cabinet/End Panel	Plastic Laminate	Nevamar	"Ochre Tempera" #TM2001T
	Adjustable Cabinet Shelves	Melamine	-	"White"
	Countertops	Solid Surface	Corian	"Cottage Lane"
	Countertop Trim (Bullnose Edging)	Wood	-	Maple - Clear Stain
	Chair rail	Plastic/Metal	IPC	#2700W Honey Nut
	Wire Pulls	Solid Metal	Amerock	AM-BP19003-SS
	Counter Support	Solid Metal	Lyman Associates	Powder Coated Black - 18" x 24" with ¼" mounting holes
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

10. KITCHENETTE				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E125a Kitchenette	Countertops	Solid Surface	Corian	"Cottage Lane"
	Backsplash	Solid Surface	Corian	"Cottage Lane"
	Integral Sink	Solid Surface	Corian	"Bisque"
	Vertical Surfaces/Cabinets	Plastic Laminate	Wilsonart	"Spiced Zephyr" #4859-60

	Shelves (Microwave Cabinet)	Plastic Laminate	Wilsonart	"Spiced Zephyr" #4859-60
	Adjustable Cabinet Shelves	Melamine	-	"White"
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"
	Wire Pulls	Solid Metal	Amerock	AM-BP19003-SS

## 11. X-RAY ROOM - PATIENT SIDE

Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E128 X-Ray Room	Countertop	Solid Surface	Corian	"Acorn"
	Backsplash	Solid Surface	Corian	"Acorn"
	Integral Sink	Solid Surface	Corian	"Bisque"
	Vertical Surfaces/Cabinets	Plastic Laminate	Nevamar	"Varnish" #VS 2003T"
	Adjustable Cabinet Shelves	Melamine	-	"White"
	Wire Pulls	Solid Metal	Amerock	AM-BP19003-SS
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

## 12. X-RAY ROOM - TECHNICAL WORKSTATION

Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E128 X-Ray Room	Countertop	Plastic Laminate	Nevamar	"Ochre Tempera" #TM 2001T
	Countertop Trim (Bullnose Edging)	Wood	-	Maple - Clear Stain
	Drawers	Plastic Laminate	Nevamar	"Carmel Sagawood" #WM 8350T

	Counter Support	Solid Metal	Lyman Associates	Powder Coated Black - 18" x 24" with ¼" mounting holes
	Grommets for Cable Pass thru countertops	Molded-Plastic	Doug Mockett & Company, Inc.	"VG Series"/Black 3 1/2" Outside Diameter/with matching caps
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

13. BREAK AREA				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E129 Break Area	Countertop	Solid Surface	Corian	"Acorn"
	Backsplash	Solid Surface	Corian	"Acorn"
	Integral Sink	Solid Surface	Corian	"Bisque"
	Vertical Surfaces/Cabinets	Plastic Laminate	Nevamar	"Carmel Sagawood" #WM 8350T
	Shelves (Microwave Cabinet)	Plastic Laminate	Nevamar	"Carmel Sagawood" #WM 8350T
	Adjustable Cabinet Shelves	Melamine	-	"White"
	Wire Pulls	Solid Metal	Amerock	AM-BP19003-SS
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

14. DECON WORKROOM				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E134 Decon Workroom	Countertop	Solid Surface	Corian	"Acorn"
	Backsplash	Solid Surface	Corian	"Acorn"
	Integral Sink	Solid Surface	Corian	"Bisque"

	Vertical Surface Cabinets	Plastic Laminate	Wilsonart	"Crisp Zephyr" #4858-60
	Adjustable Cabinet Shelves	Melamine	-	"White"
	Wire Pulls	Solid Metal	Amerock	AM-BP19003-SS
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

15. Nutrition Area				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E137a Nutrition Area	Countertop	Solid Surface	Corian	"Cottage Lane"
	Backsplash	Solid Surface	Corian	"Cottage Lane"
	Integral Sink	Solid Surface	Corian	"Bisque"
	Vertical Surfaces/Cabinets	Plastic Laminate	Nevamar	"Carmel Sagawood" #WM 8350T
	Adjustable Cabinet Shelves	Melamine	-	"White"
	Wire Pulls	Solid Metal	Amerock	AM-BP19003-SS
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

16. EMT SUPPLIES				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E139 AMBULANCE ENTRANCE	Vertical Surfaces/Cabinets	Plastic Laminate	Nevamar	"Varnish" #VS 2003T
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

17. EMT				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E139a EMT	Vertical Surface/Cabinets	Plastic Laminate	Nevamar	"Varnish" #VS 2003T
	Work surface Countertop	Plastic Laminate	Nevamar	"Ochre Tempera" #TM 2001T
	Adjustable Cabinet Shelves	Melamine	-	"White"
	Countertop Trim (Bullnose Edging)	Wood	-	Maple - Clear Stain
	Counter Support	Solid Metal	Lyman Associates	Powder Coated Black - 18" x 24" with ¼" mounting holes
	Wire Pulls	Solid Metal	Amerock	AM-BP19003-SS
	Grommets for Cable Pass thru countertops	Molded-Plastic	Doug Mockett & Company, Inc.	"VG Series"/Black 3 1/2" Outside Diameter/with matching caps
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

18. EQUIPMENT ROOM				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E143 Equipment Room	N/A	N/A	N/A	N/A

19. NURSE STATION - PATIENT/PUBLIC SIDE				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
	Transaction Top	Solid Surface	Corian	"Cottage Lane"

E1149, E156, E156a Nurse Station - Patient/Public Side	Vertical Surface/Cabinets	Plastic Laminate	Nevamar	"Carmel Sagawood" #WM 8350T
	High Vertical Surface Accent	Plastic Laminate	Nevamar	"Varnish" #VS 2003T
	Wall Bumper (High)	Vinyl/Metal	In Pro Corp.	"Silhouette" #1800, Khaki Brown #0118
	Wall Bumper (Low)	Vinyl/Metal	In Pro Corp.	"Cart Guard" #1800, Khaki Brown #0118
	Wall Protection Panel	Vinyl	In Pro Corp.	"Rigid Panel", Khaki Brown #0118, .04" Pebblette
	Corner Guards	Vinyl/Metal	In Pro Corp.	
	Recessed Cabinet Pull	Aluminum	Baer Supply	Extruded, full length 1/8" kerf: Model - EY 1500T
	Recessed Drawer Pull	Stainless Steel	Sugatsune America	Satin Finish, 5 ½"wide, #UT-140/S
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

20. NURSE STATION - STAFF SIDE				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E1149, E156, E156a Nurse Station - Staff Side	Transaction Top	Solid Surface	Corian	"Cottage Lane"
	Vertical Surface/Cabinets	Plastic Laminate	Nevamar	"Carmel Sagawood" #WM 8350T
	Work surface Countertop	Plastic Laminate	Nevamar	"Ochre Tempera" #TM 2001T
	Countertop Trim (Bullnose Edging)	Wood	-	Maple - Clear Stain
	Tackable Wall Panel	Fabric	CF Stinson	"Linea, lin #12, Angle"
	Counter Support	Solid Metal	Lyman Associates	Powder Coated Black - 18" x 24" with ¼" mounting holes

	Grommets for Cable Pass thru countertops	Molded-Plastic	Doug Mockett & Company, Inc.	"VG Series"/Black 3 1/2" Outside Diameter/with matching caps
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

21. NURSE STATION PASSAGEWAY				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E149a Passageway	Trim	Cellular PVC	ViLux	Maple
	Dry Erase Surface	Wallcovering	Wolf Gordon	Wipe Out - Beige #G 7593553
	Tack Board	Cork	Forbo	Color: 2067, See elevation for sizes.

22. TUBE STATION				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E156B Tube Station	Transaction Top	Solid Surface	Corian	"Cottage Lane"
	Vertical Surface/Cabinets	Plastic Laminate	Nevamar	"Carmel Sagawood" #WM 8350T
	Adjustable Cabinet Shelves	Melamine	-	"White"
	Wire Pulls	Solid Metal	Amerock	AM-BP19003-SS
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

23. MEDS ROOM				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size



E157 Meds Room	Worksurface Countertop	Solid Surface	Corian	"Acorn"
	Backsplash	Solid Surface	Corian	"Acorn"
	Integral Sink	Solid Surface	Corian	"Bisque"
	Vertical Surface/Cabinet	Plastic Laminate	Nevamar	"Varnish" #VS 2003T
	Adjustable Cabinet Shelves	Melamine	-	"White"
	Wire Pulls	Solid Metal	Amerock	AM-BP19003-SS
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

24. SOILED HOLDING				
Room No. and Name	Component	Material	Manufacturer	Finish/Style/Color/Size
E155 Soiled Holding	Worksurface Countertop	Solid Surface	Corian	"Acorn"
	Backsplash	Solid Surface	Corian	"Acorn"
	Integral Sink	Solid Surface	Corian	"Bisque"
	Adjustable Cabinet Shelves	Melamine	-	"White"
	Vertical Surface/Cabinet	Plastic Laminate	Wilsonart	"Crisp Zephyr" #4858-60
	Wire Pulls	Solid Metal	Amerock	AM-BP19003-SS
	Base	Resilient Rubber Base	Roppe	#171 - Sandstone, 6"

## C. SECTION 06 65 10, SOLID SURFACE FABRICATIONS

ITEM	LOCATION	MANUFACTURER	COLOR
SSM1	Countertop	Corian	Cottage Lane
SSM2	Countertop	Corian	Acorn

SSM3	Not Used	Not Used	Not Used
SSM4	Window Sill	Corian	Night Sky
SSM5	Integral Sink #804	Corian	Bisque
SSM6	Countertop	Corian	Savannah

## 2.7 DIVISION 07 - THERMAL AND MOISTURE PROTECTION

### A. SECTION 07 40 00, ROOFING AND SIDING PANELS

Type	Shape	Ext. Finish	Int. Finish	Manufacturer	Mfg. Color Name/No.
MP-1	Metal Wall Panel - 2000H series	Duranar Sunstorm Ultra-Cool	-	Kingspan Benchmark	"Champagne Bronze"
MP-2	Metal wall Panel - 2000H series	Duranar Sunstorm Ultra-Cool	-	Kingspan Benchmark	"Natural Suede"
MP-3	Metal Wall Panel - 2000H series	Duranar Ultra-Cool	-	Kingspan Benchmark	"Bone White"

### B. SECTION 07 54 23, THERMOPLASTIC POLYOLEFIN (TPO) ROOFING

Color	Manufacturer	Mfg. Color Name/No.
White	Carlise	SureWeld

### C. SECTION 07 92 00, JOINT SEALANTS

Location	Color	Manufacturer	Manufacturer Color
Masonry Expansion Joints	Match adjacent material to join	Tremco	-
CMU Control Joints	Match adjacent material to join	Tremco	-
Precast Concrete Panels	N/A	N/A	-
New to Existing Walls	Match adjacent material to join	Tremco	-
Building Expansion Joints	Match adjacent material to join	Tremco	-

Masonry Sealed Joints	Match adjacent material to join	Tremco	-
Stone Sealed Joints	Match adjacent material to join	Tremco	-

## 2.8 DIVISION 08 - OPENINGS

### A. SECTION 08 11 13, HOLLOW METAL DOORS AND FRAMES

Paint both sides of door and frames same color including ferrous metal louvers, and hardware attached to door	
Component	Color of Paint Type and Gloss
Door	Coronado Industrial Coating DTM, Semi-Gloss, "Great Plains Gold" #1077
Frame	Coronado Industrial Coating DTM, Semi-Gloss, "Great Plains Gold" #1077
Window frame	Coronado Industrial Coating DTM, Semi-Gloss, "Great Plains Gold" #1077

### B. SECTION 08 14 00, WOOD DOORS

Component	Finish/Color
Doors	Stain/Mohawk Premium 2000 Cherry - Brown

### C. SECTION 08 31 13, ACCESS DOORS AND FRAMES

Material	Finish/Color
Steel	Paint/Match adjacent color

### D. SECTION 08 41 13, ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

Component	Finish	Manufacturer	Mfg.Number
Windows	Clear Anodized	Kawneer	-
Exterior Doors	Clear Anodized	Kawneer	-
Interior Doors	Aluminum	Stanley-KU	-

## E. SECTION 08 56 19, PASS WINDOWS

Room No. and Name	Finish	Glazing
E103 Reception	Factory Finish Aluminum Track	Clear Tempered

## F. SECTION 08 71 00, BUILDERS HARDWARE

Item	Material	Finish
Hinges	Interior - Steel U.N.O. in 08 71 00 Exterior - Stainless Steel	Satin (ANSI 630)
Door Closers	Arms & Brackets - Steel	Satin Aluminum
Floor Closers	N/A	-
Floor Pivot Sets	N/A	-
Closer/ Holder	Factory Applied Finish	Satin Aluminum
Floor Stops	(ANSI 156.6)	630
Door Holders	Steel	Satin Chromium Plated (ANSI 626)
Lock/ Latches	Brass/Bronze	626
Key Cabinet	Steel	Paint
Armor Plates	Stainless Steel	630
Kick Mop Plates	Stainless Steel	630
Door Edging	Stainless Steel	630
Exit Device	Aluminum	628
Flush Bolts	Steel	626

Door Pulls	Brass/Bronze	Satin Chromium Plated (ANSI 626)
Push Plates	Stainless Steel	Satin (ANSI 630)
Combination Push Pull Plate	N/A	-
Coordinators	Steel	600
Light Proof Seals	Aluminum with silicone	Clear Coated
Weather Strip	Silicone	-
Threshold	Aluminum	Clear Coated (ANSI 673)

## G. SECTION 08 80 00, GLAZING

Glazing Type	Manufacturer	Mfg. Color Name/No.
G-3 Spandrel Glass	Opaci-Coat 300	Harmony Graylite #14 / #3-747

## H. SECTION 08 44 13, GLAZED ALUMINUM CURTAIN WALLS

Component	Material	Finish	Manufacturer	Mfg. Color Name/No.
Frame	Aluminum	Clear Anodized	Kawneer	-

## I. SECTION 08 87 00, SUN CONTROL WINDOW FILM

Item	Manufacturer	Mfg. Color Name/No.
Window Film	3M	Night Vision 25

**2.9 DIVISION 09 - FINISHES**

## A. SECTION 09 29 00, GYPSUM WALLBOARD - REVEALS

Item	Color	Manufacturer	Mfg. Name/No.
Reveal Molding	Aluminum, Clear Anodized, Satin	Fry Reglet	#DRM-50-100
Reveal End Caps	Aluminum, Clear Anodized, Satin	Fry Reglet	(associated with #DRM-50-100)

## B. SECTION 09 30 13, PORCELAIN TILING

1. SECTION 09 30 13, PORCELAIN TILING		
Finish code	Manufacturer	Mfg. Color Name/No
PFT1 (floor)	Stonepeak	Quartzite Collection, Sunset 12"x24" (horizontal)
PFT2 (floor)	Stonepeak	Quartzite Collection, Lime 12"x24" (horizontal)
PWT1 (Waiting Room & Entry) (wall)	CMC Stones	Mirage, 2.0 Chambrod 12" x 24", Matte
PWT2 (Corridor E109) (wall)	Best Tile	Mora Medley, Cream 12" x 24" (horizontal)
PWT3 (Waiting Room /Entry) (wall)	Best Tile	Style, Tabacco 13" x 13"
PWT4 (Public Toilet) (wall)	Best Tile	Style, Corda 13" x 13"
PWT5 (Pat./Staff Toilet) (wall)	Best Tile	Samarcanda Bianco 12" x 12" Beige Matte V2 Caesabi 12M PS02

## C. SECTION 09 30 13, EDGE GUARD OR TRIM (W)

Item	Manufacturer	Mfg. Color Name/No.
Clear Anodized Aluminum, Satin	Schluter	(At PFT adjacent to concrete finished floor) Reno-U AEU 125
Clear Anodized Aluminum, Satin	Schluter	Reno-V AEVT 100 B 20
Clear Anodized Aluminum, Satin	Schluter	Rondec RO 100 AE
Clear Anodized Aluminum, Satin	Schluter	Rondec E/RO 100 AE (Outside Corner)
Clear Anodized Aluminum, Satin	Schluter	Rondec I/RO 100 AE (Inside Corner)

2. SECTION 09 30 13, PORCELAIN TILE MORTAR		
Location	Manufacturer	Type Name
In E100, E101, E101a, E102 & E109 with PFT1/PFT2	Laticrete	#255 MultiMax

In E105 & E106	Laticrete	#255 MultiMax
In E103c, E119, E120, E130, E132, E135a, E136 E140a and E142 with PWT5	Laticrete	#255 MultiMax

3. SECTION 09 30 13, PORCELAIN TILE GROUT		
Location	Manufacturer	Mfg. Color Name/No.
In E100, E101, E101a, E102 & E109 with PFT1/PFT2	TEC Specialty Construction Brands, Inc.	Accu Color EFX, Epoxy Special Effects Grout, 1/8" width, Color:#945 Light Buff
In E105 & E106 with PFT1/PFT2	TEC Specialty Construction Brands, Inc.	Accu Color EFX, Epoxy Special Effects Grout, 1/8" width, Color:#945 Light Buff
In E100, E101a, E102 with PWT1	TEC Specialty Construction Brands, Inc.	Accu Color EFX, Epoxy Special Effects Grout, 1/8" width, Color:#
In E109 with PWT2	TEC Specialty Construction Brands, Inc.	Accu Color EFX, Epoxy Special Effects Grout, 1/8" width, Color:#
In E100, E101a, E102 with PWT3	TEC Specialty Construction Brands, Inc.	Accu Color EFX, Epoxy Special Effects Grout, 1/8" width, Color:#
In E105 & E106 with PWT4	TEC Specialty Construction Brands, Inc.	Accu Color EFX, Epoxy Special Effects Grout, 1/8" width, Color:#
In E103c, E119, E120, E130, E132, E135a, E136 E140a and E142 with PWT5	TEC Specialty Construction Brands, Inc.	Accu Color EFX, Epoxy Special Effects Grout, 1/8" width, Color:#

4. SECTION 09 66 13, DIVIDER STRIPS			
Size	Material	Manufacturer	Manufacturer Number
Does not apply	-	-	-


## D. SECTION 09 51 00, ACOUSTICAL CEILINGS

Finish Code	Component	Color Pattern	Manufacturer	Mfg Name/No.
	Exposed Suspension System	White	Armstrong	
-	Trim	-	Armstrong	Axiom - Profiled Trim, Concave, 5 ¼" x 2 ½", Inside 90 Degree Corner
-	Trim	-	Armstrong	Axiom - Profiled Trim, Concave, 5 ¼" x 2 ½"
AT1	Mineral Fiber	-	Armstrong	Healthzone Ultima
AT2	Metal	-	Armstrong	24"x24" Metal Works, Effects, Wood-Look, Cherry, with perforations, #6464M3FXCH, W/ Black Grid

## E. SECTION 09 54 23, LINEAR METAL CEILINGS (LMC)

Finish Code	Strip Material	Strip Face Size	Manufacturer	Mfg Name/No.
AT3	Metal	4" x 96"	Armstrong	Linear & Linear Exterior, Smooth Texture, White (WH); perforated where noted on drawings

## F. SECTION 09 65 13, RESILIENT BASE &amp; ACCESSORIES



Finish Code	Item	Height	Manufacturer	Mfg Name/No.
RB1	Resilient Base	<b>6 in. coved</b>	Roppe	#171 Sandstone

## G. SECTION 09 65 16, VINYL SHEET FLOORING (VSF)

Finish Code	Pattern name	Manufacturer	Mfg. Color Name/No.
VPF1	Northern Timbers	Roppe	#029 Toasted Teak, 4" x 36"



## H. SECTION 09 65 16, VINYL SHEET FLOORING, HEAT WELDED SEAMS (WSF)

Finish Code	Pattern name	Manufacturer	Mfg. Color Name/No.
WSF1	Biospec MD	Mannington	"Bisque" (LC) 15202
WSF2	Biospec MD	Mannington	"Citrus" 15358
WSF3	Biospec MD	Mannington	"Prairie Sand" 15396
WSF4	Biospec MD	Mannington	"Green Tea" 15334
WSF5	Biospec MD	Mannington	"Sierra" 15388
WSF6	Realities, Maple Grove,	Mannington	"Teak" #5623

## I. SECTION 09 65 16, WELDING RODS (WSF)

Finish code	Manufacturer	Mfg. Color Name/No.
WR1	Mannington	With WSF2, #842397
WR2	Mannington	With WSF1, #842365
WR3	Mannington	With WSF4, #842335
WR4	Mannington	With WSF5, #842395

## J. SECTION 09 65 16, TRANSITION STRIPS (TS)

ITEM	Manufacturer	TYPE	Mfg. Color Name/No.
TS1	Johnsonite	CRS-XX-A	#149 Milk Chocolate


## K. SECTION 09 65 13, RESILIENT BASE STAIR TREADS AND ACCESSORIES

Finish Code	Item	Height	Manufacturer	Mfg Name/No.
RST1	Resilient Tread	-	Roppe	#171 Sandstone

## L. SECTION 09 68 00, CARPET


Finish Code	Manufacturer	Model/Color Name
CPT1	American Floor Mats	Waterhog Premier/"Chestnut Brown"

## M. SECTION 09 67 23.60 RESINOUS (Urethane and Epoxy Mortar) FLOORING



Finish code	Manufacturer	Mfg. Color Name/No.
RES-6	Stonhard	Stonclad UT "Desert Tan"

## N. SECTION 09 67 23.30, RESIN (EPOXY RESIN COMPOSITION) MORTAR FLOORING



Finish code	Manufacturer	Mfg. Color Name/No.
RES-3	Stonhard	Stonclad UT "Desert Tan"

## O. SECTION 09 91 00, PAINT AND COATINGS

1. MPI Gloss and Sheen Standards		Gloss @60	Sheen @85
Gloss Level 1	a traditional matte finish-flat	max 5 units, and	max 10 units
Gloss Level 2	a high side sheen flat-"a velvet-like" finish	max 10 units, and	10-35 units
Gloss Level 3	a traditional "egg-shell like" finish	10-25 units, and	10-35 units
Gloss Level 4	a "satin-like" finish	20-35 units, and	min. 35 units
Gloss Level 5	a traditional semi-gloss	35-70 units	
Gloss Level 6	a traditional gloss	70-85 units	
Gloss level 7	a high gloss	more than 85 units	

2. Paint code	Gloss	Manufacturer/Type	Mfg. Color Name/No.
P1	Not Used	Not Used	Not Used
P2	Eggshell Finish 374, Level 3	Benjamin Moore Interior Latex Eco Spec WB	"Sierra Hills" 1053
P3	Eggshell Finish 374,	Benjamin Moore Interior	"Nantucket Gray" HC-11

	Level 3	Latex Eco Spec WB	
P4	Eggshell Finish 374, Level 3	Benjamin Moore Interior Latex Eco Spec WB	"Barley" 199
P5	Eggshell Finish 374, Level 3	Benjamin Moore Interior Latex Eco Spec WB	"Tuscany" 1208
P6	Eggshell Finish 374, Level 3	Benjamin Moore Interior Latex Eco Spec WB	"Great Plains Gold" 1077 (standard trim)
P7	Eggshell Finish 374, Level 3	Benjamin Moore Interior Latex Eco Spec WB	Ceiling White
P8	Eggshell Finish 374, Level 3	Benjamin Moore Interior Latex Eco Spec WB	"Brown Tar" 2110-20
P9	Soft Gloss Finish, Level 5	Benjamin Moore, Waterborne Exterior Paint	"Sierra Hills" 1053

M 3. Stain Code (S)	Gloss and Transparency	Manufacturer	Mfg. Color Name/No.
NA	NA	NA	NA

## P. SECTION 09 72 16, VINYL COATED FABRIC WALLCOVERING (W)

Wallcovering Code	Manufacturer	Mfg. Color Name/No.
W1	Wolf Gordon	Summit Prints, "Sofia" #SOF 7-5508 "Golden Ochre"
W2	Wolf Gordon	Summit Prints, "Shoji Screen" #SHS 7-4310 "Geisha"
W3	Wolf Gordon	White board wall covering, "Wipe-Out" #MLM 8006 "Beige"

## Q. SECTION 09 84 33, ACCOUSTICAL WALL PANELS (AWP)

Finish Code	Manufacturer	Mfg. Color Name/No.
AWP1	Armstrong	Soundsoak 85, #32061FRWE, 1" Standard Panel, Mitered Edge, Fabric FR701 - Color: "Wheat"

## R. SECTION 09 97 33.10, RESINOUS COATING SYSTEMS FOR WALLS AND CEILINGS

Item	Manufacture	Mfg. Color Name
RES-W	Stonhard	Stonglaze VSF "Cork"

## 2.10 DIVISION 10 - SPECIALTIES

### A. SECTION 10 11 13 / 10 11 23, TACKBOARDS (BB)

Room No. and Name	Component	Material	Manufacturer	Mfg. Color Number
E117, E129a, E149a	Bulletin Board	Linoleum	Forbo	2067

### B. SECTION 10 21 23, HOSPITAL CUBICLE CURTAINS AND INTRAVENOUS SUPPORT TRACKS

ITEM	Manufacturer	Model/Color Name
Cubicle Curtain Track	InPro	Optitrac/"White"
Intravenous Tracks		

### C. SECTION 10 26 00, WALL GUARDS AND CORNER GUARDS



Item	Material	Manufacturer	Mfg. Color Name/No.
Corner Guards (CG1)	Vinyl/Metal	InPro	3" wide, #150 - Color: #0252 Burlap, unless otherwise noted.
Corner Guards (CG2)	Vinyl/Metal	InPro	2" wide, #160 - Color: #0252 Burlap, unless otherwise noted.
Corner Guards (CG3)	Vinyl/Metal	InPro	2" wide, #140D, End Wall 160 - Color: #0252 Burlap, unless otherwise noted.
Corner Guards (CG4)	Vinyl/Metal	InPro	3" wide, #130, Up to 135 degree angle - Color: #0252 Burlap, unless otherwise noted.
Corner Guards (CG5)	Vinyl	InPro	3/4" wide, #3496 - Color: #0252 Burlap, unless otherwise noted.
Wall Guards (WG1)	Vinyl/Metal	InPro	Silhouette #1800i, 8" - Color: #0118 Khaki Brown #0118, unless otherwise noted.
Wall Guard (WG2)	Vinyl/Metal	InPro	MB20 Cart Guard, 2", Color: #0118 Khaki

			Brown, unless otherwise noted.
Wall Guard (WG3)	Vinyl	InPro	Rigid Sheet, Color: #0118 Khaki Brown, unless otherwise noted.
Wall Guard (WG4)	Vinyl	InPro	Rigid Sheet, Color: #0252 Burlap, unless otherwise noted.
Handrail (HR1)	Vinyl/Metal	InPro	Silhouette, #3500WV, Color: #0118 Khaki Brown (Wall Guard)& Honey Nut #0535
Chair Rail (CR1)	Vinyl/Metal	InPro	#2700W, 3" Height, Color: Honey Nut, Smooth Texture
Chair Rail (CR2)	Metal	InPro	#30SS, 5 1/2" Height, Stainless Steel Wall Guard

## D. SECTION 12 15 00 ART HANGING, DISPLAY SYSTEMS AND ACCESSORIES

Room No. and Name	Item	Finish	Manufacturer	Model No.
Waiting #E102	Magazine Rack	Cherry & Seasand	Peter Pepper Products	#462-2
Waiting #E102	Literature Rack	Cherry & Seasand	Peter Pepper Products	#487-2P
Waiting #E102	Lobby Clock	Cherry & Alum. Metallic	Peter Pepper Products	#325

## E. SECTION 10 13 00 / 10 14 00, EXTERIOR SIGNS

Component	Finish	Manufacturer	Mfg. Color Name/No.
		Creative Signage Systems	Refer to Spec. Section 10 14 00

## F. SECTION 10 13 00 / 10 14 00, INTERIOR SIGNS

Sign Type	Component	Manufacturer	Mfg. Color Name/No.
		Creative Signage Systems	Refer to Spec. Section 10 14 00

## G. SECTION 10 25 13, PATIENT BED SERVICE WALLS

Component	Material	Manufacturer	Model	Mfg. Color/Name
Frame	Metal	Herman Miller	Compass System	-
Face Panel	Durawrap	Herman Miller	Compass System	Aged Cherry, HX

## H. SECTION 10 28 00, TOILET AND BATH ACCESSORIES

Item	Material/Finish	Manufacturer	Mfg. Number
Toilet Tissue Dispenser (TTD1)	Plastic	Bay West	Silhouette Dubl-Serv OptiCore Dispenser, #BW80200
Paper Towel Dispenser (PTD1)	Plastic	Bay West	Silhouette OptiServ Hands Free Disp-Black, #BW86500
Soap Dispenser (SD1)	Plastic	Steris Acute/Kare	#1307Q5
<del>Hand Sanitizer (HS1)</del>	<del>Plastic</del>	<del>Skilcraft</del>	(Provided by Owner)
Mirror (MR1)	Stainless Steel	Bobrick	B-165 1830, 18" x 30"
Mirror (MR2)	Stainless Steel	Bobrick	B-166 1830, 18" x 30"
Mirror (MR3)	Stainless Steel	American Standard	0600, 18" x 30"
Baby Changing Station (DCS1)	Stainless Steel/Poly.	Koala Kare	KB110-SSWM
Crutch Hook (Inside Equipment Room Cabinet)	Stainless Steel with Satin Finish	Bradley	Model 9992
Utility Shelf with Mop/Broom Holders and Rag Hooks	Stainless Steel with Satin Finish	Bobrick	B-224
Clothes Hooks (CH)	Stainless Steel with Satin Finish	Bobrick	B-6707
<del>Recessed Specimen Pass-Through Cabinet</del>	<del>Stainless Steel with Satin Finish</del>	<del>Bobrick</del>	<del>B-505</del>
Infection Prevention Center (PPE)	Stainless Steel	Peter Pepper Products	ICX-1, 22¾"w x 18"h x 4"d

## I. SECTION 10 44 13, FIRE EXTINGUISHER CABINETS

Manufacturer/Component	Material	Size
Larsen's Mfg./Cabinet Door	Stainless Steel	#2409-6R Semi-Rec. 2 1/2"

## J. SECTION 10 51 13, METAL LOCKERS

Manufacturer/Component	Material	Finish
ASI Floor Anchors Legs	Steel	Powder Coat finish, Black
ASI Bench Top	Wood, 1 1/4" thick x 12" deep	Stain, Clear
ASI Traditional Lockers	Steel	Powder Coat finish, Color: Tan 01

## 2.11 DIVISION 12- FURNISHINGS

## A. SECTION 12 32 00, WOOD CASEWORK

Item Type	Location	Finish/Color
N/A	N/A	N/A

## B. SECTION 12 36 00, COUNTERTOPS AND ACCESSORIES

Type	Finish/Color
Plastic Laminate	See Section 06 20 00 Finish Carpentry
Molded Resin	See Section 06 20 00 Finish Carpentry

## C. SECTION 12 34 00, MOLDED PLASTIC CASEWORK

Component	Finish	Manufacturer	Mfg. Color Name
N/A	N/A	N/A	N/A

## D. SECTION 12 24 00, WINDOW SHADES

Component	Material	Manufacturer	Mfg. Color Name/No.
Spring Roller Shades	Sheer Weave Fabric, 5% openness factor	Draper	White/Platinum

Support Hardware	Stainless Steel Bead Chain	Draper	-
------------------	----------------------------	--------	---

## E. SECTION 12 24 21, LIGHTPROOF SHADES

Component	Material	Manufacturer	Mfg. Color Name/No.
Spring Roller Shades (in Conference Room #E125)	Opaque, Room Darkening Fabric, SunBloc Series SB9100	Draper	Putty/White
Support Hardware	Stainless Steel Bead Chain	Draper	-

## 2.12 DIVISION 14 - CONVEYING EQUIPMENT

## A. SECTION 14 92 00, PNEUMATIC TUBE SYSTEM

Manufacturer	Material	Finish/Color
Swisslogic	Exposed Metal	Paint/Manuf. Standard

## 2.15 DIVISION 22 - PLUMBING

## A. SECTION 22 40 00, PLUMBING FIXTURES AND TRIM

Item	Color
Water Closet	White (Floor Mount), Stainless Steel (Security)
Shower	White
Urinal	N/A
Bathtubs	N/A
Lavatories	White, Stainless Steel (Security)
Service Sink Corner	N/A
Service Sink	Terrazzo
Clinic Service Sink	White
Water Cooler	Stainless Steel
Shower Fixture	Chrome Plated



## B. SECTION 10 21 16, PREFABRICATED SHOWER

Room No. and Name	Component	Material	Manufacturer	Mfg. Color Name/No.
E120	Accessible Series IS4848BF 2"	Acrylic	Aqua Bath	White
E140a	Care Series - ADA C4136TD-FUS 2"	Acrylic	Aqua Bath	White

## C. SECTION 23 37 01, LOUVERS AND WALL VENTS

Item	Material	Finish	No./Color
Exterior Areaway Louver	Aluminum	Coronado Industrial Coating, Corotech DTM Semi Gloss Paint	984 Stone Hearth


**2.16 DIVISON 26 - ELECTRICAL**

## A. SECTION 26 51 00, BUILDING LIGHTING INTERIOR

Fixture Type	Exterior Finish	Color
See Electrical Drawing	Manufacturer's Standard	All White U.N.O.

## B. SECTION 26 56 00, SITE LIGHTING - see Lighting Specification

Type and Component	Exterior Finish	Manufacturer	Mfg. Name/No.
To Match Existing	To Match Existing	To Match Existing	To Match Existing

**PART 3 - EXECUTION****3.1 FINISH SCHEDULES & MISCELLANEOUS ABBREVIATIONS**

N/A - See Abbreviations on Finish Schedule Drawing A14.1 and Finish Floor Pattern Drawings A14.2 & A14.3

### 3.2 FINISH SCHEDULE SYMBOLS

#### Symbol Definition

\*\* Same finish as adjoining walls  
- No color required  
E Existing  
XX To match existing  
EFTR Existing finish to remain  
RM Remove

### 3.3 ROOM FINISH SCHEDULE

See Finish Schedule on drawing A14.1.

--- E N D---