

**RFP 36E77618R052 IOWA CITY CORRECT LIFE SAFETY DEFICIENCIES TECHNICAL QUESTIONS AND VA RESPONSE TRACKING SHEET**

ITEM NO.	DATE QUESTION RECEIVED	DATE QUESTION ANSWERED	QUESTION	GOVERNMENT RESPONSE
1.	3-26-2018	4-3-2018	Does this project contain any Commissioning requirements?	Commissioning is not required on this project.
2.	3-26-2018	3-30-2018	Is a full-time superintendent required for this project?	At all times during the performance of this contract and until work is completed and accepted, the Contractor shall provide a full time Superintendent who shall exclusively be dedicated to the supervision of this project. The Superintendent must meet all construction competency requirements, including OSHA credentialing, and have satisfactory performance as determined by the Certifying Officer. <b>(OSHA 10 is required for any workman on a construction site and OSHA 30 is required for any Superintendent.)</b>
3.	3-26-2018	3-30-2018	Are there any unique requirements for the As-Built Drawings/Safety Data Sheets and Security Plan?	The Superintendent shall maintain two full size sets of as-built drawings which will be kept current during construction of the project, to include all contract changes, modifications and clarifications. The Superintendent is required to have SDS's of all hazardous materials on site. The Superintendent is required to maintain a Safety and Security plan. Plans need to be unique to the current project – No Generic Plans!

ITEM NO.	DATE QUESTION RECEIVED	DATE QUESTION ANSWERED	QUESTION	GOVERNMENT RESPONSE
4.	3-26-2018	3-30-2018	What are the quality assurance requirements?	<p>It is your superintendent's responsibility to assure your subs are installing per the construction documents. Throughout the specifications it talks about Quality Assurance – provide a QA plan! Quality Assurance also includes coordinating the site with your subs and scheduling them to do work.</p> <p>i.e. If your sprinkler sub puts his pipe where the VAV is supposed to go and makes it inaccessible for maintenance. To the VA, this is a coordination and quality assurance issue on the prime.</p> <p>Also, provide coordination drawings, to include elevations, sizes of duct work, pipes, conduits, VAV's, FCU's etc. Don't do the work then come back and tell us it doesn't work! Lack of Coordination and Quality Assurance only creates delays and needless change orders.</p>

ITEM NO.	DATE QUESTION RECEIVED	DATE QUESTION ANSWERED	QUESTION	GOVERNMENT RESPONSE
5.	3-26-2018	3-30-2018	Are there are any unique Infection Control requirements at Iowa City?	<p>This should be part of your superintendents daily Quality Assurance Plan.</p> <ul style="list-style-type: none"> <li>- Neg Air Hepa Filters need to be cleaned once a week, if not more.</li> <li>- Paths of egress need to be clear at all times.</li> <li>- Sweep inside your construction site daily with sweeping compound.</li> <li>- Insure sticky matts are available and changed regularly throughout the day.</li> <li>- Contain construction waste before transport in a tightly covered container. Draping a cloth over the container is not acceptable - it must be secured to the cart.</li> <li>- Insure that the outside of your construction site is free of dust and debris. This includes, to and from your construction site; i.e. the Freight Elevator, Corridors, Loading Dock and Dumpsters.</li> </ul>
6.	3-26-2018	3-30-2018	What are the requirements for daily logs and payrolls?	<p>The full-time superintendent should be able to provide Daily Logs that are detailed! Need to know the Name of the Sub, Name of the Employee, Where and What they are Working on and the Duration of the Work. The daily log will include your full-time superintendent's time as well. Note: Daily logs are daily, not weekly! Payrolls must reflect what your daily logs say. You must provide payrolls and daily logs for everyday of the work week, even if there is no work.</p>

ITEM NO.	DATE QUESTION RECEIVED	DATE QUESTION ANSWERED	QUESTION	GOVERNMENT RESPONSE
7.	3-26-2018	3-30-2018	Will more than one set of keys be provided for this project?	COR will issue one set of keys only to the Full Time Superintendent. Plan on using combination locks that accept a Best 7 pin Core. Combinations cannot be written anywhere on the outside of the construction area.
8.	3-26-2018	3-30-2018	Please confirm if winter conditions are required for this project?	The Cast-In-Place Specification (03 30 00) recommends ACI 306 for cold weather conditions. Your bid must include winter conditions and must be included into your schedule of values as a separate line item.
9.	3-26-2018	3-30-2018	What is required for GEMS documentation?	You are required to separate rubble and recyclables and provide documentation on how much. Don't wait until the end of the project! See the attached GEMS Training for Contractors. If you use our dumpsters there is a requirement to separate wood, cardboard, metal and general trash. If there is cardboard in any of the dumpsters the city landfill will not take them per City of Iowa City Ordinance. Also, if you get caught placing cardboard or not separating materials - dumpster privileges may be taken away. Note: We have security cameras looking at our dumpsters and your superintendent will be responsible to dumpster dive and separate correctly.
10.	3-26-2018	3-26-2018	Can the proposals be emailed to you on due date, or do they have to be delivered? From reading the solicitation it seems to me that they can be emailed to you.	Per the solicitation instructions, proposals are to be emailed to the CO only. The bond is to be delivered via mail.

ITEM NO.	DATE QUESTION RECEIVED	DATE QUESTION ANSWERED	QUESTION	GOVERNMENT RESPONSE
11.	3-26-2018	4-3-2018	I have extensively reviewed all the documentation listed in the solicitation, I did not see a dedicated signage schedule. Do you have any knowledge of the signage schedule?	Signage schedule and details are noted on sheet IG-1.
12.	3-28-2018	4-3-2018	Ref drawing A2-01W- waiting area 1W39, 1W40 and corridor are called out by indicator detail 4/A2. In review of drawings shall we assume the drawing being referenced should be AP2. There are several similar indicator errors on other architectural drawings as well. Will additional clarification be provided?	There was an error with an embedded font when the individual PDF drawings were combined into a complete set causing certain fonts to be substituted with symbols and other characters. This sheet and the entire Volume 1 Drawing set will be reissued. See Amendment 00001 posted on 4-03-2018.
13.	3-28-2018	4-3-2018	Drawing AE1 detail 1 appear to be utilizing a different elevation number system based on elevations noted off column line 4. Also the elevation is being referenced as SLA. Assuming this is the west elevation, will additional information be provided?	There was an error with an embedded font when the individual PDF drawings were combined into a complete set causing certain fonts to be substituted with symbols and other characters. This sheet and the entire Volume 1 Drawing set will be reissued. See Amendment 00001 posted on 4-03-2018.
14.	3-28-2018	4-3-2018	Detail 8 on drawing S11 is labeled as “Framing section at floor grate”. Please clarify.	The title of Detail 8 is incorrect. This will be clarified in Addendum No. 1, which will be posted as part of Amendment 00002.
15.	3-28-2018	4-3-2018	Drawing IF2-01W- furnishing keynotes 5,7,9,11, 26, 27,28, 29 and 31 is not designated as OF/OI. Who is providing and installing these furnishings?	OF/OI is an abbreviation for “Owner Furnished/Owner Installed”. These will be provided by the Government.
16.	3-28-2018	4-3-2018	Drawing IF2-01W and IF3- general note 4 requires to contractor to contract with Pigott to remove and reinstall wall mount work surfaces and storage cabinets. Please clarify where are these cabinets are currently located and where are they to be reinstalled?	Note 4 will be clarified in Addendum No. 1, which will be posted as part of Amendment 00002.

ITEM NO.	DATE QUESTION RECEIVED	DATE QUESTION ANSWERED	QUESTION	GOVERNMENT RESPONSE
17.	4-03-2018	4-13-2018	For the Amcase wardrobes & sinks, do you have a floor plan of the patient rooms these will be going in on 5West & 7West so that we can have Amcase quote the correct quantities? Or do you know room #'s and quantities that we can include with the elevations?	Floor plans, room numbers and elevations for Amcase wardrobes and sinks are shown on sheet IN12. This was further clarified in Addendum 00002.
18.	4-03-2018	4-05-2018	We have a list of items we would like the VA to review as substitution requests. Will you please review now and provide a response?	Please refer to the instructions in FAR 52.211-6 Brand Name or Equal and VAAR 852.211-73 Brand Name or Equal that are listed in the solicitation.
19.	4-06-2018	4-13-2018	There is a note on electrical drawings that states that no exposed conduit will be allowed in stairwell. Since this is a poured in place stairwell. It will be very expensive to embedded conduit in walls. All existing stairwells have exposed conduit in them.	See response to duplicate question #21.
20.	4-10-2018	4-10-2018	There is no equipment schedule on electrical drawings	It is on the Mechanical Schedules on sheets M3 and M4.
21.	4-10-2018	4-10-2018	Per the Electrical Drawing Note: No surface mounted conduit & Junction Boxes allowed. Including stair tower. Is it possible to surface mount electrical boxes in the stair tower?	Yes, it would be preferred that conduit and electrical boxes be surface mounted in the stairwell. All other conduit and boxes shall be roughed in as specified.

22.	4-12-2018	4-13-2018	Note 7 is missing off sheet EP10-09W.	Electrical Keynotes incorrectly go 1-6, (skip 7), 8. Electrical Keynote #8 should read as #7, which corresponds to keynotes on floor plans.
-----	-----------	-----------	---------------------------------------	---

23.	4-12-2018	4-13-2018	<p>In regards to the price schedule, item 3. Of the “NOTICE” at the bottom of page 6 of the solicitation states the following:</p> <p><b><i>3. Prices for each Deduct Alternate shall be expressed as the <u>dollar amount to be deducted</u> from CLIN 0001, Item 1.</i></b></p> <p>But then the CLINS State (BASE BID MINUS)</p> <p><b>CLIN 0002, DEDUCT ALTERNATE NO. 1 (BASE BID MINUS THE FOLLOWING WORK):</b> ELIMINATE ALL WORK SHOWN IN THE POLICE SUITE ON THE FIRST FLOOR. THE PERIOD OF PERFORMANCE WITH THE APPLICATION OF THIS DEDUCT ALTERNATE REMAINS AT 620 CALENDAR DAYS AFTER ISSUANCE OF NOTICE TO PROCEED. <b>CLIN 0002: \$ _____</b></p> <p><b>CLIN 0003, DEDUCT ALTERNATE NO. 2 (BASE BID MINUS DEDUCT ALTERNATE NO. 1 AND THE FOLLOWING WORK):</b> ELIMINATE ALL WORK SHOWN ON FLOORS SEVEN THRU TEN. THE PERIOD OF PERFORMANCE WITH THE APPLICATION OF THIS DEDUCT ALTERNATE IS REDUCED TO 470 CALENDAR DAYS AFTER ISSUANCE OF NOTICE TO PROCEED. <b>CLIN 0003: \$ _____</b></p> <p>The instructions under the “NOTICE” seems to contradict the instructions on the bid schedule.</p> <p>Can you please clarify if you want the new totals for each CLIN (Base Bid minus the work) or if you want us to list the deduct amount only? If you want the deduct amount only, will there be a revised price schedule issued?</p>	<p>Notice Item #3 in the Price Schedule stating “Prices for each Deduct Alternate shall be expressed as the dollar amount to be deducted from CLIN 0001, Item 1,” shall be deleted in its entirety. The instructions under each CLIN shall be how the pricing is provided. A Revised Pricing Schedule is provided in Amendment 00004. See attached - Price Schedule - Revised 4-13-2018.</p>
-----	-----------	-----------	---	--



24.	4-14-2018	4-16-2018	Can the government confirm that all wall assemblies involved in this project are metal stud and drywall at floors 2-10?	All interior walls on floors 2-10 are metal stud or shaftwall construction.
25.	4-14-2018	4-16-2018	What is the elevation of the electrical and fiber optic duct banks?	The elevation of the electrical and fiber duct banks are unknown. They will have to be field verified during excavation. The depth is graphically shown to the best of our knowledge on Detail 4/AS-1.
26.	4-14-2018	4-17-2018	Where is the contractor's laydown area and location for construction trailer, etc?	The laydown space will have to be shared with the construction of the MRI Building. Per the contractor's construction schedule for the MRI it will be completely enclosed in September. This will significantly free up space in Lot M for the stairwell construction. Also, once we have the pre-construction meeting for Correct Life Safety we will coordinate a meeting to discuss Laydown Space with the MRI Contractor.
27.	4-16-2017	4-16-2018	On sheet AD8-07W Demolition note 06 says: "Contractor shall sole source contract with Prism Medical INC. to remove patient lift." It does not give any contact information or anything. Who would be the point of contact for Prism INC. Do you have a number?	Installer POC: Charlie Swanson (cjswanson1992@gmail.com) #320-282-5301
28.	4-17-2018	4-19-2018	Ives Continuous Hinges are specified. On some of the hardware sets the continuous hinge needs an adjusta screw. I do not believe that is an option for Ives Continuous Hinges.	Will be addressed in Addendum 00005. See Addendum 00005 documents posted on 4/20/2018, as part of Amendment 00005.
29.	4-17-2018	4-19-2018	What is an "integral Hinge Guard Channel" specified in hardware set SH-3F? Would that be a Finger Guard?	This is continuous hinge with a door edge guard incorporated into one side of the hinge.
30.	4-17-2018	4-19-2018	Set 4z calls for two passage sets? Is that a mistake? It is possible on Dutch doors but usually we see one lockset on the lower leaf with a surface bolt on the top leaf.	Two passage sets for the dutch doors are correct. These are for the corridor side of the doors to the patient room nurse servers. This matches other existing nurse server doors. Latching of both leaves are required.

31.	4-17-2018	4-19-2018	Set SH4A calls for an “alarm contact”. Would you have any idea what they are wanting for this?	“Alarm Contact” is defined in the “Security Hardware Abbreviations Legend” in Specification Section 08 71 00, Page 25 as a “Door Position Switch”.
32.	4-17-2018	4-19-2018	Set 12h Calls for 2 utility locks for a pair of doors. This would work only if a removable mullion would be include in the hardware set or non-removable mullion is part of the frame.	Will be addressed in Addendum 00005. See Addendum 00005 documents posted on 4/20/2018, as part of Amendment 00005.
33.	4-17-2018	4-19-2018	Sets 1K and 4P call for two sets of Self-Adhesive Seals? Is this Correct?	Will be addressed in Addendum 00005. See Addendum 00005 documents posted on 4/20/2018, as part of Amendment 00005.
34.	4-17-2018	4-19-2018	What Floor Plan Page is opening TD on?	TD is an abbreviation for “Temporary Door”. This is intended for doors in temporary construction walls. The temporary construction wall locations are shown on the demolition plans. TD is referenced on the temporary construction wall types 5A/5B on sheet AT1.
35.	4-17-2018	4-19-2018	Should we use hardware set X1 or X2 on opening TD? It says both on door schedule.	Set X1 is intended for the typical temporary construction door. The doors on floor 9 (mental health) have other requirements and are noted as set X2 in Specification Section 08 71 00.
36.	4-17-2018	4-19-2018	Note 7 on page A2-01W is indicating a display case. Is that to be hollow metal and is there an elevation for it?	It is OF/CI (Owner furnished, Contractor installed). The intent is a wall mounted display. It is also shown on Detail 1/AS4.
37.				
38.				
39.				
40.				
41.				
42.				
43.				
44.				

45.				
46.				
47.				

