

ADDENDUM NO. 00005

to the
Specifications and Drawings

19 APRIL 2018

**IOWA CITY VA HEALTH CARE SYSTEM
CORRECT LIFE SAFETY DEFICIENCIES**
Iowa City, Iowa

VA Project: 636A8-16-006

KENNETH HAHN ARCHITECTS
Architecture/Planning/
Interior Design/Engineering
1343 South 75th Street
Omaha, Nebraska 68124

KHA Project No. 171-005

NOTICE TO BIDDERS: The Specification and Drawings for the above-referenced project are hereby amended as follows:

SPECIFICATIONS – VOLUME 1

ITEM NO. S-01, SECTION 08 71 00, DOOR HARDWARE

- A. Paragraph 3.5, Hardware Sets:
- a. Page 22, Set HW-4Y: Delete the words “X ADJUSTA-SCREWS” from the Hinges.
 - b. Page 22, Set HW-4Z: Delete the words “X ADJUSTA-SCREWS” from the Hinges.
 - c. Page 26, Set HW-SH-3F: Delete the words “X ADJUSTA-SCREWS” from the Continuous Transfer Hinge.
 - d. Page 27, Set HW-SH-4A: Delete the words “X ADJUSTA-SCREW” from the Continuous Hinge.
 - e. Page 30, Set HW-MH5: Delete the words “X ADJUSTA-SCREWS” from the Continuous Hinge.
 - f. Page 31, Set HW-MH5A: Delete the words “X ADJUSTA-SCREWS” from the Continuous Hinge.
 - g. Page 32, Set HW-X2: Delete the words “X ADJUSTA-SCREWS” from the Continuous Hinge.
- B. Paragraph 3.5, Hardware Sets, Page 19, Set 1K:
- a. Revise Self-Adhesive Seals from 2 sets to 1 set.
- C. Paragraph 3.5, Hardware Sets, Page 21, Set 4P:
- a. Revise Self-Adhesive Seals from 2 sets to 1 set.
- D. Paragraph 3.5, Hardware Sets, Page 24, Set HW-12H:
- a. Delete the entire set and replace with the following:

Hinges		QUANTITY & TYPE AS REQUIRED
2	Exit Device	TYPE 2 F08 LEVER
2	Key Cylinder	TYPE AS REQUIRED
2	Kick Plate	J102
2	Floor Stop	L02121 x 3 FASTENERS
2	Set Self-Adhesive Seals	R0Y154
AUTO DOOR OPERATORS (BOTH LEAFS) AND CONTROLS BY SECTION 08 71 13.		

ITEM NO. S-02, SECTION 08 88 00, GLAZING

- A. Replace this section in its entirety with Attachment No. 1.

DRAWINGS – VOLUME 1

ITEM NO. D-01, SHEET A2-01W – FIRST FLOOR PLAN

- A. Detail 1, First Floor Plan:
- a. Revise the location of the automatic door operator controls at door 1CP01B as shown on the attached revised sheet A2-01W.

ITEM NO. D-02, SHEET AH1 – ROOM FINISH SCHEDULE

- A. Schedule for Finishes:
- a. At “08 80 00 GLAZING”, delete the line ‘SOLARCOOL BRONZE BY PPG, MATCH EXISTING’ and replace with the following “SOLARCOOL SOLARBRONZE BY PPG (VITRO), MATCH EXISTING COLOR”.

ITEM NO. D-03, SHEET AT20 – MISCELLANEOUS DETAILS

- A. Detail 4, TV Cover At Group Room 9W42:
- a. Replace the note “SG#1” with the note “SG#2”.

ITEM NO. D-04, SHEET AH2 – DOOR SCHEDULE

- A. Door and Frame Schedule:
- a. At door 1W70, delete Door Glass note “BR” and replace with note “SG#2”.
- B. Door Schedule Legend:
- a. Add the following line: “IL INSULATED LAMINATED GLAZING”
- C. Detail 3, Hollow Metal Frame Types:
- a. At the frame type “F02” to the far left of the detail, rename frame type to read “F04”.
 - b. At frame type “F03”, delete the note “LG#_” and replace with the following note “LG#1”.
 - c. At frame type “F04”, delete the note “LG#_” and replace with the following note “LG#1”.
- D. Detail 5, Service and Teller Window Unit
- a. Delete the note “UL RATED LEVEL 1 BULLET RESISTANT ACRYLIC INCLUDING WALL SECTIONS, WINDOWS” and replace with the following note “UL752 LEVEL 3 GLAZING WITH SECURE AIR PASSAGE AS REQUIRED FOR VOICE TRANSMISSION.”.

DRAWINGS – VOLUME 2

ITEM NO. D-05, SHEET M3 – MECHANICAL SCHEDULES

- A. Fan Coil Unit Schedule:
- a. Revise remark 5 as shown on the attached revised sheet M3.
- B. Variable Frequency Drive Schedule:
- a. Revise the schedule as shown on the attached revised sheet M3.

ITEM NO. D-06, SHEET M4 – MECHANICAL SCHEDULES

- A. Built-up Air Handling Unit Schedule:
- a. Revise the schedule as shown on the attached revised sheet M4.

ITEM NO. D-07, SHEET EP2-01W – POWER FIRST FLOOR PLAN

- A. Electrical Keynotes:
- a. Revise keynote 18 as shown on the attached revised sheet EP2-01W.

ITEM NO. D-08, SHEET EY2-01W – SPECIAL SYSTEMS FIRST FLOOR PLAN

- A. Detail 1, Special Systems First Floor Plan:
- a. Revise the location of the special systems associated with door 1CP01B as shown on the attached revised sheet EY2-01W.

ITEM NO. D-09, SHEET E4 – ELECTRICAL SCHEDULES

A. Luminaire Schedule – Luminaire Schedule Remarks:

- a. Note 7: Delete the note in its entirety and replace with the following: “Not used.”.