



Questions & Answers

Project: Activation – LV16a – OR Media Integration Device Covers

Solicitation: RFQ 36C25918Q0306 – **Amendment 0002**

Location: Denver VA Replacement Medical Center - 13611 East Colfax Ave, Aurora, CO 80045

Date: April 24th, 2018

Q1) Please confirm that the scope of this project will not require infection control.

A1) Will not require infection control, ORs are inactive

Q2) Please confirm the final total number of monitors that will need to have covers.

A2) 36

Q3) Please confirm the cabinet material requirements or if sealed laminated MDF is acceptable.

A3) Sealed laminated MDF is not acceptable. Metal or plastic

Q4) Can you please provide the remaining available weight capacity of the dual monitor arms, now that each has two (or one) monitor and covers? Specifically, we are trying to determine the amount of weight available for the covers.

A4) Single monitor arm can hold 43 lbs – 14 lb yoke – 18 lb monitor – 1 lb cables and cover = **~10 lbs remaining**

Dual monitor arm can hold 60 lbs – 28 lb yoke – 26 lb monitors – 2 lb cables and cover = **~4 lbs remaining**

Q5) In providing covers for the monitors, Stryker believes that the cables will have to be disconnected/reconnected and managed to fit within the cover space. Will the government make a Stryker tech available under the current contract warranty, or should we include the cost of a Stryker tech in this proposal?

A5) Stryker tech will be available under current contract

Q6) Can you provide cut sheets/technical specifications for the AMICO monitor arms?

A6) Specs: http://www.amico.com/sites/default/files/products/acs_sp_vt_spring_arm.pdf

Also see specific weight calculations above

Q7) Can you please determine if modification of existing backplates on the Stryker 26” VisionPro LED displays is acceptable or if separate standalone covers are required?

A7) Modification of existing backplates is acceptable

Q8) Can you please provide us with the specs for the countertops in the ORs? The manufacture/type of counter as well as color match info?
A8) Counters are Dupont Corian solid surface, color: Savannah