

Repair Dental and Medical Compressors VA Greater Los Angeles, Building 501

RFI #1 - We would request clarification on the Medical and Dental Air Intake sizing. The contract documents call out for upsizing to a single 1-1/2" Solberg Filter Housing. We feel this will be too small if in the event 2 or more of compressors, each of which has a 1-1/4" intakes were to cycle at the same time. This will happen from time to time and when it does it will create a vacuum on the intakes.

We would suggest a 2-1/2" In line filter assembly in the mainline to avoid the vacuum on the intakes happening.

Government Response to RFI Question #1 – The VA acknowledges that the line filter assembly should be 2 ½". Section 1.2.2 of the Statement of Work is amended as:

Section 1.2.2 "Provide and install (2) Solberg 851 2½" filters and modify 2" piping to provide 2 ½" remote intake for each medical and dental system."