

Attachment A

Changes to Improved Security Access Control & Monitoring System NLR

This is about the Improved Security Access Control/Monitoring System for NLR. On the last page of the prints page **TY502**. Please review the changes below when making your bid for this contract.

Under Proposed Equipment

Quantity in Building: the 6th line item shows 3 wireless radios FM1200 VOLO's. There are none for in building and quantity should be zero.

Site Plan column indicates 8 wireless radios FM1200 should be 10.

Base Floor South column: indicates 45 Sony SNC-XM631's. New total for the Base Floor South should be 43 Sony SNC-XM631's.

Base Floor North column indicates 21 Sony SNC-XM631's. New total for the Base Floor North should be 37 Sony SNC-XM631's.

First Floor South column indicates 50 Sony SNC-XM631's. New total for the First Floor North should be 49 Sony SNC-XM631's.

First Floor North column indicates 52 Sony SNC-XM631's. New total for the Base Floor North should be 54 Sony SNC-XM631's.

Second Floor North column indicates 30 Sony SNC-XM631's. New total for the Second Floor North should be 32 Sony SNC-XM631's.

Hirsch Parts

The middle column row 9 shows M8N2 should be MXM8; this is the new Hirsch controller that is used for access control.

The middle column row 10 shows M2N2 should be MXM4; they do not make the M2 panel any longer. The least number of doors in a controller is 4.

This is about the Improved Security Access Control/Monitoring System for NLR. On the last page of the prints page **TY501**. Please review the changes below when making your bid for this contract.

On print/page TY501 detail #1 it shows a picture of a Sony SNC-EM631, there are no EM631 cameras associated with NLR project. There are no pictures for the majority of the XM631's to replace with. Ignore this picture and part numbers.

Middle page of TY501 detail # 5 shows the M8 controller, should have reflected the correct part number which is MXM8 for an 8-door panel or MXM4 for a 4-door or less panel.

Attachment A (Cont')

Changes to Improved Security Access Control & Monitoring System NLR

Important Bidding Note: when bidding on the access control portion for this contract each bid needs to be based on the access control chart located on sheet TY502. The different floor plans DO NOT show the specific locations of where access control is required.

Additional camera (model # EM631) required for building 65 (VBA) on Ground Floor West entrance elevator. This will be in addition to the 3 cameras already identified on the prints page TS102.