

SCOPE OF WORK

DESIGN & INSTALL NEW IRRIGATION SYSTEM QUINCY NATIONAL CEMETERY, QUINCY, ILLINOIS 62301

- A. The Contractor: Shall furnish all labor, material, equipment, and supervision to verify existing conditions, design and install a new irrigation system, as described herein.
- B. The Work: The Work shall include, but shall not be limited to the following (not necessarily in the order indicated):
1. Contractor shall field verify existing conditions, i.e., cemetery property lines, location, size and pressure of existing water supply; location, voltage and amperage of existing electrical service; etc. and develop plans and specifications for a new underground automatic irrigation system for the Quincy National Cemetery in accordance with all applicable codes and regulations. The new irrigation system shall be an automatic, zoned sprinkler system capable of providing a minimum equivalent of 2" of water over the entire cemetery property per week with the hours of operation being from 10:00pm through 6:00am.
 2. Contractor shall provide all supervision, labor, materials, tools, and equipment to install the new underground irrigation system. All electrical tie-ins shall comply with the National Electrical Code (NEC). All plumbing tie-ins shall be compliance with International Plumbing Code (IPC). The irrigation system shall be installed and operated in accordance with all applicable local, state and federal codes and regulations.
 2. Haul away & dump debris and waste to an approved disposal site.
 3. Thoroughly clean up the work area at the end of each day's work, and at completion of the project. Leave premises clean and free of waste, scrap, used equipment, or other material intentionally or incidentally delivered to the site by Contractor or Contractor's personnel.
- C. Time of Completion: The project shall be completed within 45 calendar days after contract award.
- D. Code Compliance: All work shall be performed in accordance with the International Building Code (IBC), the International Plumbing Code (IPC), and the National Electrical Code (NEC).
- E. Contractor Quality Control: The Job Site Superintendent will: a) review and approve submittals, b) inspect the quality of work performed, and c) certify the completed work for payment and other purposes.
- F. Availability/Constraints of Site: See attachments: Specification Section 010000, "General Requirements", Specification Section 013323, "Submittals", Specification Section 220511, "Common Plumbing Work", Specification Section 312011, "Earth Moving", Specification Section 328400, "Planting Irrigation", and "*Quincy National Cemetery - Additional Information and Requirements.*"
- G. Submittals After Award: See attachment "Specification Section 013323, Submittals".
- H. Plans/details: Site Plan.
- I. POC: The Contracting Officer's Technical Representative (COTR) for this project is: Paul George.
- J. Project completion: The project site shall be protected and/or restored to a condition equal to that existing prior to the commencement of work.

END OF SCOPE OF WORK