

Monday, January 29, 2018  
10:03 PM

## CLC Loading Dock

Box style Cantilever Gate 45' with 25' opening  
Viking Access Systems  
Model L-3  
S/N 0210-S3B-17341

- **Condition Found:** Operator is severely damaged and weatherized. It is full of debris and sand. (See Pictures below). Motor seized and inoperable power was tested and is correct voltage for unit.
- **Action:** Replace with new HySecurity Slide Driver Like others on campus use nickel plated chain to ensure trouble free operations
- 
- **Condition Found:** 1 @ 5' Millers Safety was damaged after the gate contract was awarded. (See Figure 2 Below)
- **Action:** Replace Safety Edge and transmitter/Receiver pair gate to bring up to UL325 standard and ensure safe gate operation
- 
- **Condition Found:** Photo Beam not operational
- **Action:** Replace with new photo beam to ensure safe operations

**Condition Found:** Gate its self appears to be in good condition



**WARNING** - The switch "indicator" must match the voltage provided to the unit.

Voltage (AC- 1 Phase)	Switch Selector
100-120	115
200-240	230

**VIKING**  
ACCESS SYSTEMS™

Vehicular Gate Operator  
Model L-3

Date: 3/2/2012



SN#

0212-S3B-17341

Volts (VAC)	Freq (Hz)	Amps	Phase	Max Gate Weight (lbs)	Max Gate Length (ft)
120	50-60	1.50	1	1200	10
240	50-60	1	1	1200	10

Max Duty Cycle	Max Speed
100 %	12 in/sec

UL 325  
Classifications

Class I  
Class II  
Class III  
Class IV

