



KEYSTONEAUTOMATION

BED BUG OVEN

The Keystone Automation Bed Bug Oven was developed to kill bed bugs using high temperature air. It is 6 feet tall, wide and deep with 216 cubic feet of storage area.

Keystone can manufacture the oven to any size to meet your needs.



The oven has a clothes hanging area and four shelves to store clothing, bedding or other items. The shelves and center support can be removed to allow larger items to be inserted. The oven features include 1" thick fiberglass insulation, door switches and over temperature switches on the heater modules. Power supply is 115VAC and plugs into a standard wall outlet.





Keystone Bed Bug Oven Specifications:

- Self-contained insulated cabinet uses 2 electric heating elements and a gentle forced air system controlled by a digital controller that maintains temperature within 5 degrees.
- Two removable heater/fan modules mounted to bottom of unit. Integral ducting to draw air from top of unit.
- Two battery-powered digital thermometers mounted outside the oven have probe extensions that can be placed in items being treated to ensure that the proper temperature (120°F) has been reached.
- Construction is heavy-duty, all steel powder coated cabinet mounted on locking casters for mobility
- Inside of the oven has one or two clothes hanging bar on one side and four removable shelves on the other side
- The shelves and the center divider are removable so larger items can be placed in the oven.
- 1" of fiberglass insulation is provided. All seams and joints are foil taped.

