

Contractor shall completely prepare site for operations, furnish labor, and materials to perform work for the Building 21 Crawl space as required by drawings and specifications. Remove debris from crawl space, Grade earth in space so that water flows toward the west side of the crawl space to the drain pit locations, and from the west side to the pit location. Install interior drains, provided pump pumps, seal the crawl space, install liner, and install provided dehumidifying system. Install electrical components, and insulate outer walls of crawl space.

The contractor shall install an interior French drain with a 4 inch perforated corrugated pipe wrapped in silk screening material and protected with a gravel bed. The pipe will generally be placed 12 to 18 inches off the footer so as not to disrupt any termite treatment field the drain will average 10 inches wide and 12 inches deep.

The contractor shall dig twelve (12) 24-36 inch deep by 6 feet in diameter sump pits per drawing, and grading the earth in the crawl space from the outer walls to the sump pits. The drain system will be tied into the 12 different sump pits. These pits with will consist of a perforated polyethylene liner installed in the hole surrounded by crushed stone with a solid cover including a drain for any surface water that may come from above. A 1/3 hp sump pump, with a check valve and 1 1/2 inch PVC discharge pipe will take all the channeled water and pump it out of the crawlspace through an drain pipe and away from the foundation.

There will be cut through the foundation wall a hole large enough for an 18" pipe to exit the building. The sump pumps will be piped to this location by drawing and will be attached and sealed into an 18 inch double walled pipe that will be extended to the storm water ditch located south west of the building by the existing city discharge culvert.

Each unit can pump 5000 gallons per hour with the system total of 60,000 gallons per hour.

The contractor is to install a 42 space 225 amp breaker panel in the basement area by crawl space the power is to be run from room 8C-116 the contractor shall find and procure a suitable 300 amp breaker for the switch gear and install. The contractor shall make the connection according to NEC in conduit and copper wire. From equipment to the breaker panel the contractor shall use solid number 12 THHN copper wire to each pump compressor and dehumidifier in crawlspace of building 21. The wire will be encased in three-quarter inch EMT pipe with compression fittings installation and will include hangers and breakers were necessary according to the NEC. This will be connected to the new power panel in the basement adjacent to the crawl space.

The contractor is to install eight (8) commercial Santa Fe Max Dry Dual XT and dehumidifiers Provided by the VA. To ensure optimal performance, the air inlet and the outlet of the unit will be at least 1 inch from walls and other obstacles to airflow. They will be placed on anti-vibration steel spring lift suspension mounts with four per unit. The condensate drains shall be attached in a manner to allow water to flow away from the unit by gravity via the drain port. Three-quarter inch PVC drainage pipe to the sump pits from each Santa Fe dehumidifier.

Each Santa Fe dehumidifier can extract up to 150 pints of moisture per day total system moisture extraction up to 75 gallons a day.

The contractor will have Boro-care with Mold-care dilution applied to the insulation covering the water piping in crawlspace where moisture has discolored it over time.



The contractor is to install 6 mm three layer laminated polyethylene wall liner paper retarded along the length of the interior foundation wall seal at top of foundation wall and bottom 24 liners rap peers with six mill three plays polyethylene liner. Fasten 1 1/2 inch Dowel Thermax insulation board to all exterior masonry wall over wall liner. Apply foam insulation to seal all penetrations from crawlspace to living area. Install 12 mm three ply polyethylene for liner to soil to climate control areas of crawlspace. Tape liner to wall and all peer liners and insulate before installation. Seal all joints with 4 inch adhesive tape.


Liner and insulate will close crawlspace to outside air to create conditioned air environment to control humidity levels throughout crawlspace to promote clean and healthy air in the living area and working areas above.



Crawlspace humidity levels shall be centrally monitored. Panel is to be mounted in basement near new electrical panel.

The contractor is to provide the Monitoring device The Santa Fe # 4026208 or equivalent.

The contractor is to remove all construction debris from the crawlspace and dispose of according to all applicable laws.



		RECOMMEND APPROVAL				Drawing Title		Project Title		Date			Department of Veterans Affairs		
		REQUESTER		Date			COVER SHEET		BUILDING 21 CRAWL		24 Jul 2012				
		CHIEF OF SERVICE		Date	CHIEF OF STAFF		Date	SPACE DRYING PROJECT		Project No. 659-12-240 D/B					
		ASSOC. DIR. PATIENT CARE SVC.		Date	ASSOC. DIR. for OPERATIONS		Date	Approved: Safety Manager/M&O Supervisor		Building Number				Checked	Drawn
										21				NEJ	
APPROVAL BY:				Date	Approved: Chief of Facilities Management Svr.		Location		W.G.(Bill) Hefner Medical Center 1801 Brenner Ave. Salisbury NC 28144		DRAWING NO. G-000				
MEDICAL CENTER DIRECTOR											DWG. 1 of 4				
Revision	Date														



Collection pit



DEHUMIDIFIER

General Note

The contractor shall install an interior French drain with a 4 inch perforated corrugated pipe wrapped in silk screening material and protected with a gravel bed. The pipe will generally be placed 12 to 18 inches off the footer so as not to disrupt any termite treatment field the drain will average 10 inches wide and 12 inches deep.

The contractor shall dig twelve (12) 24-36 inch deep by 6 feet in diameter sump pits per drawing, and grading the earth in the crawl space from the outer walls to the sump pits. The drain system will be tied into the 12 different sump pits. These pits will consist of a bed of crushed stone with a perforated polyethylene liner installed on the bed in the hole then surrounded by crushed stone. The polyethylene liner will have a solid cover which will include a drain for any surface water that may come from above. A 1/2 hp sump pump, with a check valve and 1 1/2 inch PVC discharge pipe will take all the channelled water and pump it out of the crawlspace through an drain pipe and away from the foundation.

There will be a hole cut through the foundation wall large enough for an 18" pipe to exit the building. The penetration shall be sealed between the pipe and the wall. The sump pumps will be piped to this. As specified by drawing and will be attached and sealed into an 18 inch double walled pipe that will be extended to the storm water ditch located south west of the building by the existing city discharge culvert. The pipe shall be supported by hangers in the crawl space from the floor above. The pipe out side the building shall be buried in a trench. The pipe shall be bedded in sand and compacted the disturbed earth shall be tilled and seeded with rescue 31.

The contractor is to install eight (8) commercial Santa Fe Max Dry Dual XT and dehumidifiers. Provided by the VA. To ensure optimal performance, the air inlet and the outlet of the unit will be at least 1 inch from walls and other obstacles to airflow. They will be placed on for anti-vibration steel spring light suspension mounts with four per unit. The condensate drains shall be attached in a manner to allow water to flow away from the unit by gravity via the drain port. Three-quarter inch PVC drainage pipe to the sump pits from each Santa Fe dehumidifier.

The contractor will have Boro-care with Mold-care dilution applied to the insulation covering the water piping in crawlspace where moisture has discolored it over time.

The contractor is to install 6 mm three layer laminated polyethylene wall liner paper retarded along the length of the interior foundation wall seal at top of foundation wall and bottom 24 lines rap peers with six mill three plays polyethylene liner. Fasten 1 1/2 inch Dowel Thermax insulation board to all exterior masonry wall over wall liner. Apply foam insulation to seal all penetrations from crawlspace to living area. Install 12 mm three ply polyethylene for liner to soil to climate control areas of crawlspace. Tape liner to wall and all peer liners and insulate before installation. Seal all joints with 4 inch adhesive tape.


The contractor is to provide the Monitoring device The Santa Fe # 4026208 or equivalent.

GROUND FLOOR SOUTH END OF BUILDING 21

SOUTH END OF BUILDING 21
1/8" = 1'

Revision		Date																																																																							
<table><tr><td colspan="4">RECOMMEND APPROVAL</td><td colspan="2">Drawing Title</td><td colspan="2">Project Title</td><td colspan="2">Date</td></tr><tr><td>REQUESTER</td><td>Date</td><td>CHIEF OF SERVICE</td><td>Date</td><td>CHIEF OF STAFF</td><td>Date</td><td colspan="2">SOUTH CRAWL SPACE EQUIPMENT PLACEMENT</td><td colspan="2">BUILDING 21 CRAWL SPACE DRYING PROJECT</td><td colspan="2">24 Jul 2012</td></tr><tr><td>ASSOC. DIR. PATIENT CARE SVC.</td><td>Date</td><td>ASSOC. DIR. for OPERATIONS</td><td>Date</td><td colspan="2"></td><td colspan="2">Approved: Safety Manager/M&O Supervisor</td><td>Building Number</td><td>Checked</td><td>Drawn</td><td>Project No.</td></tr><tr><td colspan="4">APPROVAL BY:</td><td colspan="2">Date</td><td colspan="2">Approved:Chief of Facilities Management Svr.</td><td>21</td><td>NEJ</td><td>NEJ</td><td>659-12-240 D/B</td></tr><tr><td colspan="4">MEDICAL CENTER DIRECTOR</td><td colspan="2"></td><td colspan="2"></td><td>Location</td><td colspan="2">W.G.(BII) Hefner Medical Center 1601 Brenner Ave Salisbury NC 28144</td><td>DRAWING NO. M-100</td></tr><tr><td colspan="4"></td><td colspan="2"></td><td colspan="2"></td><td colspan="2"></td><td colspan="2">DWG. 2 of 4</td></tr></table>				RECOMMEND APPROVAL				Drawing Title		Project Title		Date		REQUESTER	Date	CHIEF OF SERVICE	Date	CHIEF OF STAFF	Date	SOUTH CRAWL SPACE EQUIPMENT PLACEMENT		BUILDING 21 CRAWL SPACE DRYING PROJECT		24 Jul 2012		ASSOC. DIR. PATIENT CARE SVC.	Date	ASSOC. DIR. for OPERATIONS	Date			Approved: Safety Manager/M&O Supervisor		Building Number	Checked	Drawn	Project No.	APPROVAL BY:				Date		Approved:Chief of Facilities Management Svr.		21	NEJ	NEJ	659-12-240 D/B	MEDICAL CENTER DIRECTOR								Location	W.G.(BII) Hefner Medical Center 1601 Brenner Ave Salisbury NC 28144		DRAWING NO. M-100											DWG. 2 of 4	
RECOMMEND APPROVAL				Drawing Title		Project Title		Date																																																																	
REQUESTER	Date	CHIEF OF SERVICE	Date	CHIEF OF STAFF	Date	SOUTH CRAWL SPACE EQUIPMENT PLACEMENT		BUILDING 21 CRAWL SPACE DRYING PROJECT		24 Jul 2012																																																															
ASSOC. DIR. PATIENT CARE SVC.	Date	ASSOC. DIR. for OPERATIONS	Date			Approved: Safety Manager/M&O Supervisor		Building Number	Checked	Drawn	Project No.																																																														
APPROVAL BY:				Date		Approved:Chief of Facilities Management Svr.		21	NEJ	NEJ	659-12-240 D/B																																																														
MEDICAL CENTER DIRECTOR								Location	W.G.(BII) Hefner Medical Center 1601 Brenner Ave Salisbury NC 28144		DRAWING NO. M-100																																																														
										DWG. 2 of 4																																																															





General Note

The contractor shall install an interior French drain with a 4 inch perforated corrugated pipe wrapped in silt screening material and protected with a gravel bed. The pipe will generally be placed 12 to 18 inches off the footer so as not to disrupt any termite treatment field the drain will average 10 inches wide and 12 inches deep.

The contractor shall dig twelve (12) 24-36 inch deep by 6 feet in diameter sump pits per drawing, and grading the earth in the crawl space from the outer walls to the sump pits. The drain system will be tied into the 12 different sump pits. These pits will consist of a bed of crushed stone with a perforated polyethylene liner installed on the bed in the hole then surrounded by crushed stone. The polyethylene liner will have a solid cover which will include a drain for any surface water that may come from above. A 1/3 hp sump pump, with a check valve and 1 1/2 inch PVC discharge pipe will take all the channeled water and pump it out of the crawlspace through on drain pipe and away from the foundation.


There will be a hole cut through the foundation wall large enough for an 18" pipe to exit the building. The penetration shall be sealed between the pipe and the wall. The sump pumps will be piped to this As specified by drawing and will be attached and sealed into an 18 inch double walled pipe that will be extended to the storm water ditch located south west of the building by the existing city discharge culvert. The pipe shall be supported by hangers in the crawl space from the floor above. The pipe out side the building shall be buried in a trench. The pipe shall be bedded in sand and compacted the disturbed earth shall be tiled and seeded with grass 31.

The contractor is to install eight (8) commercial Santa Fe Max Dry Dual XT and dehumidifiers. Provided by the VA. To ensure optimal performance, the air inlet and the outlet of the unit will be at least 1 inch from walls and other obstacles to airflow. They will be placed on for anti-vibration steel spring tight suspension mounts with four per unit. The condensate drains shall be attached in a manner to allow water to flow away from the unit by gravity via the drain port. Three-quarter inch PVC drainage pipe to the sump pits from each Santa Fe dehumidifier.

The contractor will have Boro-care with Mold-care dilution applied to the insulation covering the water piping in crawlspace where moisture has discolored it over time.

The contractor is to install 6 mm three layer laminated polyethylene wall liner paper retarded along the length of the interior foundation wall seal at top of foundation wall and bottom 24 liners rap peers with six mil three ply polyethylene liner. Fasten 1 1/2 inch Dowel Thermax insulation board to all exterior masonry wall over wall liner. Apply foam insulation to seal all penetrations from crawlspace to living area. Install 12 mm three ply polyethylene for liner to soil to climate control areas of crawlspace. Tape liner to wall and all peer liners and insulate before installation. Seal all joints with 4 inch adhesive tape.


The contractor is to provide the Monitoring device The Santa Fe # 4026208 or equivalent.



TYPICAL VIEW OF HUMIDITY CONTROL SYSTEM FOR 21

GROUND FLOOR NORTH END OF BUILDING 21

NORTH END OF BUILDING 21
1/8" = 1'

Revision	Date	RECOMMEND APPROVAL				Drawing Title	Project Title	Date		
		REQUESTER	Date	CHIEF OF SERVICE	CHIEF OF STAFF	NORTH CRAWL SPACE	BUILDING 21 CRAWL SPACE DRYING PROJECT	24 Jul 2012		
		ASSOC. DIR. PATIENT CARE SVC.	Date	ASSOC. DIR. for OPERATIONS	Date	Approved: Safety Manager/M&O Supervisor	Building Number	Checked	Drawn	Project No.
		APPROVAL BY:				Approved: Chief of Facilities Management Svr.	21	NEJ		659-12-240 D/B
		MEDICAL CENTER DIRECTOR					Location	W.G.(BII) Hefner Medical Center 1601 Brenner Ave Salisbury NC 28144		DRAWING NO. M-101 DWG. 3 of 4

