

Line Item	Description	Qty	Unit	Price	Cost
0001	Post Sterile Storage Cabinet Manufacturer: SBB Part Number: SSC4300 Or Equal	8	EA		
Total Cost					

Salient Characteristics

- Cleanable storage cabinet for post sterilized medical instruments
- Control temperatures, humidity and pressure for stored Dental Instruments, to meet requirements of VA Directive 1116(2)
 - Maintain 66 – 75 degrees F temperature (set point 70 degrees F)
 - VA approved humidification: Maintain humidity at 20 – 60% RH
 - Maintain positive pressure (+0.03"WC), pressure monitoring with alarm
- Digital display for monitoring temperature humidity status.
- Mounted on casters for mobile storage
- Battery backup
- Self-modulating fan
- HEPA filtration system
- Dimensions should not exceed 76"H X 33"W X 28"D
- See-through glass door
- Stainless steel pull out shelves with adjustable height
- 120 V hospital grade, with at least 10 ft. long cord
- At least a 1-year Warranty for parts