

LUMINAIRE SCHEDULE								
FIXTURE LETTER	FIXTURE TYPE	VOLTAGE	MOUNTING	LAMPS	CONTROL MEDIA (LENS, LOUVER, ETC.)	MANUFACTURER'S SERIES NUMBERS	LUMINAIRE DESCRIPTION	NOTES
A	2X4 LENSED TROFFER	120V	RECESSED LAY-IN GRID INVERTED TEE	3-F28 T8 4100K	.125" MINIMUM ACRYLIC LENS FLAT SIDED PRISMS	COLUMBIA #ST824 SERIES LITHONIA #2SP8 SERIES METALUX #2GC8 SERIES DAY-BRITE #2DPC SERIES LIGHTOLIER #SPS2 SERIES WILLIAMS #50G-S24 SERIES	SPRING LATCHES. POST PAINTED STEEL HOUSING. FLUSH WHITE ALUM. MITERED CORNERED DOOR FRAME. GASKETED AND/OR WITH METAL LIGHT Baffles. DOOR CAN BE LATCHED FROM EITHER SIDE OF HOUSING. 3-11/16" MINIMUM HOUSING DEPTH. ONE ELECTRONIC BALLAST.	-
A1	2X4 LENSED TROFFER DUAL LEVEL SWITCHED	120V	RECESSED LAY-IN GRID INVERTED TEE	3-F28 T8 4100K	.125" MINIMUM ACRYLIC LENS FLAT SIDED PRISMS	COLUMBIA #ST824 SERIES LITHONIA #2SP8 SERIES METALUX #2GC8 SERIES DAY-BRITE #2DPC SERIES LIGHTOLIER #SPS2 SERIES WILLIAMS #50G-S24 SERIES	SPRING LATCHES. POST PAINTED STEEL HOUSING. FLUSH WHITE ALUM. MITERED CORNERED DOOR FRAME. GASKETED AND/OR WITH METAL LIGHT Baffles. DOOR CAN BE LATCHED FROM EITHER SIDE OF HOUSING. 3-11/16" MINIMUM HOUSING DEPTH. TWO ELECTRONIC BALLASTS. (1)-ONE LAMP AND (1)-TWO LAMP.	-
A1m	2X4 LENSED TROFFER DUAL LEVEL SWITCHED MASTER	120V	RECESSED LAY-IN GRID INVERTED TEE	3-F28 T8 4100K	.125" MINIMUM ACRYLIC LENS FLAT SIDED PRISMS	COLUMBIA #ST824 SERIES LITHONIA #2SP8 SERIES METALUX #2GC8 SERIES DAY-BRITE #2DPC SERIES LIGHTOLIER #SPS2 SERIES WILLIAMS #50G-S24 SERIES	SPRING LATCHES. POST PAINTED STEEL HOUSING. FLUSH WHITE ALUM. MITERED CORNERED DOOR FRAME. GASKETED AND/OR WITH METAL LIGHT Baffles. DOOR CAN BE LATCHED FROM EITHER SIDE OF HOUSING. 3-11/16" MINIMUM HOUSING DEPTH. TWO ELECTRONIC BALLASTS FOR DUAL LEVEL SWITCHING (1) 4 LAMP BALLAST & (1) 2 LAMP BALLAST.	-
A1s	2X4 LENSED TROFFER DUAL LEVEL SWITCHED SATELLITE	120V	RECESSED LAY-IN GRID INVERTED TEE	3-F28 T8 4100K	.125" MINIMUM ACRYLIC LENS FLAT SIDED PRISMS	COLUMBIA #ST824 SERIES LITHONIA #2SP8 SERIES METALUX #2GC8 SERIES DAY-BRITE #2DPC SERIES LIGHTOLIER #SPS2 SERIES WILLIAMS #50G-S24 SERIES	SPRING LATCHES. POST PAINTED STEEL HOUSING. FLUSH WHITE ALUM. MITERED CORNERED DOOR FRAME. GASKETED AND/OR WITH METAL LIGHT Baffles. DOOR CAN BE LATCHED FROM EITHER SIDE OF HOUSING. 3-11/16" MINIMUM HOUSING DEPTH. NO ELECTRONIC BALLASTS. TANDEM WIRED WITH FIXTURE TYPE "A1m" (DUAL LEVEL SWITCHING).	-
A2	2X4 LENSED TROFFER	120V	RECESSED LAY-IN GRID INVERTED TEE	2-F28 T8 4100K	.125" MINIMUM ACRYLIC LENS FLAT SIDED PRISMS	COLUMBIA #ST824 SERIES LITHONIA #2SP8 SERIES METALUX #2GC8 SERIES DAY-BRITE #2DPC SERIES LIGHTOLIER #SPS2 SERIES WILLIAMS #50G-S24 SERIES	SPRING LATCHES. POST PAINTED STEEL HOUSING. FLUSH WHITE ALUM. MITERED CORNERED DOOR FRAME. GASKETED AND/OR WITH METAL LIGHT Baffles. DOOR CAN BE LATCHED FROM EITHER SIDE OF HOUSING. 3-11/16" MINIMUM HOUSING DEPTH. ONE ELECTRONIC BALLASTS.	-
A6	2X4 RECESSED INDIRECT	120V	RECESSED LAY-IN GRID INVERTED TEE	3-F28 T8 4100K	ROUND CENTER PERFORATED SHIELD PAINTED WHITE. 51% LIGHT TRANSMISSION. WHITE ACRYLIC OVERLAY. UPPER REFLECTOR PAINTED WHITE.	COLUMBIA #STR24 SERIES LITHONIA #2AV SERIES METALUX #2RD SERIES DAY-BRITE #2AV SERIES LIGHTOLIER #WFS2 SERIES WILLIAMS #DVG-S24 SERIES	POST PAINTED STEEL HOUSING. PLASTIC END CAPS SUPPORT REFLECTOR. LIGHT BASKET ACTS AS A LIGHT SEAL. ONE ELECTRONIC BALLAST.	-
A7	2X4 RECESSED INDIRECT DUAL LEVEL SWITCHED	120V	RECESSED LAY-IN GRID INVERTED TEE	3-F28 T8 4100K	ROUND CENTER PERFORATED SHIELD PAINTED WHITE. 51% LIGHT TRANSMISSION. WHITE ACRYLIC OVERLAY. UPPER REFLECTOR PAINTED WHITE.	COLUMBIA #STR24 SERIES LITHONIA #2AV SERIES METALUX #2RD SERIES DAY-BRITE #2AV SERIES LIGHTOLIER #WFS2 SERIES WILLIAMS #DVG-S24 SERIES	POST PAINTED STEEL HOUSING. PLASTIC END CAPS SUPPORT REFLECTOR. LIGHT BASKET ACTS AS A LIGHT SEAL. TWO ELECTRONIC BALLAST FOR DUAL LEVEL SWITCHING (1) 1 LAMP BALLAST & (1) 2 LAMP BALLAST.	-
A7m	2X4 RECESSED INDIRECT DUAL LEVEL SWITCHED MASTER	120V	RECESSED LAY-IN GRID INVERTED TEE	3-F28 T8 4100K	ROUND CENTER PERFORATED SHIELD PAINTED WHITE. 51% LIGHT TRANSMISSION. WHITE ACRYLIC OVERLAY. UPPER REFLECTOR PAINTED WHITE.	COLUMBIA #STR24 SERIES LITHONIA #2AV SERIES METALUX #2RD SERIES DAY-BRITE #2AV SERIES LIGHTOLIER #WFS2 SERIES WILLIAMS #DVG-S24 SERIES	POST PAINTED STEEL HOUSING. PLASTIC END CAPS SUPPORT REFLECTOR. LIGHT BASKET ACTS AS A LIGHT SEAL. TWO ELECTRONIC BALLAST FOR DUAL LEVEL SWITCHING (1) 2 LAMP BALLAST & (1) 4 LAMP BALLAST.	-
A7s	2X4 RECESSED INDIRECT DUAL LEVEL SWITCHED SATELLITE	120V	RECESSED LAY-IN GRID INVERTED TEE	3-F28 T8 4100K	ROUND CENTER PERFORATED SHIELD PAINTED WHITE. 51% LIGHT TRANSMISSION. WHITE ACRYLIC OVERLAY. UPPER REFLECTOR PAINTED WHITE.	COLUMBIA #STR24 SERIES LITHONIA #2AV SERIES METALUX #2RD SERIES DAY-BRITE #2AV SERIES LIGHTOLIER #WFS2 SERIES WILLIAMS #DVG-S24 SERIES	POST PAINTED STEEL HOUSING. PLASTIC END CAPS SUPPORT REFLECTOR. LIGHT BASKET ACTS AS A LIGHT SEAL. NO BALLAST. TANDEM WIRED WITH FIXTURE TYPE "A7m" (DUAL LEVEL SWITCHING)	-
B	2X2 LENSED TROFFER	120V	RECESSED LAY-IN GRID INVERTED TEE	3-31U1 T8 4100K	0.125" MINIMUM ACRYLIC LENS FLAT SIDED PRISMS	COLUMBIA #ST822 SERIES LITHONIA #2SP8 SERIES METALUX #2GC8 SERIES DAY-BRITE #2DPC SERIES LIGHTOLIER #SPS2 SERIES WILLIAMS #50G-S22 SERIES	SPRING LATCHES. POST PAINTED STEEL HOUSING. FLUSH WHITE ALUM. MITERED CORNERED DOOR FRAME. GASKETED AND/OR WITH METAL LIGHT Baffles. DOOR CAN BE HINGED FROM EITHER SIDE OF HOUSING. 3-11/16" MINIMUM HOUSING DEPTH. ONE ELECTRONIC BALLAST.	-
B2	2X2 INDIRECT	120V	RECESSED LAY-IN GRID INVERTED TEE	3-F17W T8 4100K	ROUND CENTER PERFORATED SHIELD PAINTED WHITE. 51% LIGHT TRANSMISSION. WHITE ACRYLIC OVERLAY. UPPER REFLECTOR PAINTED WHITE.	COLUMBIA #STR22 SERIES LITHONIA #2AV SERIES METALUX #2RD SERIES DAY-BRITE #2AV SERIES LIGHTOLIER #WFS2 SERIES WILLIAMS #DVG-D22 SERIES	POST PAINTED STEEL HOUSING. PLASTIC END CAPS SUPPORT REFLECTOR. LIGHT BASKET ACTS AS A LIGHT SEAL. ONE ELECTRONIC BALLAST.	-
B3	2X2 INDIRECT DUAL LEVEL SWITCHED	120V	RECESSED LAY-IN GRID INVERTED TEE	3-F17W T8 4100K	ROUND CENTER PERFORATED SHIELD PAINTED WHITE. 51% LIGHT TRANSMISSION. WHITE ACRYLIC OVERLAY. UPPER REFLECTOR PAINTED WHITE.	COLUMBIA #STR22 SERIES LITHONIA #2AV SERIES METALUX #2RD SERIES DAY-BRITE #2AV SERIES LIGHTOLIER #WFS2 SERIES WILLIAMS #DVG-D22 SERIES LSI #2PFC SERIES	POST PAINTED STEEL HOUSING. PLASTIC END CAPS SUPPORT REFLECTOR. LIGHT BASKET ACTS AS A LIGHT SEAL. TWO ELECTRONIC BALLASTS.	-
C	-	120V	RECESSED LAY-IN GRID INVERTED TEE	-	-	-	-	-
D	6" DIAMETER DOWNLIGHT COMPACT FLUORESCENT	120V	RECESSED GYP-BOARD AND/OR LAY-IN GRID INVERTED TEE	1-F26DOTT 4100K HORIZ. MOUNT	HAZE REFLECTOR	PRESCOLITE #CFR6128EB SERIES GOTHAM #AF-126DOTT SERIES PORTFOLIO #C6126E-6251 SERIES OMEGA #S61H26 SERIES LIGHTOLIER #W50S SERIES TRIM #T26 SERIES HOUSING INFINITY #PH60-126Q SERIES	SELF-FLANGED TRIM. RELAMPING FROM BELOW. SOLID PLATE BAR HANGERS ACCESSIBLE. J-BOX FROM BELOW END OF LIFE SHUTDOWN BALLAST ONE ELECTRONIC BALLAST.	2
D1	6" DIAMETER DOWNLIGHT COMPACT FLUORESCENT TWO QUAD LAMPS	120V	RECESSED GYP-BOARD AND/OR LAY-IN GRID INVERTED TEE	2-F26DOTT 4100K HORIZ. MOUNT	HAZE REFLECTOR	PRESCOLITE #CFR6228EB SERIES GOTHAM #AF-226DOTT SERIES PORTFOLIO #C6226E-6151 SERIES OMEGA #S62H26 SERIES LIGHTOLIER #W50S SERIES TRIM #T26 SERIES HOUSING INFINITY #PH60-226Q SERIES	SELF-FLANGED TRIM. RELAMPING FROM BELOW. SOLID PLATE BAR HANGERS ACCESSIBLE. J-BOX FROM BELOW END OF LIFE SHUTDOWN BALLAST ONE ELECTRONIC BALLAST.	2
D2	6" DIAMETER DOWNLIGHT COMPACT FLUORESCENT	120V	RECESSED GYP-BOARD AND/OR LAY-IN GRID INVERTED TEE	1-F32TRT 4100K HORIZ. MOUNT	HAZE REFLECTOR	PRESCOLITE #CFR632HEB SERIES GOTHAM #AF-132TRT SERIES PORTFOLIO #C6142E-6151 SERIES OMEGA #S61H32 SERIES LIGHTOLIER #W50S SERIES TRIM #T32 SERIES HOUSING INFINITY #PH60-132T SERIES	SELF-FLANGED TRIM. RELAMPING FROM BELOW. SOLID PLATE BAR HANGERS ACCESSIBLE. J-BOX FROM BELOW END OF LIFE SHUTDOWN BALLAST ONE ELECTRONIC BALLAST.	2
D6	6" DIAMETER DIMMABLE LED DOWNLIGHT	120V	RECESSED GYP-BOARD AND/OR LAY-IN GRID INVERTED TEE	3500K LED 1500 LUMENS MIN	SEMI-SPECULAR CLEAR ALZAK	INDY #85D6 SERIES PORTFOLIO #D6H15 SERIES OMEGA #OM6LED SERIES OR PRIOR APPROVED EQUAL	SEAMLESS TAPERED WHITE DOOR WITH ALUMINUM HOUSING. PRE-WIRED J-BOX. TWO 27" HANGER BARS.	2

LUMINAIRE SCHEDULE								
FIXTURE LETTER	FIXTURE TYPE	VOLTAGE	MOUNTING	LAMPS	CONTROL MEDIA (LENS, LOUVER, ETC.)	MANUFACTURER'S SERIES NUMBERS	LUMINAIRE DESCRIPTION	NOTES
D11	7"-8" DIAMETER DOWNLIGHT METAL HALIDE	120V	RECESSED CANOPY	1-70W MH 4100K COATED MED BASE	HAZE REFLECTOR	PRESCOLITE #LF8MHV SERIES LITHONIA #LF8H SERIES PORTFOLIO #M7800T-730-48801 SERIES OMEGA #OM870 SERIES LIGHTOLIER #C7E170 SERIES TRIM #C770 SERIES HOUSING INFINITY #MH75-70ED17MED SERIES	SELF-FLANGED TRIM. RELAMPING FROM BELOW. SOLID PLATE BAR HANGERS ACCESSIBLE. J-BOX FROM BELOW. HEAT SINK LAMP SOCKET HOLDER. POST PAINTED.	2
D12	6" DIAMETER SHOWER DOWNLIGHT METAL U.L. WET LOCATION	120V	RECESSED GYP-BOARD	2-F26DOTT 4100K HORIZ. MOUNT	HAZE REFLECTOR. REGRESSED SPREAD ACRYLIC PRISMATIC LENS	PRESCOLITE #LF8FH SERIES LITHONIA #LF8H SERIES PORTFOLIO #C6226E-6181 SERIES OMEGA #SS8RD SERIES LIGHTOLIER #S096 SERIES TRIM #S728 SERIES HOUSING INFINITY #PHRL75-226Q SERIES	SELF-FLANGED TRIM. DIE CAST SOCKET. RELAMPING FROM BELOW. PLATE BAR HANGERS ACCESSIBLE. J-BOX FROM BELOW END OF LIFE SHUT DOWN BALLAST HEAT SINK LAMP SOCKET POST PAINTED.	2
D13	7"-8" DIAMETER DOWNLIGHT METAL HALIDE-WITH QUARTZ RESTRIKE	120V	RECESSED CANOPY	1-70W MH 4100K COATED MED BASE 1-QUARTZ RESTRIKE	HAZE REFLECTOR	PRESCOLITE #LF8MHV SERIES LITHONIA #LF8H SERIES PORTFOLIO #M7800T-730-48801 SERIES OMEGA #OM870 SERIES LIGHTOLIER #C7E170 SERIES TRIM #C770 SERIES HOUSING INFINITY #MH75-70ED17MED SERIES	SELF-FLANGED TRIM. RELAMPING FROM BELOW. SOLID BAR HANGERS ACCESSIBLE. J-BOX FROM BELOW. HEAT SINK LAMP SOCKET HOLDER. POST PAINTED.	2
D14	6" DIAMETER DOWNLIGHT COMPACT FLUORESCENT WITH GLASS TRIM RING	120V	RECESSED GYP-BOARD AND/OR LAY-IN GRID INVERTED TEE	1-F32TRT 4100K VERT. MOUNT	OPAL CYLINDER ENCASED IN CLEAR GLASS WITH SATIN ALUMINUM RING	LIGHTOLIER #D14 SERIES OR PRIOR APPROVED EQUAL	SELF-FLANGED TRIM. RELAMPING FROM BELOW. SOLID PLATE BAR HANGERS ACCESSIBLE. J-BOX FROM BELOW END OF LIFE SHUTDOWN BALLAST ONE ELECTRONIC BALLAST.	2
E1	EXIT SIGN SINGLE FACE LED DIE CAST HOUSING	120V	UNIVERSAL	LED	RED LETTERS STENCIL FACE	DUAL-LITE #SES9RWV SERIES LITHONIA #LE SERIES SURE-LITES #XJX SERIES MCPHILSEN #55L SERIES CHLORIDE #C402RA SERIES LIGHTALARMS #XJX SERIES	DIFFUSING OVERLAY. BLACK DIE CAST ALUMINUM HOUSING. BRUSHED ALUMINUM FACEPLATE. UNIVERSAL ARROWS, AC ONLY.	-
E2	EXIT SIGN DOUBLE FACE LED DIE CAST HOUSING	120V	UNIVERSAL	LED	RED LETTERS STENCIL FACE	DUAL-LITE #SES9RWV SERIES LITHONIA #LE SERIES SURE-LITES #XJX SERIES MCPHILSEN #55L SERIES CHLORIDE #C402RA SERIES LIGHTALARMS #XJX SERIES	DIFFUSING OVERLAY. BLACK DIE CAST ALUMINUM HOUSING. BRUSHED ALUMINUM FACEPLATE. UNIVERSAL ARROWS, AC ONLY.	-
E3	EXIT SIGN SINGLE FACE EDGE LIT LED DIE CAST HOUSING	120V	RECESSED	LED	RED LETTERS STENCIL FACE	DUAL-LITE #DCEV SERIES LITHONIA #PRECISE SERIES SURE-LITES #ELX SERIES MCPHILSEN #44L SERIES LIGHTOLIER #LE SERIES	CLEAR FACE WITH MIRROR UNIVERSAL ARROWS. BRUSHED ALUMINUM COVERPLATE. FULLY RECESSED HOUSING. AC ONLY.	-
E4	EXIT SIGN DOUBLE FACE EDGE LIT LED DIE CAST HOUSING	120V	RECESSED	LED	RED LETTERS STENCIL FACE	DUAL-LITE #DCEV SERIES LITHONIA #PRECISE SERIES SURE-LITES #ELX SERIES MCPHILSEN #44L SERIES LIGHTOLIER #LE SERIES	CLEAR FACE WITH MIRROR UNIVERSAL ARROWS. BRUSHED ALUMINUM COVERPLATE. FULLY RECESSED HOUSING. AC ONLY.	-
F	4" INDUSTRIAL	120V	SURFACE/CHAIN HUNG	2-F28 T8 4100K	APERATURED REFLECTOR WITH 20% UP LIGHT	COLUMBIA #K4L SERIES LITHONIA #AF SERIES METALUX #D0M SERIES DAY-BRITE #TF232 SERIES LIGHTOLIER #TF4 SERIES WILLIAMS #S24-232 SERIES	STEEL CHANNEL. ONE ELECTRONIC BALLAST.	-
F1	8" INDUSTRIAL	120V	SURFACE/CHAIN HUNG	4-F28 T8 4100K	APERATURED REFLECTOR WITH 20% UP LIGHT	COLUMBIA #K8L SERIES LITHONIA #AF SERIES METALUX #D0M SERIES DAY-BRITE #TF232 SERIES LIGHTOLIER #TF8 SERIES WILLIAMS #S28-232 SERIES	STEEL CHANNEL. ONE ELECTRONIC BALLAST.	-
J	4" STAIR LIGHT	120V	SURFACE	2-F28 T8 4100K	#12 ARCYLIC PRISMATIC DIFFUSER	COLUMBIA #W4 SERIES LITHONIA #WC SERIES METALUX #B0C SERIES DAY-BRITE #SWB SERIES NULITE #D0WM SERIES	POST PAINTED STEEL HOUSING. 5" HIGH X 4" DEEP WHITE INJECTED MOLDED END CAPS. HEAT SINK EMBOSMENTS IN BODY FOR BALLAST COOLING. FIXTURE PAINTED WHITE. 1 - 2 LAMP ELECTRONIC BALLAST.	-
L	1X4 LENSED TROFFER	120V	RECESSED LAY-IN GRID INVERTED TEE	2-F28 T8 4100K	0.125" MINIMUM ACRYLIC LENS FLAT SIDED PRISMS	COLUMBIA #STR14 SERIES LITHONIA #SP8 SERIES METALUX #GC8 SERIES DAY-BRITE #DPC SERIES LIGHTOLIER #SPS1 SERIES WILLIAMS #50G-S14 SERIES	SPRING LATCHES. POST PAINTED STEEL HOUSING. FLUSH WHITE ALUMINUM. MITERED CORNERED DOOR FRAME. GASKETED AND/OR WITH METAL LIGHT Baffles. DOOR CAN BE LATCHED FROM EITHER SIDE OF HOUSING. 3-11/16" MINIMUM HOUSING DEPTH. ONE ELECTRONIC BALLAST.	-
L1	1X4 LENSED TROFFER	120V	RECESSED LAY-IN GRID INVERTED TEE	3-F28 T8 4100K	0.125" MINIMUM ACRYLIC LENS FLAT SIDED PRISMS	COLUMBIA #STR14 SERIES LITHONIA #SP8 SERIES METALUX #GC8 SERIES DAY-BRITE #DPC SERIES LIGHTOLIER #SPS1 SERIES WILLIAMS #50G-S14 SERIES	SPRING LATCHES. POST PAINTED STEEL HOUSING. FLUSH WHITE ALUMINUM. MITERED CORNERED DOOR FRAME. GASKETED AND/OR WITH METAL LIGHT Baffles. DOOR CAN BE LATCHED FROM EITHER SIDE OF HOUSING. 3-11/16" MINIMUM HOUSING DEPTH. ONE ELECTRONIC BALLAST.	-
N	NIGHT LIGHT	120V	FLUSH IN WALL	WHITE LED LAMPS 1.6 WALL 230-280 MCD LUMINOUS INTENSITY	DIE-FORMED LOUVERED ALUMINUM FACE PLATE LOUVER WITH CLEAR ACRYLIC LENS WHITE FINISH WHITE REFLECTOR	HEALTHCARE LIGHTING INC. #HNL SERIES VISTA #RAGVSPLED SERIES BRONZILITE #WLA SERIES CHLORIDE #P2WCH SERIES	3" DEEP SHEET ALUMINUM HOUSING. PAINTED WHITE FRONT FACE GASKETED TO HOUSING. THERMALLY PROTECTED. ENCASED AND POTTED BALLAST. OVERALL FINISH DIMENSION 9-3/4" X 7-1/8". TAMPER PROOF SCREWS.	-
R	WEATHER PROOF WALL PACK LED	120V	WALL	2-BAR LED 3500 LUMENS MIN.	CLEAR TEMPERED GLASS. TYPE III DISTRIBUTION	MCGRAW-EDISON #ISC SERIES HUBBELL #RDI SERIES OR EQUAL BY LITHONIA, GARCO, EXCELINE, ACCULITE	INTEGRAL PHOTOCELL, TAMPER RESISTANT SCREWS.	-
S	PORCELAIN SOCKET	120V	CEILING MOUNT	1-28W SELF BALLAST MEDIUM BASE FLUORO	NONE	PASS & SEYMOUR #272 SERIES OR EQUAL	NONE	-
U2	2' UNDERCABINET LIGHT	120V	UNDERCABINET	1-F17 T8 4100K	LAY-IN PRISMATIC LENS	HEALTHCARE LIGHTING INC. #HJC SERIES LITHONIA #M2S SERIES FAIL-SAFE #M4S SERIES DAY-BRITE #BUC SERIES NULITE #B19 SERIES WILLIAMS #2SF SERIES LEGION #316 SERIES	SOLID FRONT INTEGRAL ROCKER SWITCH LAY-IN PRISMATIC LENS.	-
U3	3' UNDERCABINET LIGHT	120V	UNDERCABINET	1-F25 T8 4100K	LAY-IN PRISMATIC LENS	HEALTHCARE LIGHTING INC. #HJC SERIES LITHONIA #M2S SERIES FAIL-SAFE #M4S SERIES DAY-BRITE #BUC SERIES NULITE #B19 SERIES WILLIAMS #2SF SERIES LEGION #316 SERIES	SOLID FRONT INTEGRAL ROCKER SWITCH LAY-IN PRISMATIC LENS.	-
U4	4' UNDERCABINET LIGHT	120V	UNDERCABINET	1-F28 T8 4100K	LAY-IN PRISMATIC LENS	HEALTHCARE LIGHTING INC. #HJC SERIES LITHONIA #M2S SERIES FAIL-SAFE #M4S SERIES DAY-BRITE #BUC SERIES NULITE #B19 SERIES WILLIAMS #2SF SERIES LEGION #316 SERIES	SOLID FRONT INTEGRAL ROCKER SWITCH LAY-IN PRISMATIC LENS.	-

LUMINAIRE SCHEDULE								
FIXTURE LETTER	FIXTURE TYPE	VOLTAGE	MOUNTING	LAMPS	CONTROL MEDIA (LENS, LOUVER, ETC.)	MANUFACTURER'S SERIES NUMBERS	LUMINAIRE DESCRIPTION	NOTES
VA9	2X4 VANDAL RESISTANT TROFFER	120V	RECESSED GYP BOARD	3-F28 T8 4100K	.125" MINIMUM PRISMATIC ACRYLIC LENS ON FIXTURE SIDE WITH 250" CLEAR POLYCARBONATE ON THE ROOM SIDE.	FAIL-SAFE #2VRGC SERIES OR EQUAL BY KENALL	SPRING LATCHES. STEEL HOUSING. ONE ELECTRONIC BALLAST. FRAME AND LENS SECURED TO HOUSING USING TORX SCREWS.	-
VA10	2X4 VANDAL RESISTANT TROFFER	120V	RECESSED LAY-IN GRID INVERTED TEE	3-F28 T8 4100K	.125" MINIMUM PRISMATIC ACRYLIC LENS ON FIXTURE SIDE WITH 250" CLEAR POLYCARBONATE ON THE ROOM SIDE.	FAIL-SAFE #2VRGC SERIES OR EQUAL BY KENALL	SPRING LATCHES. STEEL HOUSING. TWO ELECTRONIC BALLASTS. FRAME AND LENS SECURED TO HOUSING USING TORX SCREWS.	-
VB3/ VB3F	2X2 VANDAL RESISTANT TROFFER (VB3F IS FLANGED)	120V	RECESSED LAY-IN GRID INVERTED TEE	3-31U1 T8 4100K	.125" MINIMUM PRISMATIC ACRYLIC LENS ON FIXTURE SIDE WITH 250" CLEAR POLYCARBONATE ON THE ROOM SIDE.	FAIL-SAFE #VRGC SERIES OR EQUAL BY KENALL	SPRING LATCHES. STEEL HOUSING. ONE ELECTRONIC BALLAST. FRAME AND LENS SECURED TO HOUSING USING TORX SCREWS.	-
VB4	2X2 VANDAL RESISTANT TROFFER	120V	RECESSED GYP BOARD	3-31U1 T8 4100K	.125" MINIMUM PRISMATIC ACRYLIC LENS ON FIXTURE SIDE WITH 250" CLEAR POLYCARBONATE ON THE ROOM SIDE.	FAIL-SAFE #VRGC SERIES OR EQUAL BY KENALL	SPRING LATCHES. STEEL HOUSING. TWO ELECTRONIC BALLASTS. FRAME AND LENS SECURED TO HOUSING USING TORX SCREWS.	-
VD13F	SQUARE FLUORESCENT VANDALPROOF FIXTURE	120V	RECESSED GYP BOARD	2-F26W QUAD 4100K	.125" MINIMUM PRISMATIC ACRYLIC LENS ON FIXTURE SIDE WITH 250" CLEAR POLYCARBONATE ON THE ROOM SIDE.	FAIL-SAFE #BCP SERIES KENALL #R00C SERIES OR PRIOR APPROVED EQUAL	MAXIMUM 16"X16" SQUARE VANDALPROOF RECESSED FIXTURE WITH INNER AND OUTER LENSES AS SPECIFIED. 16 GAUGE STEEL HOUSING. TAMPER RESISTANT SCREWS. WET LOCATION RATED.	-
VE1	VANDALPROOF EXIT SIGN SINGLE FACE LED DIE CAST HOUSING	120V	UNIVERSAL	LED	IMPACT-RESISTANT POLYCARBONATE LENS, STEEL STENCIL FACE, RED LETTERING	FAIL-SAFE #EXL SERIES OR EQUAL BY LITHONIA SURE-LITES MCPHILSEN CHLORIDE LIGHTALARMS DUAL-LITE	BLACK DIE-FORMED. 14 GAUGE STEEL HOUSING AND DOOR FRAME. TAMPER RESISTANT TORX SCREWS. UNIVERSAL ARROWS, AC ONLY.	-
VE2	VANDALPROOF EXIT SIGN DOUBLE FACE LED DIE CAST HOUSING	120V	UNIVERSAL	LED	IMPACT-RESISTANT POLYCARBONATE LENS, STEEL STENCIL FACE, RED LETTERING	FAIL-SAFE #EXL SERIES OR EQUAL BY LITHONIA SURE-LITES MCPHILSEN CHLORIDE LIGHTALARMS DUAL-LITE	BLACK DIE-FORMED. 14 GAUGE STEEL HOUSING AND DOOR FRAME. TAMPER RESISTANT TORX SCREWS. UNIVERSAL ARROWS, AC ONLY.	-
VE3	VANDALPROOF EXIT SIGN SINGLE FACE (WEATHER RESISTANT)	120V	UNIVERSAL	LED	IMPACT-RESISTANT POLYCARBONATE LENS, STEEL STENCIL FACE, RED LETTERING	FAIL-SAFE #XLW SERIES OR EQUAL BY LITHONIA SURE-LITES MCPHILSEN CHLORIDE LIGHTALARMS DUAL-LITE	INJECTION MOLDED UV STABILIZED POLYCARBONATE. TAMPER RESISTANT TORX SCREWS. UNIVERSAL ARROWS, AC ONLY, WET LOCATION.	-
VL1	1X4 VANDAL RESISTANT TROFFER	120V	RECESSED LAY-IN GRID INVERTED TEE	2-F28 T8 4100K	.125" MINIMUM PRISMATIC ACRYLIC LENS ON FIXTURE SIDE WITH 250" CLEAR POLYCARBONATE ON THE ROOM SIDE.	FAIL-SAFE #2VRGC SERIES OR EQUAL BY KENALL	SPRING LATCHES. STEEL HOUSING. ONE ELECTRONIC BALLAST. FRAME AND LENS SECURED TO HOUSING USING TORX SCREWS.	-
SL1	SITE LIGHT SINGLE HEAD	480V	POLE MOUNTED	1-250W MH	TYPE II DISTRIBUTION	STERNER #EXEC-RT25 SERIES	DARK BRONZE FINISH. NAFCO 6" SQUARE ALUMINUM LIGHT POLE WITH T-BASE (BY MILLERBERND) FOR SPAULDING SSA-30-60-C	3
SL2	SITE LIGHT TWO HEADS	480V	POLE MOUNTED	1-250W MH PER HEAD	TYPE III DISTRIBUTION	STERNER #EXEC-RT25 SERIES	DARK BRONZE FINISH. NAFCO 6" SQUARE ALUMINUM LIGHT POLE WITH T-BASE (BY MILLERBERND) FOR SPAULDING SSA-30-60-C	3
GENERAL NOTES:						KEY NOTES:		
A. SEE SPECIFICATION SECTION 16500 FOR ADDITIONAL LIGHT FIXTURE REQUIREMENTS.						1. SUBSTITUTE FIXTURE SUBJECT TO ARCHITECT APPROVAL.		
B. ANY CONFLICTS BETWEEN THE MANUFACTURER'S CATALOG NUMBER AND THE DESCRIPTIONS. SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER.						2. VERIFY CEILING TYPE PRIOR TO ORDERING FIXTURES.		
C. ALL FLUORESCENT FIXTURES WILL BE SUPPLIED WITH ELECTRONIC BALLASTS UNLESS SPECIFICALLY NOTED OTHERWISE.						3. POLES AND FIXTURES TO MATCH EXISTING SITE POLES.		
D. TO INSURE MATCHING COLOR AND APPEARANCE, ALL LAMPS SHALL BE FROM THE SAME MANUFACTURER. LAMPS SHALL HAVE COLOR TEMPERATURE #100K, WITH CRI OF 80 UNLESS OTHERWISE NOTED.								
E. LUMINAIRE WITH T5 OR SMALLER COMPACT FLUORESCENT LAMPS SHALL HAVE BALLAST/LAMPS WITH END OF LIFE POWER UNIT.								
F. UNLESS A SPECIFIC CATALOG NUMBER OR SERIES IS NAMED, THE MANUFACTURER'S NAMED AS ALTERNATES MUST SUBMIT CATALOG CUT SHEETS, IES FORMATTED PHOTOMETRIC REPORT TO THE ENGINEER FOR APPROVAL AT LEAST 10 DAYS PRIOR TO THE BID DATE. THE ENGINEER MAY REQUEST SAMPLE OF FIXTURE TO BE SUPPLIED.								
G. PROVIDE FACTORY INSTALLED DISCONNECTING MEANS FOR ALL DOUBLE-ENDED FLUORESCENT LUMINAIRES WHERE REQUIRED BY NEC 410.130(C).								
H. ALL FIXTURES ARE TO BE ENERGY STAR COMPLIANT.								

### OCCUPANCY SENSOR SCHEDULE

TAG	EQUIPMENT DESCRIPTION	MANUFACTURER	MOUNTING
IS	DUAL TECHNOLOGY LINE VOLTAGE SENSOR	WATTSTOPPER #DPT-365 SENSORSWITCH #CMR-PDT OR EQUAL BY LEVITON	CEILING
OS	WALLBOX OCCUPANCY LINE VOLTAGE SENSOR	WATTSTOPPER #DOW-100 SENSORSWITCH #WSD-PDT OR EQUAL BY LEVITON	WALL
OS	DUAL LEVEL SWITCHING WALLBOX OCCUPANCY LINE VOLTAGE SENSOR	WATTSTOPPER #DOW-200 SENSORSWITCH #WSD-PDT-2P OR EQUAL BY LEVITON	WALL

100% OWNER REVIEW  
NOT FOR CONSTRUCTION  
12/16/2011



**RSP Architects**  
1220 Marshall Street NE  
Minneapolis  
Minnesota 55413-1036  
612.677.7100  
612.677.7499 fax  
www.rsparch.com

NOTICE: The designs shown and described herein including all technical drawings, graphics, and/or text are the property of RSP Architects and shall not be copied, duplicated, or commercially exploited, in whole or in part, without express written permission of RSP Architects. These are available for limited review and evaluation by clients, consultants, contractors, government agencies, vendors and other personnel only in accordance with this Notice.

© Copyright RSP Architects 2011. All rights reserved.



#### CONSULTANTS:

**Structural**  
Van Sickle, Allen & Assoc.  
2955 Xenium Lane N  
Suite 10  
Plymouth, MN 55441  
**Civil**  
Eden Prairie, MN 55434

**Landscaping**  
Damon Farber Assoc.  
923 Nicollet Mall  
Minneapolis, MN 55402  
**Fire Protection**  
Gary Travinski Associates  
Engineering  
94 Boston Hill  
Larksville, PA 18513-3298



**MEP**  
Dunham Associates, Inc.  
50 South River Street, Suite 100  
Minneapolis, Minnesota 55402  
Tel: 612.446.7000  
Fax: 612.446.7001  
www.dunhaminc.com  
mechanical & electrical  
consulting and construction  
management services

I hereby certify that this plan, specification or report was prepared by me or under my direct supervision and that I am a duly licensed Engineer under the laws of the State of Minnesota.

Signature  
Registration No.  
Date 11/17/2011