



LONG TERM / INTERMEDIATE **PSYCHIATRIC UNIT**

St. Cloud VA Health Care System Main Campus, St. Cloud, Minnesota






DOCUMENT PACKAGE

DECEMBER 16, 2011

PACKAGE: **100% OWNER**

REVIEW ESTIMATE



Contractor is responsible for repairing and replacing any damaged lawn. The restoration will be performed by a landscape contractor that regularly does sodding as part of their business. All damaged lawn will be overcut by 6" or more to accomodate full width rolls of sod. Top soil to be tilled and graded to a smooth matching grade of undamaged lawn. Sod to be thoroughly saturated with water upon placement. The contractor is responsible for watering new sod until project acceptance by the COTR. Access to all buildings and parking areas must be maintained throughout the project. Contractors are to coordinate all work with the Contracting Officers Technical Representative. (C.O.T.R.) PROJECT LOCATION PLAN **SCALE: 1" = 300'-0"** | HHO..OHHHHHD NORTH TO 8TH ST WEST ONLY TO 8TH ST EAST & WEST


Contractor is responsible for the safeguarding of their tools and equipment. All tools and equipment are not to be left unattended and are to be secured at all times when the contractor is not present, or the construction site is not supervised by the contractor.


All demolished material becomes the property and the responsibility of the contractor with the exception of specified items designated either in the plans or verbally requested by the COTR to be retained by the VA. Offsite disposal of the demolished items is

Contractor must control demolition and construction dust from facility by erecting a dust barrier and ventilation with hepa filters. If venting to outside, the contractor will insure negative air pressure is maintained in encapsulated work area. When transporting

If scaffolding is used, it must be used in accordance with (OSHA) regulations and is to be enclosed for the first eight feet above ground at end of each working day, until dismantled. Ladders must be removed and locked up at the end of each working day to

Contractor is responsible for erecting a barrier around work site to prevent patients, staff and visitors from entering construction site. This fence may be a plastic snow fence. Coordinate construction materials and location of fence with COTR.







1220 Marshall Street NE Minneapolis Minnesota 55413-1036 612.677.7100 612.677.7499 fax www.rsparch.com

NOTICE: The designs shown and described herein including all technical drawings, graphics, and models thereof, are proprietary and cannot be copied, duplicated or commercially exploited, in whole or in part, without express written permission of RSP Architects. These are available for limited review and evaluation by clients, consultants, contractors, government agencies, vendors and office personnel only in accordance with this Notice. © Copyright RSP Architects 2011. All rights reserved.



Van Sickle, Allen & Assoc. 2955 Xenium Lane N Suite 10 Plymouth, MN 55441 10250 Valley View Road

Suite 113

Eden Prairie, MN 55344

GENERAL CONDITIONS

prevent unauthorized persons from having access.

Clean all debris from construction site to the satisfaction of the COTR.

Damon Farbar Assoc. Dunham Associates 50 South Sixth Street 923 Nicollet Mall Minneapolis, MN 55402 Suite 1100 Minneapolis, MN 55402 Fire Protection Gary Travinski Associates Engineering 94 Boston Hill

Larksville, PA 18651-3298

All dimensions on drawings are approximate; Drawings are not to be scaled. It is the responsibility of the contractor to verify all field conditions and physical dimensions that influence the construction area.

All VA property is to be safeguarded from damage. Any damaged VA property is to be restored to original condition prior to damage or replaced completely. This includes installation, labor, and procurement expenses.

It is recommended that contractors visit the proposed construction site prior to submitting their bids and they are encouraged to do so.

Contractor shall park only in the designated parking areas and are not to park on the lawn areas; the only exception is to load or unload supplies or equipment.

Contractor shall adhere strictly to State and Federal Occupational Safety and Health Administration (OSHA) Standards.

I hereby certify that this plan, specification or report was prepared by me or under my direct supervision and that I am a duly licensed Architect under the laws of the State of Minnesota. Signature Registration No.

APPROVED: SERVICE LINE DIRECTOR DATE: APPROVED: INFECTION CONTROL NURSE PPROVED: PROJECTS SECTION MANAGER DATE: APPROVED: CHIEF OF POLIC DATE: APPROVED: SAFETY MANAG PPROVED: DIRECTOR FMS

LONG TERM / INTERMEDIATE PSYCHIATRIC DATE: BUILDING No CHECKED BY DRAWN | Checker | MSC APPROVED: MEDICAL CENTER DIRECTOR 4801 VETERANS DRIVE, ST CLOUD MN

APPROVED: CHIEF OF STAFF

