

Room Finish Schedule							
Number	Name	Floor Finish	Base Finish	Wall Finish	Ceiling Finish	Ceiling Height	Comments
---	COURTYARD						
001	CRAWL SPACE						
100	LINK CONCOURSE	VCT-1, VCT-3, GRATE*	VB	PT-1, HR-2, CR-1, CG-1	ACT-1	10' - 0"	*WALK-OFF GRATE AS SHOWN ON PLAN, VCT-3 BORDER
101	CORRIDOR	VCT-1, VCT-3, GRATE*	VB	PT-1, HR-2, CR-1, CG-1, PT-3	ACT-1, GYP	9' - 0"	*WALK-OFF GRATE AS SHOWN ON PLAN, VCT-3 BORDER, PT-3 ACCENT WALL
102	FAMILY WAITING	CPT-1	CB	PT-1, PT-3*	ACT-1	9' - 0"	*PT-3 ACCENT WALL
103-1	CORRIDOR	VCT-1, VCT-3*	VB	PT-1	ACT-1, GYP	9' - 0"	*VCT-3 BORDER
103-2	CORRIDOR	VCT-1, VCT-3*	VB	PT-1	ACT-1, GYP	8' - 0"	*VCT-3 BORDER
104-1	CORRIDOR	VCT-1	VB	PT-1	ACT-1, GYP	8' - 0"	
104-2	RECEPTION SECURITY DESK	CPT-1	CB	PT-1, PT-3*	ACT-1, GYP	9' - 0"	*PT-3 AT BACK WALL
104-3	STAFF TLT	CT-1	CT-2	CT-2, PT-2*	GYP	8' - 0"	*CT FULL HEIGHT AT FIXTURE WALL AND SHOWER, 8 COURSES HIGH AT ALL OTHER WALLS WITH PT ABOVE, ALUMINUM TRIM AT OUTER CORNERS
104-4	LOCKERS	CPT-1	CB	PT-1	ACT-2	8' - 0"	
104-5	STAFF LOUNGE	VCT-1, VCT-2, VCT-3*	VB	PT-1, PT-2, PT-3**	ACT-2	9' - 0"	*VCT PATTERN, SEE PLAN **PT-2 AND PT-3 ACCENT WALLS
105	PUBLIC TLT	CT-1	CT-2	CT-2, PT-2*	ACT-2	9' - 0"	*CT TO CEILING AT FIXTURE WALLS, AND 8 COURSES HIGH ABOVE BASE AT ALL OTHER WALLS WITH PT ABOVE
106	PUBLIC TLT	CT-1	CT-2	CT-2, PT-2*	ACT-2	9' - 0"	*CT TO CEILING AT FIXTURE WALL, AND 8 COURSES HIGH ABOVE BASE AT ALL OTHER WALLS WITH PT ABOVE
107	TEL / DATA	SC	VB	PT-1	EXP	0"	
108	HEAD NURSE	CPT-1	CB	PT-1, PT-2*	ACT-2	8' - 0"	*PT-2 ACCENT WALL
109	CORRIDOR	VCT-1, VCT-3*	VB	PT-1, HR-2, CR-1, CG-1	ACT-1	8' - 0"	*VCT-3 BORDER
110	WARD CLERK	CPT-1	CB	PT-1, PT-2	ACT-2	9' - 0"	*PT-2 ACCENT WALL
111	OFFICE	CPT-1	CB	PT-1, PT-2*	ACT-2	9' - 0"	*PT-2 ACCENT WALL
112	CORRIDOR	VCT-1, VCT-3*	VB	PT-1, HR-2, CR-1	ACT-1	8' - 8"	*VCT-3 BORDER
113	CONSULT (FUTURE ELEVATOR)	CPT-1	CB	PT-1, PT-2*	ACT-2	9' - 0"	*PT-2 ACCENT WALL
114	SOCIAL WORK OFFICE (FUTURE ELEVATOR)	CPT-1	CB	PT-1, PT-2*	ACT-2	9' - 0"	*PT-2 ACCENT WALL
115	RECEIVING	SC	NONE	PT-1	EXP	0"	
116	INTAKE	VCT-2	VB	PT-1, PT-2	GYP	9' - 0"	*PT-2 ACCENT WALLS
117	SALLY PORT	VCT-1, VCT-3*	VB	PT-1, HR-1, CR-1, CG-1	GYP	9' - 0"	*VCT-3 BORDER
118	CORRIDOR	CPT-2	CB	PT-1, PT-2, PT-3 HR-1, CR-1, CG-1	ACT-3	9' - 0"	
119	EXAM RM	SF-2	VB	PT-1, PT-2*	GYP	9' - 0"	*PT-2 ACCENT WALLS
120-1	ANTE	SF-1	ICB	PT-2	GYP	9' - 0"	
120-2	PAT TLT	CT-1	CT-2	CT-2, PT-2*	GYP	9' - 0"	*CT FULL HEIGHT ON ALL WALLS, ALUMINUM TRIM AT OUTER CORNERS
120-3	SECLUSION	SF-1	ICB	PT-2	GYP	9' - 0"	
120-4	RESTRAINT ROOM	SF-1	ICB	PT-2	GYP	9' - 0"	
121-1	PAT RM #8	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
121-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
122-1	NURSE STATION	CPT-1	CB	PT-1, PT-3*	ACT-3, GYP	9' - 0"	*PT-3 ACCENT WALLS
122-2	NURSE WORK	CPT-1	CB	PT-2, PT-3*	ACT-3, GYP	9' - 0"	*PT-3 ALL SIDES OF DIVIDER WALL AND PT-2 ON BACK WALL
123-1	PAT RM #7	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
123-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
124-1	BARiatric PAT RM #6	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
124-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
125	QUIET LOUNGE	CPT-2	CB	PT-1, PT-2, PT-3*	ACT-3	9' - 0"	*PT-2 AND PT-3 ACCENT WALLS
126-1	PAT RM #5	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
126-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
127-1	EM EXIT	VCT-2, GRATE	VB	PT-1	GYP	9' - 0"	WALK-OFF GRATE AS SHOWN ON PLAN
127-2	CRAWL SPACE ACCESS	SC	VB	PT-1	GYP	0"	
128	STORAGE	VCT-2	VB	PT-1	GYP	9' - 0"	*WP WAINSCOT
129-1	SEMI PRIVATE #6	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
129-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
130-1	SEMI PRIVATE #5	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
130-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
131-1	SEMI PRIVATE #4	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
131-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
132-1	SEMI PRIVATE #3	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
132-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
133-1	DINING	SF-2	VB	PT-1, PT-2, PT-3	ACT-3, GYP	9' - 0"	SEE WALL FINISH PLAN
133-2	DAY ROOM	CPT-2	CB, VB*	PT-1	ACT-3, GYP	9' - 0"	*VB ON ALL SIDES HALF WALL
136-1	SEMI PRIVATE #2	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
136-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
137-1	PAT RM #4	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
137-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
138-1	PAT RM #3	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
138-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
139-1	PAT RM #2	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
139-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
140-1	PAT RM #1	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
140-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
141-1	SEMI PRIVATE #1	VCT-2	VB	PT-1, PT-2, PT-3*	GYP	9' - 0"	*PT-1 ON TOILET ROOM WALL, PT-3 ON DOOR WALL, PT-2 ALL OTHER WALLS.
141-2	PAT TLT	EPOXY	EPOXY	GLAZ	GYP	9' - 0"	
142	GROUP THERAPY	CPT-2	CB	PT-1, PT-2, PT-3*	ACT-3	9' - 0"	*PT-2 AND PT-3 ACCENT WALLS
143	CORRIDOR	CPT-2	CB	PT-1, PT-2, HR-1, CG-1, CR-1	ACT-3, GYP	9' - 0"	
145	MEDS	VCT-2	VB	PT-1	ACT-3	9' - 0"	
146	SALLY PORT	VCT-1, VCT-3*	VB	PT-1, HR-1, CR-1, CG-1	ACT-2	9' - 0"	*VCT3 BORDER
147	LAUNDRY / TUB	CT-1	CT-2	CT-2	GYP	9' - 0"	*CT FULL HEIGHT ALL WALLS, ALUMINUM TRIM AT OUTER CORNERS
150	CORRIDOR	VCT-1, VCT-3*	VB	PT-1, HR-2, CR-1	ACT-2	9' - 0"	*VCT-3 BORDER
151	CLEAN LINEN	VCT-1	VB	PT-1, WP-1*	ACT-2	9' - 0"	*WP WAINSCOT
152	SPD	VCT-1	VB	PT-1, WP-1*	ACT-2	9' - 0"	*WP WAINSCOT
153	ENVIRON STORAGE /HSKP	SC	VB	PT-1, WP-1*	ACT-2	9' - 0"	*WP WAINSCOT
154	SOILED HOLD	VCT-1	VB	PT-1, WP-1*	GYP	9' - 0"	*WP WAINSCOT
155-1	CORRIDOR	VCT-1, VCT-3*	VB	PT-1, HR-2, CR-1, CG-1	ACT-2	8' - 0"	*VCT-3 BORDER
155-2	CORRIDOR	VCT-1, VCT-3*	VB	PT-1, HR-2, CR-1, CG-1	ACT-2	8' - 0"	*VCT-3 BORDER
156	VESTIBULE	VCT-1, VCT-3, GRATE*	VB	PT-1, HR-2, CR-1, CG-1	ACT-2	8' - 0"	*WALK-OFF GRATE, VCT-3 BORDER
157	COPY	VCT-2	VB	PT-1	ACT-2	8' - 0"	
158	OFFICE	CPT-1	CB	PT-1, PT-2*	ACT-2	8' - 0"	*PT-2 ACCENT WALLS
159	MECHANICAL	SC	VB	PT-1	EXP	0"	
160	ELEC	SC	VB	PT-1	EXP	0"	

## FINISH LIST - BASIS OF DESIGN

### VINYL COMPOSITION TILE (VCT)

MANUFACTURER: ARMSTRONG MIGRATIONS BIO-BASED TILE (OR EQUAL)  
COLOR:

VCT-1:T3511 QUARTZ WHITE

VCT-2:T3510 NATURAL BEIGE

VCT-3:T3508 BARK BROWN

### CARPET (CPT, CB)

MANUFACTURER: TANDUS

PATTERN: ATOLL

COLOR: PAPER MULBERRY

NSF140: PLATINUM

INSTALLATION: DIRECT GLUE.

PRODUCT

CPT-1:

PRODUCT: ER3 MODULAR

SIZE: 24" TILE

CPT-2:

PRODUCT: POWERBOND ER3 CUSHION

SIZE: 6' ROLL

CARPET BASE (CB)

HEIGHT: 4 INCHES

PRODUCT: BROADLOOM CARPET BASE MATCHING CPT-1 AND 2,

FINISHING: BOUND TOP TO MATCH BASE CARPET COLOR. PROVIDE

COLOR SELECTIONS TO DESIGNER FOR FINAL APPROVAL

### SHEET FLOORING (SF)

SF-1

MANUFACTURER: CAPRI CORK

PRODUCT: RUBBER CORK

COLOR: SAND #AD1001

WIDTH: 4' ROLLS

THICKNESS 6MM

FINISH: LOW VOC SEALANT

SF -2

MANUFACTURER: NORA

PRODUCT: ENVIRONCARE

COLOR: 2946 MORNING DEW

WIDTH: 48 INCHES

THICKNESS: 2MM

### VINYL BASE (VB)

MANUFACTURER: VPI

PRODUCT: 4" COVED BASE

COLOR: 14 TAUPE

INSTALLATION: CUT INTO 1-FOOT STRIPS AFTER STANDARD INSTALLATION

### CERAMIC TILE

MANUFACTURER: DAL TILE

CT-1:

PRODUCT: KEYSTONES

COLOR: MOTTLED MEDIUM BROWN

SIZE: 2 x 2 MOSAIC

GROUT: MAPEI 39 IVORY

LOCATION: FLOOR TILE

CT-2:

PRODUCT: MATTE

COLOR: ALMOND X735

SIZE: 4 1/4 x 4 1/4

GROUT: MAPEI 14 BISCUIT

LOCATION: WALL TILE

ALL TRIM TO MATCH ADJACENT TILE

COVE BASE TO MATCH CT-2

OUTSIDE CORNER TRIM:

MANUFACTURER: SCHLUTER SYSTEMS

PRODUCT: RONDEC R060AT

SIZE: 1/4" - 6MM

MATERIAL: ANODIZED ALUMINUM

FINISH: NICKEL

### EPOXY FLOORING

MANUFACTURER: STONHARD

PRODUCT: STONSHIELD BROADCAST

COLOR: ACORN

TEXTURE: STANDARD

### PAINT

PT-1:

MANUFACTURER: BENJAMIN MOORE

PRODUCT: ECO SPEC

COLOR: GRAY MIST 962

FINISH: EGGSHELL

LOCATION: GENERAL PAINT

PT-2:

MANUFACTURER: BENJAMIN MOORE

PRODUCT: ECO SPEC

COLOR: SHAKER BEIGE HC-45

FINISH:EGGSHELL FINISH

LOCATION: ACCENT WALLS

PT-2B:

MANUFACTURER: BENJAMIN MOORE

PRODUCT: ECO SPEC

COLOR: SHAKER BEIGE HC-45

FINISH: SEMI-GLOSS

LOCATION: HOLLOW METAL FRAMES

PT-3:

MANUFACTURER: BENJAMIN MOORE

PRODUCT: ECO SPEC

COLOR: SMOKEY MOUNTAIN AC-18

FINISH: EGGSHELL

LOCATION: ACCENT WALLS

PT-4:

MANUFACTURER: BENJAMIN MOORE

PRODUCT: ECO SPEC

COLOR: GRAY MIST 962

FINISH: FLAT

LOCATION: CEILINGS

### GLAZED BLOCK

COLOR FROM MANUFACTURER'S STANDARD TO MATCH PT-1

### ACOUSTICAL CEILING TILE

MANUFACTURER: ARMSTRONG

PRODUCTS:

ACT-1:

SIZE: 24 x 24

LOCATION: PUBLIC CORRIDORS

ACT-2:

SIZE: 24 x 48

LOCATION: OFFICE SPACES

ACT-3:

SIZE: 24x24

ACCESSORIES: HOLD-DOWN CLIPS

LOCATION: WITHIN PATIENT PUBLIC AREAS

### PLASTIC LAMINATE

PL-1:

PRODUCT: PIONITE

COLOR: ANIGRE WX041 SUEDE

### SOLID SURFACE

SS-1:

MANUFACTURER: CORIAN

COLOR: BEIGE FIELDSTONE

LOCATION: COUNTERTOPS AND WINDOW SILLS

SS-2:

MANUFACTURER: CORIAN

COLOR: BISQUE

LOCATION: TRANSITIONS, UNDERMOUNT SINKS

### WALL PROTECTION

WALL PROTECTION SHEET

WP-1

MANUFACTURER: C/S ACROVYN

COLOR: EGGSHELL #100

SIZE: 4'H SHEET

THICKNESS: 0.060"

WP-2

(NOT USED)