

DOOR SCHEDULE

DOOR NUMBER	ROOM NAME	NEW/EXIST. TO REMAIN	DOOR			FRAME		HARDWARE SET	COMMENTS
			WIDTH	HEIGHT	MATERIAL	MATERIAL			
602-1	OFFICE (SUPERVISOR)	ETR, SEE COMMENTS	3' - 8"	7' - 0"	WD.	H.M.	HW-6D	SEE DOOR NOTES MKD. ①, ②, ③ / PROVIDE AND INSTALL NEW HARDWARE	
603-1	GENERAL STORAGE	ETR, SEE COMMENTS	3' - 8"	7' - 0"	WD.	H.M.	HW-7D	SEE DOOR NOTES MKD. ①, ②, ③ / PROVIDE AND INSTALL NEW HARDWARE	
604-1	SHOWER ROOM	ETR, SEE COMMENTS	3' - 10"	7' - 0"	H.M.	H.M.	-	SEE DOOR NOTES MKD. ①, ④, ⑤	
605-1	LAUNDRY ROOM	ETR, SEE COMMENTS	3' - 10"	7' - 0"	ACROVYN	H.M.	-	SEE DOOR NOTES MKD. ①, ⑤	
605A-1	TOILET	ETR, SEE COMMENTS	3' - 0"	7' - 0"	WD.	H.M.	-	SEE DOOR NOTES MKD. ①, ②	
606-1	BEDROOM, ONE-BED	ETR	3' - 10"	7' - 0"	ACROVYN	H.M.	-	TO REMAIN AS IS.	
606A-1	TOILET	ETR, SEE COMMENTS	3' - 0"	7' - 0"	WD.	H.M.	-	SEE DOOR NOTES MKD. ①, ②	
607-1	BEDROOM, ONE-BED	ETR	3' - 10"	7' - 0"	ACROVYN	H.M.	-	TO REMAIN AS IS.	
607A-1	TOILET	ETR, SEE COMMENTS	3' - 0"	7' - 0"	WD.	H.M.		SEE DOOR NOTES MKD. ①, ②, ③	
608-1	RESIDENT EDUCATION	ETR, SEE COMMENTS	3' - 10"	7' - 0"	ACROVYN	H.M.	HW-4D	SEE DOOR NOTE MKD. ①, ⑤ / PROVIDE & INSTALL NEW HARDWARE	
608A-1	TOILET	ETR, SEE COMMENTS	3' - 0"	7' - 0"	WD.	H.M.	-	SEE DOOR NOTES MKD. ①, ②	
609-1	BEDROOM, TWO-BED	ETR	3' - 10"	7' - 0"	ACROVYN	H.M.	-	TO REMAIN AS IS.	
609A-1	TOILET	ETR, SEE COMMENTS	3' - 0"	7' - 0"	WD.	H.M.	-	SEE DOOR NOTES MKD. ①, ②	
610-1	BEDROOM, TWO-BED	ETR	3' - 10"	7' - 0"	ACROVYN	H.M.	-	TO REMAIN AS IS.	
610A-1	TOILET	ETR, SEE COMMENTS	3' - 0"	7' - 0"	WD.	H.M.	-	SEE DOOR NOTES MKD. ①, ②	
611-1	BEDROOM, TWO-BED	ETR	3' - 10"	7' - 0"	ACROVYN	H.M.	-	TO REMAIN AS IS.	
611A-1	TOILET	ETR, SEE COMMENTS	3' - 0"	7' - 0"	WD.	H.M.	-	SEE DOOR NOTES MKD. ①, ②	
612-1	KITCHENETTE / MULTIPURPOSE ROOM	ETR, SEE COMMENTS	3' - 10"	7' - 0"	ACROVYN	H.M.	HW-5D	SEE DOOR NOTE MKD. ①, ⑤ / PROVIDE & INSTALL NEW HARDWARE	
613-1	OFFICE (SHARED STAFF)	ETR, SEE COMMENTS	3' - 6"	7' - 0"	WD.	H.M.	HW-8D	SEE DOOR NOTES MKD. ①, ②, ⑤, ⑥ / PROVIDE AND INSTALL NEW HARDWARE	
649-1	CORRIDOR	ETR, SEE COMMENTS	3' - 6" EA. (PAIR)	8' - 0"	WD.	H.M.	-	SEE DOOR NOTES MKD. ①, ②, ⑥	
ES-16	STAIR 'A'	ETR, SEE COMMENTS	4' - 0"	7' - 0"	H.M.	H.M.	-	SEE DOOR NOTES MKD. ①, ④, ⑥	

LEGEND / DOOR NOTES, REFERRED FROM DOOR SCHEDULE:

- ① PAINT EXISTING HOLLOW METAL DOOR FRAME TO MATCH COLOR OF FRAMES ALREADY PAINTED (DOOR FRAMES ALREADY PAINTED CORRESPOND TO THE FOLLOWING DOORS: 606-1, 607-1, 609-1, 610-1 AND 611-1).
- ② CONTRACTOR TO APPLY WOOD FILLER TO DAMAGED WOOD DOORS, AS NEEDED, TO MATCH EXIST DOOR COLOR AND FINISH, STAIN AROUND WORKED AREAS AND OTHER DISCOLORED AREAS, TO MATCH EXISTING COLOR AND FINISH.
- ③ REMOVE EXISTING PAINTED HINGES AND INSTALL NEW STAINLESS STEEL HINGES OF THE SAME SIZE AND THICKNESS.
- ④ PAINT EXISTING HOLLOW METAL DOOR TO MATCH COLOR OF FRAMES ALREADY PAINTED.
- ⑤ CONTRACTOR TO REMOVE PLASTIC JAMB COVERS FROM EXISTING HOLLOW METAL FRAMES. THE CONTRACTOR SHALL REMOVE ALL GLUE RESIDUE THAT REMAINS ADHERED TO THE FRAME, AND ALSO PREP. THE FRAME FOR PAINT, SO THAT IT PRESENTS A SMOOTH SURFACE.
- ⑥ PAINT METAL FRAME AROUND VISION PANEL, TO MATCH COLOR AND FINISH OF DOOR FRAMES ALREADY PAINTED.