

HARDWARE SCHEDULE:

- HW-4D
 - * CLASSROOM LOCK "BEST" SPSL-ML-R-16F US32D
 - * MORTISE CYLINDER "BEST" 1E-74 (Blank Core)
 - * DOOR CLOSER, EQUAL OR SIMILAR TO "LCN" 4040XP AL.
 - * WRAPAROUND S.S. US32D COVER PLATE, AROUND LOCKSET, SIZE TO MATCH THE ONE INSTALLED IN THE LAUNDRY ROOM DOOR.
 - * ARMOR PLATE, EQUAL OR SIMILAR TO "BURNS" AP50 US32D, 24" HIGH.
 - * MOP PLATE, EQUAL OR SIMILAR TO "BURNS" KP50 US32D, 8" HIGH.
 - * SET OF SEALS S888L.
 - * DOOR STOP, DOME TYPE EQUAL OR SIMILAR TO "ASSA ABLOY" ROCKWOOD 441CU.
 - * 3 SILENCERS.
 - * MAINTAIN EXISTING HINGES ALREADY INSTALLED.
 - * REMOVE EXIST. FLOOR MOUNTED DOOR STOP.

- HW-5D
 - * CLASSROOM LOCK "BEST" SPSL-ML-R-16F US32D
 - * MORTISE CYLINDER "BEST" 1E-74 (Blank Core)
 - * WRAPAROUND S.S. US32D COVER PLATE, AROUND LOCKSET, SIZE TO MATCH THE ONE INSTALLED IN THE LAUNDRY ROOM DOOR.
 - * ARMOR PLATE, EQUAL OR SIMILAR TO "BURNS" AP50 US32D, 24" HIGH.
 - * MOP PLATE, EQUAL OR SIMILAR TO "BURNS" KP50 US32D, 8" HIGH.
 - * SET OF SEALS S888L.
 - * 3 SILENCERS.
 - * MAINTAIN EXISTING HINGES / DOOR MOUNTED STOP

- HW-6D
 - * CLASSROOM LOCK "BEST" SPSL-ML-R-16F US32D.
 - * MORTISE CYLINDER "BEST" 1E-74 (Blank Core).
 - * WRAPAROUND S.S. US32D COVER PLATE, AROUND LOCKSET, SIZE TO MATCH THE ONE INSTALLED IN THE LAUNDRY ROOM DOOR.
 - * DOOR STOP, DOME TYPE EQUAL OR SIMILAR TO "ASSA ABLOY" ROCKWOOD 441CU.
 - * MAINTAIN EXISTING HINGES / DOOR CLOSER / KICK PLATE / MOP PLATE / ELECTRIC STRIKE
 - * REMOVE EXISTING LOCK AND PLASTIC PLATE ON THE SIDE OF THE LOCK.
 - * REMOVE EXISTING WALL STOP / PATCH AND PAINT ANY DAMAGE TO EXIST. G.B. WALL THAT RESULTS FROM THE REMOVAL OF THE WALL STOP.

- HW-7D
 - * CLASSROOM LOCK "BEST" SPSL-ML-R-16F US32D.
 - * MORTISE CYLINDER "BEST" 1E-74 (Blank Core).
 - * WRAPAROUND S.S. US32D COVER PLATE, AROUND LOCKSET, SIZE TO MATCH THE ONE INSTALLED IN THE LAUNDRY ROOM DOOR.
 - * DOOR STOP, DOME TYPE EQUAL OR SIMILAR TO "ASSA ABLOY" ROCKWOOD 441CU.
 - * MAINTAIN EXISTING HINGES / DOOR CLOSER / KICK PLATE / MOP PLATE / ELECTRIC STRIKE.
 - * REMOVE EXISTING LOCK AND PLASTIC PLATE ON THE SIDE OF THE LOCK.
 - * REMOVE EXISTING FLOOR MOUNTED DOOR STOP.

- HW-8D
 - * CLASSROOM LOCK "BEST" SPSL-ML-R-16F US32D.
 - * MORTISE CYLINDER "BEST" 1E-74 (Blank Core).
 - * WRAPAROUND S.S. US32D COVER PLATE, AROUND LOCKSET, SIZE TO MATCH THE ONE INSTALLED IN THE LAUNDRY ROOM DOOR.
 - * MAINTAIN EXISTING HINGES / DOOR CLOSER / KICK PLATE / MOP PLATE / ELECTRIC STRIKE / DOOR STOP.