

DESCRIPTION	U/I	QTY	UNIT PRICE	TOTAL PRICE
Project Title: REPLACE BOILERS (Project 573-14-600) Location: Malcom Randall VA Medical Center, Gainesville, FL.				
ITEM NO.1 (BASE ITEM): Work includes all Architectural and Engineering associated installation components as shown on the contract documents, with all necessary removal of existing systems and installation of new systems. Contract performance period of 730 calendar days upon issuance of a Notice to Proceed (NTP).	JB	1	\$_____	\$_____
ITEM NO. 2 (DEDUCT ALTERNATE NO. 1): Includes all work in Item NO. 1, except DEDUCT AND REPLACE as follows: 1) DEDUCT the exterior face brick as shown on the documents and, 2) REPLACE with exterior synthetic stucco system on metal studs where the brick was previously shown. Contract performance period of 730 calendar days upon issuance of a NTP.	JB	1	\$_____	\$_____

ITEM NO. 3 (DEDUCT ALTERNATE NO. 2): Includes all work in Item NO.1 except DEDUCT:

The specific portions of the redundant electrical feed to the new boiler plant, specifically the following items:

- 1) ATS-BPB and associated new normal breaker in US-9 and new emergency breaker in EMSGR-ACA,
- 2) Normal and emergency conductors and raceways on line side of ATS-BPB,
- 3) Conductors on load side of ATS-BPB extending to BPB,
- 4) Exposed raceway extending from ATS-BPB to boiler plant (underground raceway extending from southwest terminus of tunnel to BPB shall remain regardless of alternate item),
- 5) BPB main breaker and associated power meter (switchboard section and main breaker provisions to remain regardless of alternate item).

Contract performance period of 730 calendar days upon issuance of a NTP.

JB

1

\$ _____

\$ _____