

**SECTION 02 65 00
UNDERGROUND STORAGE TANK REMOVAL**

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Removing and disposal of underground storage tank (UST) liquid contents.
2. Removing, cleaning, and disposing UST.
3. Testing and removing contaminated soils.
4. Backfilling and restoring excavation areas.

1.2 RELATED REQUIREMENTS

- A. Laboratory Services: Section 01 45 29, TESTING LABORATORY SERVICES.
- B. Demolition Exposing UST: Section 02 41 00, DEMOLITION.
- C. UST Removal Excavation: Section 31 20 00, EARTHWORK.
- D. Excavation Backfilling: Section 31 20 00, EARTHWORK.

E. Excavation Surface Restoration: // Section 32 05 23, CEMENT AND CONCRETE FOR EXTERIOR IMPROVEMENTS // Section 32 12 16, ASPHALT PAVING // Section 32 90 00, PLANTING //.

1.3 PRICE AND PAYMENT PROCEDURES

- A. Differing Site Conditions: Extent of excavation and restoration for UST removal indicated on drawings and extent of additional soils sampling and testing specified in this section are estimated. Variations less than 5 percent change are not cause for contract price and time adjustments. Additional work will be paid by unit prices as directed by Contracting Officer's Representative.

1.4 APPLICABLE PUBLICATIONS

- A. Comply with references to extent specified in this section.
- B. American Petroleum Institute (API):
 1. 1604-96(R2010) - Closure of Underground Petroleum Storage Tanks.
 2. 2217A-09 - Safe Work in Inert Confined Spaces in the Petroleum and Petrochemical Industries.
 3. 2015-14 - Safe Entry and Cleaning of Petroleum Storage Tanks.
- C. Code of Federal Regulations (CFR):
 1. 40 CFR Part 280 - Underground Storage Tanks; Technical Requirements.
 2. 49 CFR Part 178 - Specifications for Packagings.

- D. United States Environmental Protection Agency (EPA):
 - 1. SW-846 - Evaluating Solid Waste: Physical/Chemical Methods.
- E. NYS DEC Regulations 6NYCRR 612-614
- F. NYS DEC Regulations 6NYCRR 613.9
- G. NYS DEC Technical Guidance for Site Investigation and Remediation DER-10

1.5 PRE-REMOVAL MEETINGS

- A. Conduct pre-removal meeting at project site minimum 30 days before beginning Work of this section.
 - 1. Required Participants:
 - a. Contracting Officer's Representative.
 - b. VA Syracuse Environmental Protection Specialist
 - c. Inspection and Testing Agency.
 - d. General Contractor.
 - e. UST removal contractor.
 - 2. Meeting Agenda: Distribute agenda to participants minimum 3 days before meeting.
 - a. Removal schedule.
 - b. Removal sequence.
 - c. Preparatory work.
 - d. Contaminated material containment and disposal.
 - e. Removal.
 - f. Inspecting and testing.
 - g. Other items affecting successful completion.
 - 3. Document and distribute meeting minutes to participants to record decisions affecting installation.

1.6 SUBMITTALS

- A. Submittal Procedures: Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Notice of intent to close UST.
- C. Test Reports: Submit testing laboratory reports.
 - 1. UST liquid contents analysis.
 - 2. UST interior environment analysis.
 - 3. Soil sample analysis.
- D. Qualifications: Substantiate qualifications comply with specifications.
 - 1. UST removal contractor.
 - 2. Testing laboratory.

- 3. Liquid disposal facility.
- 4. UST disposal facility.
- 5. Soils disposal facility.
- E. UST removal plan.
- F. Record Documents:
 - 1. Six copies of Final Closure Report.
 - 2. Record Drawings in electronic CAD file format showing:
 - a. Soil sample locations.
 - b. Detailed plan view.
 - c. Piping removal diagrams.
 - d. Control removal diagrams.
 - e. Component diagrams including tank removal procedure.
 - f. Detailed sequence of procedure.
 - 3. Photographs of work in progress showing UST removal plan compliance.
 - 4. Chain-of-custody documentation.
 - 5. Disposal facility receipts and disposition reports.

1.7 QUALITY ASSURANCE

- A. UST Removal Contactor: Experienced contractor, registered or licensed by applicable state agency regulating UST removal.
- B. Testing Laboratory: State certified independent testing laboratory experienced in hazardous waste liquid and soil testing.
- C. Liquid Disposal Facility: State certified disposal facility qualified to receive and dispose UST liquid contents.
- D. UST Disposal Facility: State certified disposal facility qualified to receive and dispose UST.
- E. Soils Disposal Facility: State certified disposal facility qualified to receive and dispose contaminated soils.
- F. UST Removal Plan: Describe detailed procedures for:
 - 1. Removing and disposing UST liquid content.
 - 2. Removing, ventilating, cleaning and disposing UST.
 - 3. Soil sampling and testing.
 - 4. Removing and disposing contaminated soils.
- G. UST Final Closure Report: Assemble work progress documentation showing removal plan compliance, including:
 - 1. Sample test records.
 - 2. Local Fire Marshal requirement.
 - 3. State Agency requirements.
 - 4. Hazardous material plan for local VA management.

1.8 FIELD CONDITIONS

- A. Do not close or obstruct streets, sidewalks or drives without Contracting Officer's Representative's approval.
 - 1. Submit closure request minimum 45 days before starting work.

1.9 WARRANTY

- A. Construction Warranty: FAR clause 52.246-21, "Warranty of Construction."

PART 2 - PRODUCTS**2.1 ACCESSORIES**

- A. Waste Collection Drums: 49 CFR Part 178; Type 1A2, steel, removable head, 200 L (55 gal.) capacity, capable of containing waste without loss.

PART 3 - EXECUTION**3.1 PREPARATION**

- A. Coordinate demolition specified in Section 02 41 00, DEMOLITION required to access UST site.

3.2 UST SEQUENCE

- A. Notify applicable State Agency minimum 30 days before UST closure. Forms to be submitted per Section 1.6 and approved by Syracuse VA facility environmental specialist prior to notification.
- B. Determine if contamination from UST is present.
- C. When contamination exists, notify Syracuse VA facility environmental specialist and cooperate to record site with applicable State Agency and EPA.
- D. Remove and polish UST liquid contents and pump into remaining UST, remove UST and associated facilities.
- E. Remove contaminated soil.
- F. Backfill excavated area.
- G. Restore excavation surfaces.

3.3 UST CLOSURE

- A. Conform to API 1604, 40 CFR Part 280, 29 CFR Part 1910, and 29 CFR Part 1926.

3.4 UST LIQUID CONTENTS REMOVAL

- A. Contractor shall provide the service of fuel polishing the in-ground diesel fuel. This will include additive for the fuel polishing, waste disposal and waste pick up. Fuel cleaning shall be conducted IAW NFPA 110 and appropriate ASTM standards, include centrifugal field testing for organic and inorganic contamination and filtration to remove of all significant contamination. Provide written report to VA to report contamination levels found and outlining work accomplished.
- B. Collect, test, and analyze UST liquid content samples.
 - 1. Identify individual constituents and concentrations.
 - 2. Identify lower explosive limits for constituents in gaseous form.
 - 3. Identify disposal facilities qualified to receive and process UST waste contents.
- C. Remove UST liquid contents before removing UST.
 - 1. Record liquid volume removed from UST.
- D. Polished fuel to be pumped into existing tank #5 (20,000 gallon tank).

3.5 UST REMOVAL

- A. Excavate overburden and soils immediately surrounding UST as specified in Section 31 20 00, EARTHWORK.
 - 1. Contain excavated materials to prevent loss and mixing with other materials until completion of initial soils testing.
- B. Remove UST from excavation.
- C. Place UST on ground adjacent to removal location.
- D. Secure UST before cleaning.

3.6 UST CLEANING

- A. Measure combustible gas and oxygen concentrations within UST.
- B. Ventilate UST interior to reduce combustible gas concentrations to maximum 10 percent of lower explosive limit and to provide 19.5 to 23.5 percent oxygen concentration.
 - 1. Test UST interior atmosphere confirming gas concentrations.
 - 2. Complete required ventilation before cleaning.
- C. Cut ports in UST wall facilitating cleaning access. Comply with API Standard 2217A and API Standard 2015 for UST entry.
- D. Clean surface contaminates from UST and access port interior wall surfaces.
 - 1. Contain removed materials without producing further contamination.
 - 2. Collect removed materials in waste collection drums. Seal drums to prevent material loss.

- E. Request UST inspection by local State Agency certifying completed UST cleaning if requested.
- F. Dismantle UST as required for transport to disposal facility.
- G. Deliver UST, removed access ports, and waste collection drums to disposal facility.
 - 1. Obtain signed receipt including date, time, quantity, and description of materials received.
 - 2. Obtain final report of materials disposition after disposal completion.

3.7 SOIL TESTING

- A. Collect five initial soil samples from UST excavation area after tank removal.
- B. Take one sample from both UST sidewalls, one sample from both UST endwalls, and one sample from UST base.
 - 1. Containerize samples to prevent sample loss and preserve sample condition until tested.
 - 2. Test and analyze samples according to EPA SW-846 for total petroleum hydrocarbon (TPH) concentrations.
- C. When soil testing reveals evidence of hydrocarbons at concentrations greater than permitted by applicable NYS DEC for uncontaminated soil used as fill material, collect six additional soil samples 6 m (20 feet) from UST walls.
 - 1. Take two samples from both UST sidewalls and one sample from both UST endwalls.
 - 2. Test and analyze samples as specified for initial samples.
 - 3. Notify Contracting Officer's Representative when additional samples are contaminated.
 - 4. The base price for volume between the final tank volume of material for the enclosure and the enclosure shall not to exceed 76 cubic meters (100 cubic yards) of soil removed. Any work beyond 76 cubic meters (100 cubic yards) and more than 6 test locations shall be considered extra and shall be based on unit pricing.
- D. Perform additional soil sampling and testing around UST as directed by Contracting Officer's Representative until contamination concentration is less than permitted by applicable NYS DEC for uncontaminated soil used as fill material.

3.8 CONTAMINATED SOIL REMOVAL

- A. Excavate contaminated materials as specified in Section 31 20 00, EARTHWORK.
- B. Remove contaminated soil from site according to applicable NYS DEC requirements.
- C. Deliver contaminated soils to disposal facility.
 - 1. Obtain signed receipt including date, time, quantity, and description of materials received.
 - 2. Obtain final report of materials disposition after disposal completion.

3.9 UST EXCAVATION BACKFILL AND RESTORATION

- A. Backfill excavation with fill materials and compact as specified in Section 31 20 00, EARTHWORK.
- B. Restore pavements, sidewalks, and curbs matching adjacent materials as specified in // Section 32 05 23, CEMENT AND CONCRETE FOR EXTERIOR IMPROVEMENTS // Section 32 12 16, ASPHALT PAVING //.
- C. deleted.

3.10 FIELD QUALITY CONTROL

- A. Field Tests: Performed by testing laboratory specified in Section 01 45 29, TESTING LABORATORY SERVICES.
- B. Perform sampling and testing for the following:
 - 1. UST liquid contents.
 - 2. UST interior environment.
 - 3. Soils contamination.
- C. Record chain-of-custody for samples until disposal.

3.11 PROTECTION

- A. Protect restored areas from traffic and construction operations.
- B. Repair damage.

- - - E N D - - -