# LUMINAIRE SCHEDULE

| LUMINAIRE TYPE | DESCRIPTION | | LAMPS | | | | | VOLTS | TOTAL CONNECTED WATTS | TOTAL RATED WATTS | MOUNTING | FINISH | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | MANUFACTURER | CATALOG NUMBER | QTY | TYPE | WATTS | INIT. MIN. LUMENS | TEMP. COLOR (KELVINS) | | | | | | |
| 1 | GOTHAM LIGHTING | ALED-30/18-6-AR-120 | 1 | LED | 38 | 1867 | 3000 | 120 | 38 | 38 | CEILING/RECESSED | WHITE | |
| 2 | LITHONIA LIGHTING | RAZ18 | 1 | LED | 9.7 | 349.2 | 3000 | 120 | 10 | 10 | SURFACE/ UNDERCABINET | WHITE | UNDER CABINET LIGHTING SHALL BE DIRECT WIRED USING PART: UCDJB, AND SHALL BE CONNECTED TO A 24 VOLT TRANSFORMER USING PART: RAZTRANS24 120. PROVIDE ALL OTHER ACCESSORIES REQUIRED FOR COMPLETE INSTALLATION OF UNDER CABINET LUMINAIRES. |
| 3 | LITHONIA LIGHTING | CA-2-32-MVOLT-GEB10PS-LP830 | 2 | T8 | 32 | 2950 | 3000 | 120 | 64 | 64 | CEILING/SURFACE | WHITE | |
| 4 | HUBBARDTON FORGE | 139590-07-48 | 1 | EL/mdT DIM | 20 | 1150 | 3000 | 120 | 20 | 100 | CEILING/ PENDANT | DARK SMOKE HARDWARE | INSTALL 20 WATT ENERGY SAVING "DIMMABLE" FLUORESCENT LAMPS. SHADE TO BE NATURAL ANNA. MOUNT LUMINAIRE AT 6'-6" TO BOTTOM OF FIXTURE. |
| 5 | HUBBARDTON FORGE | 206410-G | 2 | GU24 | 26 | 1600 | 3000 | 120 | 52 | 52 | SURFACE WALL | BRUSHED STEEL WITH OPAL GLASS | WALL MOUNT LUMINAIRE AT 2" ABOVE VANITY MIRROR TO THE BOTTOM OF THE LUMINAIRE. |
| 6 | HUBBARDTON FORGE | 126503-252290-37-251590-48 | 3 | EL/mdT DIM | 20 | 1150 | 3000 | 120 | 60 | 300 | CEILING/ SEMI-FLUSH MOUNT | DARK SMOKE HARDWARE | INSTALL 20 WATT ENERGY SAVING "DIMMABLE" FLUORESCENT LAMPS. INNER SHADE TO BE ECLIPSE MICRO-SUEDE, OUTER SHADE TO BE NATURAL ANNA. |
| 7 | LITHONIA LIGHTING | 2RTLED-3300L D45 LP830 N100 | 1 | LED | 45 | 3300 | 3000 | MVOLT | 45 | 45 | RECESSED CEILING | WHITE | |
| 8 | WINONA LIGHTING | 5230-F-120-FAHS-BB-STD | 2 | PL-T | 26 | 1800 | 3000 | 120 | 52 | 52 | CEILING/SURFACE | BRUSHED BRASS | |
| 9 | LITHONIA LIGHTING | 2AV-G-2-32-SBL-MVOLT-GEB10RS-LP830 | 2 | T8 | 32 | 2950 | 3000 | MVOLT | 64 | 64 | CEILING/RECESSED | WHITE | |
| 10 | COLOR KINETICS | COLORBURST POWERCORE ARCHITECTURAL | 1 | LED | 30 | 647 | RGB | MVOLT | 30 | 30 | SURFACE FLOOR | GREY | 8 DEGREE BEAM ANGLE. FIELD AIM LUMINAIRES TO WASH ADJACENT COLUMNS. COORDINATE FINAL AIMING WITH ARCHITECT. PROVIDE FIXTURE WITH HONEYCOMB LOUVER ACCESSORY. |
| 11 | LITHONIA LIGHTING | OLW14 | 1 | LED | 26.45 | 1436 | 5470 | MVOLT | 26 | 26 | SURFACE WALL | BRONZE | WALL MOUNT LUMINAIRE AT 72" ABOVE FINISH FLOOR TO CENTER OF FIXTURE. |
| 12 | LITHONIA LIGHTING | 2GT8-2-32-A12-MVOLT-GEB10RS-LP830 | 2 | T8 | 32 | 2950 | 3000 | MVOLT | 64 | 64 | CEILING/RECESSED | WHITE | |
| 13 | LITHONIA LIGHTING | 2GT8-2-17-A12-MVOLT-GEB10RS-LP830 | 2 | T8 | 17 | 1350 | 3000 | MVOLT | 34 | 34 | CEILING/RECESSED | WHITE | |
| F1 | QUORUM INTERNATIONAL | 43525-44 | - | - | - | - | - | 120 | 68 | 68 | CEILING/SURFACE | TOASTED SIENNA/WALNUT | PROVIDE FAN WITH TOASTED SIENNA HOUSING AND ROSEWOOD/WALNUT BLADES. COORDINATE FAN SWITCH REQUIREMENTS WITH MANUFACTURER SHOP DRAWINGS. |
| X1 | LITHONIA LIGHTING | EDG-R | 1 | LED | 2.5 | - | - | MVOLT | 2.5 | 2.5 | SURFACE CEILING / SURFACE WALL | WHITE | REFER TO ELECTRICAL PLANS FOR NUMBER OF FACES AND DIRECTIONAL ARROWS. |

three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
three eighths inch = one foot
one quarter inch = one foot
one eighth inch = one foot

| Revisions: | Date: |
|---|---|
| | |


ARCHITECT/ENGINEERS:

SFCS Architecture Engineering Planning Interiors

SFCS Inc. ▪305 South Jefferson Street
Roanoke, Virginia 24011.2003
540.344.6664 ▪Fax 540.343.6925
www.sfcs.com


COMMONWEALTH OF VIRGINIA
TYE A. UPPER
12/14/2007
PROFESSIONAL ENGINEER

Approved: Energy Engineer

Approved: Infection Control

Approved: Service Chief

CONSTRUCTION DOCUMENTS

Approved: Safety Manager

Approved: Chief of Staff

Approved: GEMS Coordinator

Approved: Associate Director

Drawing Title: LUMINAIRE SCHEDULE

Approved: Chief of Facility Management Services

Approved: Medical Center Director

Project Title: Patient Dining Area CLC
VA Medical Center
SFCS Commission Number: 6527.00

Location: Salem, Virginia

Date: 03/15/12

Checked: WAM

Drawn: CIW

Project Number: 658-307

Building Number(s): 2/2A

Drawing Number: E0.2

Dwg. 57 of 65

Office of Construction and Facilities Management

Department of Veterans Affairs

VA FORM 08-6231 (Modified)

9/20/11 10:35 A.M.