



PARTIAL EXISTING THIRD FLOOR PLAN - LIGHTING

2	THIRD FLOOR PLAN - LIGHTING
---	-----------------------------

PLAN NOTES (THIS DWG)

① PROVIDE PHILIPS COLOR KINETICS IPLAYER 3 CONTROLLER WITH POWER CORD ACCESSORY. ITEM # 103-0000041-00 TO CONTROL ALL TYPE 10 FIXTURES. IPLAYER 3 SHALL BE PROGRAMMED TO TURN TYPE 10 FIXTURES ON AT SUNSET AND OFF AT MIDNIGHT.

② PROVIDE DATA ENABLER PRO ABOVE CEILING. CONNECT BACK TO IPLAYER 3 LOCATED IN ROOM 301 UTILIZING CAT6 OR CAT6. PROVIDE 120V POWER CONNECTION UTILIZING CIRCUIT SHOWN. COORDINATE EXACT ELECTRICAL CONNECTIONS WITH MANUFACTURER SHOP DRAWINGS.

PLAN NOTES (THIS DWG)

- (4) UTILIZE BODINE #RLCD-208 TO ENSURE AUTOMATIC ON OF EMERGENCY LIGHT FIXTURES IN THE EVENT OF A POWER LOSS. PROVIDE WIRING TO EMERGENCY RELAY CONTROLS ALL EMERGENCY FIXTURES ON SWITCHES FOR INDICATED EMERGENCY CIRCUIT.
- (5) PROVIDE NEW LIGHTING CIRCUIT FOR NEW LIGHT FIXTURES IN THIS ROOM. UTILIZE CIRCUIT 2-HBA-24 TO FEED NEW FIXTURES. PANEL 2-HBA 15 LOCATED APPROXIMATELY Y 100 FEET AWAY IN ELECTRICAL ROOM 3-325C.
- (6) PROVIDE FAN CONTROLLER COMPATIBLE WITH TYPE II CEILING FAN COORDINATE REQUIREMENTS WITH MANUFACTURERS SHOP DRAWINGS.

PLAN NOTES (THIS DWG)

- ① PROVIDE MANUFACTURER RECOMMENDED BACKBOXES FOR DIMMER SWITCHES TO ENSURE THAT DIMMERS ARE NOT DERATED. MOUNT DIMMERS AND SWITCHES AT 48" AFF TO CENTER OF DEVICE. REFER TO DETAIL 46/1 FOR DEVICE SPACING.
- ② UTILIZE EXISTING SWITCH LOCATIONS IN SPACE FOR NEW SWITCHES TO CONTROL NEW LIGHT FIXTURES. UTILIZE EXISTING LIGHTING CIRCUIT SERVING ROOM TO POWER NEW LIGHT FIXTURES. EXTEND WIRING AND CONDUIT AS NECESSARY FOR CONNECTION TO NEW FIXTURES.
- ③ FIXTURES TO BE SWITCHED WITH LOCAL CORRIDOR FIXTURES. UTILIZE EXISTING LIGHTING CIRCUIT SERVING AREA TO POWER NEW LIGHT FIXTURES. EXTEND WIRING AND CONDUIT AS NECESSARY FOR CONNECTION TO NEW FIXTURES.

GENERAL NOTES (THIS DWG)

I. ALL EXIT SIGNS SHALL BE TYPE XI.

ROOM SCHEDULE	
NUMBER	NAME
300	EXISTING LOBBY
301	FOYER
302	UNISEX TOILET
303	STORAGE
304	KITCHEN
305	STOR
306	DINING
307	MEGH
308	COVERED PORCH
309A	STOR
309B	STAIR
309	STORAGE
310	MEDS ROOM
311	RECEPTION
312	WC TOILET
313	CORR.
314	STORAGE
315	OFFICE
316	OFFICE
317	CONFERENCE ROOM
318	CORRIDOR
319	CORRIDOR

[illegible]

ARCHITECT/ENGINEERS:

SFC S | Architecture
Engineering
Planning
Interiors

SFCS Inc. • 305 South Jefferson Street
Roanoke, Virginia 24011.2003
540.344.6664 • Fax 540.343.6925
www.sfcs.com



Approved: Energy Engineer

CONSTRUCTION
DOCUMENTS

Approved: Infection Control
Approved: Safety Manager
Approved: GEMS Coordinator

Approved: Service Chief
Approved: Chief of Staff
Approved: Associate Director

Drawing Title: THIRD FLOOR PLAN - LIGHTING	
Approved: Chief of Facility Management Services	
Approved: Medical Center Director	

Project Title: Patient Dining Area CLC VA Medical Center SFCS Commission Number: 6527.00		
Location: Salem, Virginia		
Date: 03/15/12	Checked: WAM	Drawn: CIW

Project Number:
658-307

Building Number(s):
2/2A

Drawing Number:
E1.2

Dwg. 60 of 65