

Salient Characteristics

Vendor Shall: Remove the existing condensate return system, vacuum system, piping and heaters.

Description of Need: Install a pressure powered condensate return pump package in building two

Must meet the following specs:

Install Spriax pump package Model # DPC2-0-CS-D-12670

Pumps must meet hydro test pressure of 15 psig

Reciver PMO = 0 psig @ 300F sized for flash steam rates of up to 2000 lb/hr

Over flow connection on receiver should be with a loop seal and visible discharge

Unit must be anchored to the floor

Reinsulate all new piping and tanks

Install a new vent piping and size to meet code