



1511 Route 22, Suite C24, Brewster, NY 10509
Phone: 845.278.7710 Fax: 845.278.7750

Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

Project: Main Building, 1st Floor

VA Medical Center
Wilkes-Barre, PA 18711

Inspector(s): James Reber

Thomas Ferro

Date(s): 2/2010-3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
1st Floor, W wing, room C1-01						
Floor	Rug over red brown 9" X9" floor tile	280 ft ²	N/A	4/12-03	N/A	15% Chrysotile
Walls	Sheetrock/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32-64ft ²	Damaged			Assumed
1st Floor, W wing, room C1-02 (suite)						
Floor	Rug over floor tile	360 ft ²	N/A	4/12-01	N/A	3% Chrysotile
	Mastic	360 ft ²	N/A	4/12-02	N/A	10% Chrysotile
Walls	Sheetrock/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	V	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, room C1-03						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile	160 ft ²	N/A	N/A	Prev. tested pos.	>1%
	Floor tile mastic	160 ft ²	N/A	N/A	Prev. tested pos.	>1%

VA Medical Center, Main Building, 1st Floor

Adelaide Environmental Health Services, Inc. – Project No. VAMC:10013.00-IN



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tiles (above 2' X 4')	160 ft ²	N/A	N/A	1-195	None detected
Univents	Transite panels	20-40 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, room C-1-03A						
Floor	Rug over tile	N/A	N/A	N/A	N/A	Non-suspect
	12" x 12" floor tile and mastic	200 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tiles (off white w/ grainy surface) – above 2' X 4'	N/A	N/A	1-195	N/A	None detected
Univents	Transite panels	20-40 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, W wing, room C1-05 (suite) – 05 , 06, 07, 08, 09, 10, 11, 12, 13						
Floor	Rug over concrete or platform	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tiles (white w/rows of holes) – above 2' X 4'	N/A	N/A	N/A	1-187	None detected
Univents	Transite panels (one front panel missing)	100-200 ft ²	Damaged	N/A	N/A	Assumed
Over ceiling, far S wall	Duct insulation (black mastic over cork)	Not found	N/A	N/A	6-96	Not found
Chases + over ceiling in room next to ladies room	Pipe insulation (C1-11)	12 LF	Good	N/A	N/A	Assumed



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, W wing, ladies' (C1-14) and men's (C1-15) rooms across from C1-05						
In wall between mens/ladies rooms	Pipe insulation	5 LF	Good	N/A	N/A	Assumed
1st Floor, W wing, electrical closet (E of stair #1)						
Pipe riser	Pipe insulation (black mastic over cork)	10 LF	Good	N/A	6-96	8% Chrysotile
1st Floor, room C1-18						
Floor	12" X 12" floor tile (light gray w/white dark gray mottles)	100 ft ²	N/A	N/A	6-105	None detected
	Floor tile mastic	100 ft ²	N/A	N/A	6-106	5% Chrysotile
Ceilings	2' X 2' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	24-48 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, room C1-19						
Floor	Rug over leveling compound over black mastic - Removed	N/A	N/A	N/A	N/A	N/A
	Black mastic - Removed	150 ft ²	N/A	N/A	N/A	N/A
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, rooms C1-21B and C1-21C and C1-20						
Floor	Rug over floor tile - Removed	N/A	N/A	N/A	N/A	N/A
	12" X 12" floor tile - Removed	150 ft ²	N/A	N/A	N/A	N/A
Walls	Plaster/ sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, W wing, room C1-21A - Removed and is part of C1-22A now						
Floor	12" X 12" floor tile (white w/olive mottles) - Removed	525 ft ²	N/A	N/A		N/A
	Floor tile mastic - Removed	525ft ²	N/A	N/A		N/A
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, room C1-22A (and also C1-21B and C1-21C)						
Floor (raised floor; tiles not found underneath)	12" X 12" floor tile (off-white w/tan & brown streaks) - Removed	N/A	N/A	N/A	6-103	5% Chrysotile
	Floor tile mastic - Removed	N/A	N/A	N/A	6-104	5% Chrysotile
Walls	Sheetrock	N/A	N/A	N/A	Previously tested positive	>1%
Ceilings	2' X 4' ceiling tiles - removed	N/A	N/A	N/A	Previously tested positive	>1%
1st Floor, room C1-22						
Floor	12" X 12" floor tile (white w/brown streaks) –E room (C1-22D)	150 ft ²	N/A	N/A	6-103	5% Chrysotile
	Floor tile mastic	150 ft ²	N/A	N/A	6-104	5% Chrysotile
	12" x 12" floor tile (off white w/tan marks) –W room	150 ft ²	N/A	N/A	3-165	None detected
	Floor tile mastic- W room	150 ft ²	N/A	N/A	3-166	5% Chrysotile
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
C1-22E has pipe insulation – 8 LF, good. Same floor tiles as C1-22 – 484 ft². Has suspect drywall on S wall - 30ft², damaged						



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, mechanical room behind C1-22 (on drawings as C1-22C)						
Floor	12" X 12" floor tile (off-white w/tan marks)	400 ft ²	N/A	N/A	3-165	None-detected
	Floor tile mastic	400 ft ²	N/A	N/A	3-166	5% Chrysotile
1st Floor, room C1-23						
Floor	Rug	N/A	N/A	N/A	N/A	Non-suspect
	12" X12' floor tile	400 ft ²	N/A	N/A	N/A	Assumed
	Floor tile mastic	400 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tiles & plaster	Pipe insulation	10 LF	Damaged	N/A	N/A	Assumed
1st Floor, room C1-24 and C1-27 (Armory)						
Floor	12" X 12" floor tile (off white w/tan & dark tan mottles)	N/A	N/A	N/A		Non-suspect
	Floor tile mastic	N/A	N/A	N/A		Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels removed)	24-48 ft ²	Damaged	N/A	N/A	Assumed
Chases	Pipe insulation	N/A	N/A	N/A	N/A	Assumed



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, room C1-28						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
	12" x 12" floor tile and mastic - Removed	200 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off white w/random pock markings)	200 ft ²	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	24-48 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, Room C1-32						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile- new	V	V	V	V	Non-suspect
Chases	Pipe insulation – no view in chases	indeterminate	N/A	N/A	N/A	Assumed
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, rooms C1-32-A and C1-32B – No suspect materials observed						



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, E wing, room C1-30						
Floor	9" X 9" floor tile (brown)	25 ft ²	Good	N/A	N/A	Assumed
	Floor tile mastic	25 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, E wing, room C1-35A						
Pipes	Pipe insulation (black mastic over cork)	12 LF	N/A	N/A	6-96	8% Chrysotile
1st Floor, rooms C1-36 and C1-37						
Ceilings	12" X 12" ceiling tiles (white, perforated)	20-30 ft ²	N/A	1-187	N/A	None detected
	2' X 2' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
	Ceiling tile mastic	20-30 ft ²	N/A	1-188	N/A	None detected
Univents	Transite panels	32-64 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, E wing, room C1-36A						
S wall	Pipe insulation	30 LF	Significant damage	N/A	N/A	Assumed
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed
Comments: Behind the plaster fascia, there is a pipe chase which runs E to W on the S wall. Suspect pipe insulation may exist within the chase, and this situation may exist in all rooms within this area						
1st Floor, room C1-38						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tiles- new and 12" X 12"	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	40 – 80 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, E wing, rooms C1-43,C1-44, C1-45, C1-51, C1-52, 56A – No exposed suspect asbestos materials observed						
1st Floor, E wing, rooms C1-39, C1-40, C1-41, & C1-42						
Univents	Transite panels	50 ft	Damaged	N/A	N/A	Assumed
Comments: Except for C1-42, the front transite panels have been removed. The rear could not be observed at the time of this inspection and could be present.						
1st Floor, room C1-53						
Pipe in SW corner	Pipe insulation in chase- can't see condition	N/A	N/A	N/A	N/A	Assumed
1st Floor, room C1-54						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tiles	Pipe insulation (SE corner)	5 LF	Good	N/A	N/A	Assumed
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, room C1-56-B, C1-56C (Corridors)						
Floors	12" X12" floor tile-Terrazzo	N/A	N/A	N/A	N/A	Non-suspect
	Floor tile mastic	N/A	N/A	N/A	N/A	N/A
Walls	Plaster/	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 4' ceiling tile over fireproofing	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, C1-56						
Floor	12" X 12" floor tile (brown w/ white, gray and dark brown marble effect)	480 ft ²	N/A	N/A	1-01	None detected
	Floor tile mastic	480 ft ²	N/A	N/A	1-02	3% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles (concrete deck)	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Pipe insulation (runs down into SW wall)	15-20 LF	Significant damage	N/A	N/A	Assumed
Univents	Transite panels	32-64 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, room C1-55						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12 X 12" floor tile	160 ft ²	N/A	N/A	N/A	Assumed
	Floor tile mastic	160 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	12" X 12" ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, smoking area NOT FOUND – Non-existing						
Floor	12" X 12" floor tile (off-white w/ tan & dark tan mottles)	625 ft ²	N/A	8-281	N/A	None detected
	Floor tile mastic	625 ft ²	N/A	8-282	N/A	<1% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	12" X 12" ceiling tile	N/A	N/A	8-283	N/A	None detected



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, room C1-59						
Floor	12" X 12" floor tile (off-white w/gray mottles) and mastic	115 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above & behind plaster	Pipe insulation	20-30 LF	N/A	N/A	v N/A	Assumed
1st Floor, ladies room (C1-60) & men's room (C1-61) plus C1-58 (vestibule)						
Above ceiling and in walls where it was partially removed and replaced w/ fiberglass	Pipe insulation	N/A	Damaged	N/A	N/A	Assumed
Comment: C1-58 vestibule – 18 LF of pipe (aircell). Nothing above men's room/no access to ladies room ceiling						
1st Floor, room C1-62						
Floor	Ceramic Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, room C1-63						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, C1-64						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (white w/ striations)	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, room C1-65, C1-66, C1-67, C1-68						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	Previously tested	Non-suspect
Comments: In rooms C1-63 through C1-68, suspect asbestos insulation possible on pipes above plaster ceiling						
1st Floor, W wing, room C1-70						
Floor	Rug over 12" X 12" floor tiles/mastic	185 ft ²	N/A	N/A	N/A	Assume
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, room C1-71 and C1-70-A						
Floor	Rug over brown 9X9 floor tile and mastic	360 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tile (white w/rows of holes) – above 2' X 4'	160 ft ²	N/A	N/A	1-187	None detected



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, W wing, room C1-72						
Floor	Rug over leveling compound and brown 9X9 floor tile and mastic	180 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	1-196	N/A	None detected
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tiles (off-white w/ holes) – above 2' X 4'	150 ft ²	N/A	N/A	1-187	None detected
1st Floor, W wing, rooms C1-74a, C1-74, & C1-73						
Floor	Rug over brown 9X9 floor tile and mastic	450 ft ²	Good	N/A	N/A	Assumed
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' Ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tiles (white w/rows of holes) – above 2'X4'	380 ft ²	N/A	N/A	1-187	None detected
Comments: No access under rug at the time of this inspection – possible floor tile and mastic materials under rug. Checked – Floor tile found						
1st Floor, room C1-76						
Pipes	Pipe / fitting insulation	4-6 LF	N/A	N/A	N/A	Assumed
1st Floor, room C1-77						
Floor	9" X 9" floor tile (white w/ black flecks)	110 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, hall by main elevator						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Marble	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, main hall (mental health to Chapel Hall) (C1-18)						
Floor	12" X 12" floor tile (tan w/ white/dark tan mottles)	2696 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	2696 ft ²	N/A	N/A	8-040	2% Chrysotile
1st Floor, security locker room by stair # 3 (C1-78)						
Floor	12" X 12" floor tile (chocolate w/ white/brown marble effect)	40 ft ²	N/A	N/A	7-86	None detected
	Floor tile mastic	40 ft ²	N/A	N/A	7-87	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	4 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, N wing, N1-71 (Not on plans or in field)						
Floor	Rug over leveling compound	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/carpeted panels	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation	8 LF	Damaged	N/A	N/A	Assumed
Univents	Transite Panels	16-32 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, N wing, room N1-80						
Floor	12" X 12" floor tile (off-white w/ light & dark olive mottles)	216 ft ²	N/A	N/A	1-286	5% Chrysotile
	Floor tile mastic	216 ft ²	N/A	N/A	1-287	3% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, N wing, room N1-81 (room N of N1-80)						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile (off-white w. light & dark olive mottles)	300 ft ²	N/A	N/A	1-286	5% Chrysotile
	Floor tile mastic	300 ft ²	N/A	N/A	1-287	3% Chrysotile
Walls	Plaster/Sheetrock	N/A	N/A	N/A	✓	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tiles & above E wall & duct	Pipe insulation	< 25 LF	FN/A	N/A	N/A	Assumed
1st Floor, N wing, room N1-86D						
Floor	Rug over tile	N/A	N/A	N/A	N/A	Non- suspect
	12" X 12" floor tile (white w/ black streaks	560 ft ²	N/A	N/A	8-028	10 % Chrysotile
	Floor tile mastic	560 ft ²	N/A	✓	8-029	5% Chrysotile
Walls	Plaster/ sheetrock	N/A	N/A	N/A	N/A	Non- suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non- suspect
Above ceiling tile	Pipe insulation	20-25 LF	Damaged	N/A	N/A	Assumed
Univents	Transite panels	64-128 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, N wing, room just S of N1-81						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-Suspect
	12' x 12" (off-white w/ light and dark olive mottles)	160 ft ²	N/A	N/A	1-286	5% Chrysotile
	Floor tile mastic	160 ft ²	N/A	N/A	1-287	3% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Pipe insulation	8-10 LF	Damaged	N/A	N/A	Assumed
1st Floor, N wing, room N 1-82						
Floor	12" X12" Floor tile (off-white w/ light & dark olive mottles)	80-100 ft ²	N/A	1-286	N/A	5% Chrysotile
	Floor tile mastic	80-100 ft ²	N/A	1-287	N/A	3% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" x 12" ceiling tile (white w/ rows of holes) –above 2' X 4'	N/A	N/A	N/A	Previously tested	<1%
1st Floor, N wing, room N1-83						
Floor	Carpet over 12" X12" floor tile (tan w/ white/dark tan mottles)	250 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	250 ft ²	N/A	N/A	8-040	2% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile/plaster ceiling	Pipe insulation (can't see above plaster)	N/A	N/A	N/A	N/A	Assumed



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, N wing, room N1-85						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Marble/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	216 ft ²	Damaged	N/A	2-121	5% Chrysotile
Comments: No access above ceiling tiles within this area due to the asbestos content of the ceiling tiles.						
1st Floor, N wing, room N1-86 and Mechanical room Labeled N1-89 on drawings(which is labeled twice)						
Floor	12" X 12" floor tile (white w/tan & dark tan mottles)	960 ft ²	N/A	N/A	5-69	None detected
	Floor tile mastic	960 ft ²	N/A	N/A	5-70	5% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Ceiling tile - Removed					N/A
Above ceiling tile	Pipe/fitting insulation (N1-86)	20-25 LF	Damaged	N/A	N/A	Assumed
Pipes in Mech N1-89	Valve Fitting Insualtion	1 LF	Significant Damage	N/A	N/A	Assumed
Univents	Transite panels	64-128 ft ²	Damaged	V	N/A	Assumed
1st Floor, N wing, room N1-89 (Room between N1-86D and N1-79)						
Floor	12" X12" floor tile under rug	250 ft ²	N/A	N/A	1-286	5% Chrysotile
	Mastic	250 ft ²	N/A	N/A	1-287	3% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
In chase	Pipe/fitting insulation	20-30 LF	Good	N/A	N/A	Assumed
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, N wing, room N1-91						
Pipe riser	Pipe insulation (black mastic over cork)	10 LF	Good	N/A	6-96	8% Chrysotile
1st Floor, N wing, room N1-92 and N1-93 (bathroom)						
Floor	12" X 12" floor tile (gray/green w/ white & gray mottles) - Removed	160ft ² (N1-92) 50ft ² (N1-93)	N/A	1-190	N/A	N/A
	Floor tile mastic - Removed	160 ft ²	N/A	1-191	N/A	N/A
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile and plaster	Pipe insulation	>30 LF	Good	N/A	N/A	Assumed
Univents (N1-92 only)	Transite panels	16-32 ft ²	Significant damage	N/A	N/A	Assumed
1st Floor, N wing, room N1-95 and N1-94 (bathroom)						
Floor	12" X 12" floor tile (gray/green w/ white & gray mottles)	150 ft ²	Good	N/A	1-190	5% Chrysotile
	Floor tile mastic	150 ft ²	N/A	N/A	1-191	10% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile (over W wall)	Pipe insulation	20 LF	Good	N/A	N/A	Assumed
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, N wing, rooms N1-99, N1-100, N1-102A, N1-102, N1-103A, N1-103 and N1-104A						
Floor	9" X9" floor tile (white w/blue marks)	~160 ft ² /area	N/A	N/A	N/A	Assumed
	Floor tile mastic	~160 ft ² /area	N/A	N/A	N/A	Assumed
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
In chases (all rooms) & above ceiling tile in 99,102,103A- removed above ceilings	Pipe insulation – 103A No pipe above, 102 8in damage piece B4 chase, 99 can't see/plaster ceiling	20-30 LF each	Damaged	N/A	N/A	Assumed
Univents	Transite panels (103 & 103A 3 of 4 front panels gone)	16-32 ft ² /area	Damage	N/A	N/A	Assumed
1st Floor, N wing, rooms N1-104B and N1-104						
Floor	12" X 12" floor tile (gray w/ white and dark gray mottles)	160 ft ² /area	N/A	N/A	8-039	None detected
	Floor tile mastic	160 ft ² /area	N/A	N/A	8-040	2% Chrysotile
	9" X 9" floor tile (N1-104B)	4-5 ft ²	N/A	N/A	N/A	Assumed
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite Panels	16-32ft ² (104B) 8-16ft ² (104)	Damaged	N/A	N/A	Assumed
1st Floor, N wing, room N1-108						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, corridor N1-101						
Floor	12" X12" floor tile (off-white w/ light & dark tan mottles)	1400 ft ²	N/A	1-224T	N/A	None detected
	Floor tile mastic	1400 ft ²	N/A	1-224M	N/A	8% Chrysotile
	9" X 9" floor tile (by 104B)	6-8 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	16 ft ²	Damaged	N/A	N/A	Assumed
Above E ceiling	Pipe insulation in deck - Removed	N/A	N/A	N/A	N/A	Assumed
1st Floor, N wing, room N1-96A						
Floor	12" X 12" floor tile(over hard tile)	160 ft ²	N/A	1-225T	N/A	None detected
	Floor tile mastic	160 ft ²	N/A	1-225M	N/A	None detected
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, N wing, room N1-96						
Floor	12" X12" floor tile (over hard tile)	50 ft ²	N/A	N/A	1-225T	None detected
	Floor tile mastic	50 ft ²	N/A	N/A	1-225M	None detected



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, N wing, room N1-97						
Floor	12" X 12" floor tile (over hard tile)	160 ft ²	N/A	N/A	1-225T	None detected
	Floor tile mastic	160 ft ²	N/A	N/A	1-225M	None detected
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, N wing, room N1-98						
Floor	12" X 12" floor tile (over hard tile)	160 ft ²	N/A	N/A	1-225T	None detected
	Floor tile mastic	160 ft ²	N/A	N/A	1-225M	None detected
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, N wing, rooms N1-105A and N1-105						
Floor	12" X 12" floor tile	160 ft ² /area	N/A	N/A	1-225T	None detected
	Floor tile mastic	160 ft ² /area	N/A	N/A	1-225M	None detected
	9" X 9" floor tile (under 12" X 12")	160 ft ² /area	N/A	N/A	N/A	Assumed
	Floor tile mastic	160 ft ² /area	N/A	N/A	N/A	Assumed
Univents	Transite panels (N1-105 missing front panels)	16-32 ft ²	Damaged	N/A	N/A	Assumed
1st Floor, N wing, room N1-109						
Floor	12" X 12" floor tile (tan w/ white & dark tan mottles) - Removed	300 ft ²	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	300 ft ³	N/A	N/A	N/A	N/A



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X4' ceiling tiles	N/A	N/A	N/A	Previously tested	<1%
Above ceiling tile (N wall)	Pipe insulation	3 LF	Good	N/A	N/A	Assumed
Univents	Transite panels (front missing)	16 ft ²	Damaged	N/A	N/A	Assumed
Comments: The front of the panels have been removed. The rear panes could not be observed at the time of this inspection and could be present.						
1st Floor, N wing, room N1-110						
Floor	12" X12" floor tiles - Removed	150 ft ²	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	150 ft ²	N/A	N/A	N/A	N/A
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, N wing, rooms N1-111, N1-112, N1-113, N1-114, N1-115, N1-116, N1-119						
Floor	12" X 12" floor tile (yellow/orange) - Removed	180 ft ²	N/A	N/A	8-039	N/A
	Floor tile mastic - Removed	180 ft ²	N/A	N/A	N/A	N/A
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	16 ft ² / Room	Damaged	N/A	N/A	Assumed
Chases	Pipe insulation - Assume still there	N/A	N/A	N/A	N/A	Assumed



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, N wing, room N1-120						
Floor	12" X 12" floor tile - Removed	200 ft ²	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	200 ft ²	N/A	N/A	N/A	N/A
1st Floor, N wing, rooms N1-121, N1-122, N1-123, and N1-124 - Removed						
Floor	12" X 12" floor tile	100 ft ² /area 50 ft ² N1-124	N/A	N/A	8-039	None detected
	Floor tile mastic	100 ft ² /area 50 ft ² N1-124	N/A	N/A	8-040	2% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, N wing, room N1-125						
Floor	12" X 12" floor tile - Removed	200 ft ²	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	200 ft ²	N/A	N/A	N/A	N/A
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, N wing, room N1-130						
Floor	12" X 12" floor tile - Removed	100 ft ²	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	100 ft ²	N/A	N/A	N/A	N/A
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, N wing, room N1-131						
Floor	12" X 12" floor tile - Removed	50 ft ²	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	50 ft ²	N/A	N/A	N/A	N/A
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, N wing, telephone closet (off room N 1-136) and N1-128						
Floor	12" X 12" floor (telephone closet)	9 ft ²	N/A	N/A	N/A	Assumed
	Floor tile mastic	9 ft ²	N/A	N/A	N/A	Assumed
	12" X 12" floor tile(N1-128) - Removed	25 ft ²	N/A	N/A	N/A	Assumed
	Floor tile mastic - Removed	25 ft ²	N/A	N/A	N/A	Assumed
1st Floor, N wing, room N1-32 – Not on prints or Field						
Floor	Rug over tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile	160 ft ²	N/A	N/A	N/A	Assumed
	Floor tile mastic	160 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tiles (N wall)	Pipe insulation	5 LF	Damaged	N/A	N/A	Assumed



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1ST Floor, N wing, rooms N1-134, N1-135, N1-136 (dental area)						
Floor	Rug over concrete or terrazzo	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock and joint material	N/A	N/A	1-189	N/A	None detected
Above ceiling tiles (wall by nurse' station)	Pipe insulation - Removed	N/A	N/A	N/A	N/A	N/A
1st Floor, halls (in dental areas)						
Floor	12" X12" floor tile - Removed	N/A	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	N/A	N/A	N/A	N/A	N/A
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' Ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, N wing, room N1-136A – Area not present						
Floor	12" X 12" floor tile	320 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	320 ft ²	N/A	N/A	8-040	2% Chrysotile
Walls	Sheetrock	N/A	N/A	1-189	N/A	None detected
Ceilings	2'X4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
1st Floor, N wing, room N1-137						
Floor	12" X 12" floor tile (white w/tan & dark tan mottles)	20 ft ²	N/A	N/A	5-69	None detected
	Floor tile mastic	20ft ²	N/A	N/A	5-70	5% Chrysotile



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

1st Floor, N wing, rooms N1-143, N1-142, N1-141, N1-140, N1-139 and N1-138						
Floor	Rug over terrazzo	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster / sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Main Chapel and Sacristy						
Floor of main chapel	Rug over concrete (main area) Altar – rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" Floor tile (purple w/ white/dark purple markings)	940 ft ²	N/A	C-149	N/A	None detected
	Floor tile mastic	940 ft ²	N/A	C-159	N/A	2% Chrysotile
Floor of Sacristy	9" X 9" Floor tile	300 ft ²	N/A	N/A	N/A	Assumed
	Floor tile mastic	300 ft ²	N/A	N/A	N/A	Assumed
Walls	Sheetrock/joints	N/A	N/A	N/A	Previously tested	None detected
Ceiling	2' X 2' ceiling tile (tan, rough variegations w/foil backing)	N/A	N/A	N/A	N/A	Non-suspect
Sacristy Closet	Pipe insulation	30-40 ft	Significant damage	N/A	N/A	Assumed
Eucharist Room (21-3)						
Floor	Rug over wood underlayment over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock/ Joint	N/A	N/A	N/A	Previously tested	None detected
Ceilings	2' X 4' ceiling tile (off-white, crater- like worm markings)	N/A	Good	C-148	N/A	None detected



Building 1, Floor I - Specific Survey Findings
Project No. VAMC: 10013.00-IN

S Office (21-4)						
Floor	Rug over 9" X 9" floor tile	150 ft ²	N/A	N/A	N/A	Assumed
	Mastic					Assumed
Walls	Sheetrock/Joints	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles (Not fire rated)	N/A	N/A	N/A	N/A	Non-suspect
Hall to Chapel (21-13)						
Floor	12" X 12" floor tile/carpet	N/A	N/A	N/A	N/A	Non-suspect, installed after 1981
Pipes	Pipe fitting insulation	1 fitting	Good	N/A	N/A	Assumed
NOTE: No suspect asbestos-containing material were observed in rooms C1-17, C1-31, C1-43, C1-44, C1-45, C1-51, C1-52, C1-104, C1-56A, N1-133, N1-132, main hallway in dental areas, and crawlspace behind room C1-22 (mechanical room). The halls within the East wing have been recently renovated – no suspect asbestos-containing materials observed. The Dental Wing was completely renovated since 2005 Inspection						