



1511 Route 22, Suite C24, Brewster, NY 10509
Phone: 845.278.7710 Fax: 845.278.7750

Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

Project: Main Building, 2nd Floor
VA Medical Center
Wilkes-Barre, PA

Inspector(s): James Reber
Thomas Ferro
Date(s): 2/2010-3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
2nd Floor, Corridor – center/east (service elevator side and small hall to Nuclear Medicine)						
Floor	12" X 12" floor tile(light green w/white & dark green mottles)	1100 ft ²	good	N/A	7-58	15% Chrysotile
	Floor tile mastic	1100 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation – mastic and cork	>100 LF	Good	N/A	N/A	Assumed
2nd Floor, room C2-02 (No access – Assume materials still present)						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Metal/concrete	N/A	N/A	N/A	N/A	Non-suspect
NW Corner	Pipe insulation	2 LF	N/A	N/A	N/A	Assumed
2nd Floor, room C2-3A and C2-3B						
Floor	Composite/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

Small closet of NE corner of Liberty Hall, C2-21						
Floor	12" X 12" floor tile	16 ft ²	N/A	N/A	6-103	Assumed
	Floor tile mastic	16 ft ²	N/A	N/A	6-104	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
2nd Floor, room C2-03						
Floor	12" x 12" floor tile (light green w/ white & dark green mottles)	160 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	160 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed
2nd Floor, room C2-04						
Floor	12" X 12" floor tile – replaced w/carpet					N/A
	Floor tile mastic –replaced w/carpet					N/A
Walls	Paneling over plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles (white w/worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed
In walls	Brown tissue paper- like material	N/A	N/A	2-116	N/A	None detected
On walls	Plaster (light/soft)	N/A	N/A	2-117	N/A	None detected
Comment: Pipe insulation may be in chase						



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, room C2-05						
Floor	12" X 12" floor tile(light green w/white & dark green mottles)	168 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	168 ft ²	N/A	V	7-59	10% Chrysotile
Walls	Tile/plaster/paneling	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off white w/ pinhole perforations & crater worm markings)	N/A	N/A	2-120	N/A	None detected
	2' X 4' ceiling tile (off-white w/pinholes & pockmarks)	N/A	N/A	N/A	2-123	None detected
2nd Floor, room C2-05A						
Floor	12" X 12" floor tile (off –white w/ white & brown streaks)	332 ft ²	N/A	2-118	N/A	<1% Chrysotile
	Floor tile mastic	332 ft ²	N/A	2-119	N/A	5% Chrysotile
Walls	Plaster/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation (aircell)	35-40 LF	Damaged	N/A	N/A	Assumed
2nd Floor, room C2-05B						
Floor	12" X12" floor tile (white w/brown streaks)	192 ft ²	N/A	N/A	6-103	5% Chrysotile
	Floor tile mastic	192 ft ²	N/A	N/A	6-104	5% Chrysotile
Walls	Sheetrock joint material	N/A	N/A	2-118	N/A	None detected
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
Above ceiling tile	Pipe insulation	28 LF	Good	N/A	N/A	Assumed



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, hall by rooms C2-05A and 2-130						
Floor	12" X12' floor tile (light green w/white & dark green mottles)	385 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	385 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
Above ceiling tile	Pipe insulation	<10 LF	Damaged	N/A	N/A	Assumed
2nd Floor, room C2-06						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	198 ft ²	N/A	N/A	N/A	Non-suspect
Univents	Transite Panels	8-16 ft ²	Damaged	N/A	N/A	Assumed
Comment: Pipe insulation in chase - NE						
2nd Floor, rooms C2-07 & C2-08						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" Floor tile	144 ft ² / area	N/A	N/A	N/A	Assumed
	Floor tile mastic	144 ft ² / area	N/A	N/A	N/A	Assumed
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X4' ceiling tile(pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
Above plaster ceiling (room C2-08 & C2-07)	Pipe insulation	30 – 35 LF	Significant damage	N/A	N/A	Assumed



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

C2-09 and C2-10 – Probable asbestos pipe insulation in walls.						
C2-11 (corridor) – 12" X 12" green floor tile (7-58: 15% Chrysotile) and mastic (7-59: 10% Chrysotile) – 300 ft² - Good						
2nd Floor, Liberty Hall, room C2-14						
Floor	Ceramic Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/ sparse pinhole perforations & worm markings)	3500 ft ²	N/A	2-121	N/A	5% Chrysotile
Above ceiling tile (N wall)	Pipe insulation (black mastic over cork)	N/A	Good	N/A	6-96	8% Chrysotile
	Pipe insulation (aircell)	N/A	Good	N/A	N/A	Assumed
Comment: Cannot check above ceiling tiles because it will disturb ACM						
2nd Floor, room C2-13 (Credit Union) and C2-12						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock joint material	N/A	N/A	N/A	Previously tested	<1%
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Vertical chase	Pipe insulation	N/A	N/A	N/A	N/A	Assumed
2nd Floor, rooms C2-14B, C2-14C, C2-14D, C2-14E, and C2-14F						
Floor	Rug over concrete/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, room C2-15						
Floor	Rig over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	128 ft ²	N/A	N/A	2-123	None detected
Above ceiling tile (over N wall)	Pipe insulation	4 LF	Good	N/A	N/A	Assumed
2nd Floor, room C2-16						
Floor	Rug over ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 4' ceiling tile (pinhole perforations & worm markings)	144 ft ²	N/A	N/A	2-123	None detected
Above ceiling tile (N side)	Pipe insulation	10 LF	Good	N/A	N/A	Assumed
2nd Floor, room C2-17, C2-18, C2-19 (C2-19 not found)						
Floor	Ceramic Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	Non-suspect
Above ceiling and in chase(has cork pipe aircell)	Pipe insulation (aircell, mastic cork pipe)	>50 LF aircell >40 LF cork	N/A	N/A	N/A	Assumed
2nd Floor, pipe chase by C2-22 (electrical closet) (Room was not found)						
Pipe	Pipe insulation (black mastic over cork)	3 LF	N/A	N/A	6-96	8% Chrysotile



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, room C2-22						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile (tan w/white & dark tan mottles) – bathroom	40 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic – bathroom	40 ft ²	Good	N/A	8-040	2% Chrysotile
Ceilings	2' X4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
2nd Floor, room C2-23						
Floor	12" X 12" floor tile – new	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X4' ceiling tile (pinhole perforations w/ worm markings)	N/A	N/A	N/A	2-123	None detected
Univents	Transite panels	24-48 ft ²	Damaged	N/A	N/A	Assumed
Above ceiling tile	Pipe insulation (aircell)	16 LF	Good	N/A	N/A	Assumed
	Pipe insulation (black mastic over cork and MAG)	12 LF	Damaged	N/A	6-96	8% Chrysotile
Threshold of C2-24 and C2-25 – 3 ft² - 12" X 12" Floor tile (blue green) and floor tile mastic.						
2nd Floor, room C2-24						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile /plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X4' ceiling tile (off-white w/perforations & worm markings)	648 ft ²	N/A	N/A	2-128	None detected
Univents	Transite panels	40 – 80 ft ²	Damaged	N/A	N/A	Assumed
Above ceiling and in chase	Pipe insulation	>20 LF	Good	N/A	N/A	Assumed



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, room C2-25						
Floor	Rug 12" X 12' pads (brown)	258 ft ²	N/A	N/A	N/A	Non-suspect
	Mastic	258 ft ²	N/A	N/A	N/A	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
2nd Floor, room C2-27A Mechanical						
Pipes	Pipe insulation (black mastic over cork)	12 LF	Damaged	N/A	6-96	8% Chrysotile
2nd Floor, room C2-28						
Floor	Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile/plaster	Pipe insulation	25-30 LF	Good	N/A	N/A	Assumed
Univent	Transite panels (front missing)	8 ft ²	N/A	N/A	N/A	Assumed
2nd Floor, rooms C2-29 and C2-30						
Floor	12"X 12" floor tile under rug (room C2-29 & C2-30)	420 ft ²	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic (room C2-29)	420 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32-64 ft ² /area	Damaged	N/A	N/A	Assumed
Above plaster in C2-29	Pipe insulation	16-20 LF	Damaged	N/A	N/A	Assumed
2nd Floor, rooms C2-33A						
Floor	12" X 12" floor tile – new	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' –new	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	16 ft ²	N/A	N/A	N/A	Assumed
2nd Floor, room C2-30A						
Floor	Rug over 12" X 12" floor tile/mastic	N/A	N/A	N/A	N/A	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd floor, room C2-31						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile (off-white)	880 ft ²	N/A	2-131	7-59	5% Chrysotile
	Floor tile mastic	880 ft ²	N/A	N/A	N/A	Assumed
Walls	Wood paneling	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/ perforations & worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	24-48 ft ²	Damaged	N/A	N/A	Assumed
2nd Floor, room C2-33						
Floor	Rug over floor tile No rug	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile (off-white)	120 ft ²	Good	2-132	N/A	3% Chrysotile
	Floor tile mastic	120 ft ²	N/A	2-133	N/A	3% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	20 – 40 ft ²	Damaged	N/A	N/A	Assumed
E Wall	Pipe insulation	8 linear feet	N/A	N/A	N/A	Assumed
2nd floor, Room C2-33B through C2-43						
Floor	12" X 12" floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
2nd Floor, room C2-43A – No suspect material						



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, C2-44						
Floor	Terrazzo Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile 9pinhole perforations & worn markings	N/A	N/A	N/A	2-123	None detected
2nd Floor, hall by service elevator						
Floor	12' X 12" floor tile (light green W/ white & dark green mottles)	200 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor mastic	200 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Brick/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
Pipe insulation in chase behind elevator #2 – 15LF - Damaged						
2nd Floor, room C2-46 (Electrical closet)						
Pipe	Pipe insulation (black mastic over cork)	12 LF	Good	N/A	6-96	8% Chrysotile
Pipe	Pipe/fitting insulation on fiberglass lines	4 fittings	Good	N/A	N/A	Assumed
C2-106A and B, Pipe Room to N of 106B, and C2-107 – No exposed suspect asbestos containing materials observed.						
2nd Floor, room C2-47						
Floor	12" X 12" floor tile (chocolate w/white & dk brown marble effect)	120 ft ²	Good	N/A	7-86	None detected
	Floor tile mastic	120 ft ²	N/A	N/A	7-87	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12-24 ft ²	Damaged	N/A	N/A	Assumed



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, room C2-118 and C2-121 (Library area)						
Floor	Rug over	N/A	N/A	N/A		Non-suspect
	Mastic	N/A	N/A		2-112	None detected
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32-64ft ² (C2-118) 56-112 ft ² (C2-121)	Damaged	N/A	N/A	Assumed
C2-129 and C2-130 – No exposed suspect asbestos materials observed. (Not found)						
Recreation Room						
Floor	12" X 12" floor tile (off-white with brown mottles)	2000 ft ²	N/A	N/A	Previously tested positive	>1%
	Mastic	2000 ft ²	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
2nd Floor, N wing, room N2-48 (Labeled N2-49A on drawings)						
Floor	12" X 12" floor tile- green mottles) Not there – newer 12" X 12"	180-200 ft ²	N/A	N/A		
	Mastic	180-200 ft ²	N/A	N/A		
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	12-24 ft ²	Damaged	N/A	N/A	Assumed
Above ceiling tiles	Pipe insulation (aircell) – removed					



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, room N2-49						
Floor	Ceramic Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock joint material/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	36 ft ²	N/A	N/A	N/A	Assumed
Utility room off C49 9 (N2-49B)	Pipe insulation (aircell)	10 LF	Good	N/A	N/A	Assumed
2nd floor, N wing, room N2-50						
Floor	Ceramic Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock joint material/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
Univents	Transite panels (front panels missing)	20 ft ²	N/A	N/A	N/A	Assumed
SW Chase	Pipe insulation	>20 LF	N/A	N/A	N/A	Assumed
2nd Floor, N wing, N2-48A – Turned into mechanical room.						
Floor	12" X 12" floor tile — green mottled)					
	Mastic -Removed					
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Pipes in N wall	Pipe insulation/fitting	12 LF	Significant damage			Assumed



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, N wing, room N2-53						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	40 ft ²	N/A	N/A	N/A	Assumed
Chase – NE corner	Pipe insulation	>12 LF	N/A	N/A	N/A	Assumed
2nd Floor, N wing, room N2-55 & electrical room						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
2nd Floor, N wing, room N2-56 (Electrical room)						
Floor	Concrete/metal	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Vertical Chase	Pipe insulation 9black mastic over cork)	12 LF	Good	N/A	6-96	8% Chrysotile
Vertical Chase	Duct insulation (black mastic over cork)	100 ft ²	Good	N/A	6-96	8% Chrysotile
2nd floor, N wing, room N2-58						
Floor	12" X 12" and 2' X 2'	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	8 ft ²	N/A	N/A	N/A	Assumed



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, N wing, room N2-60 – No exposed suspect asbestos materials observed.						
2nd Floor, N wing, room N2-59						
Floor	12" X 12" Floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
Univents	Transite panels	32 ft ²	N/A	N/A	N/A	Assumed
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						
2nd Floor, N wing, rooms N2-64 and N2-64A						
Floor	12" X 12" floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings) – N2-64	N/A	N/A	N/A	2-123	None detected
	2' X 4' ceiling tile – N2-62	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe fitting - Removed	1	N/A	N/A	N/A	Assumed
Univents	Transite panels (front panels missing)	36 ft ²	N/A	N/A	N/A	Assumed
2nd Floor, N wing, rooms N2-66 and bathroom N2-67						
Bathroom - in chases	Pipe insulation	>40 LF	Significant damage	N/A	N/A	Assumed
Univents	Transite panels (N2-67)	8 ft ²	N/A	N/A	N/A	Assumed
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, N wing, room N2-68						
Floor	12" X 12" floor tile (tan w/white & dark tan mottles)	250-300 ft ²	N/A	N/A	8-039	None detected
	Floor tile mastic	250-300 ft ²	N/A	N/A	8-040	2% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	24 ft ²	N/A	N/A	N/A	Assumed
NE Corner chase	Pipe insulation – Same chase as N2-70	10-20 LF	Good	N/A	N/A	Assumed
2nd Floor, N wing, room N2-70						
Floor	12" X 12" floor tile (tan w/white & dark tan mottles)	36 ft ²	good	N/A	8-039	None detected
	Floor tile mastic	36 ft ²	N/A	N/A	8-040	2% Chrysotile
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	16 ft ²	N/A	N/A	N/A	Assumed
S wall	Pipe insulation	10-20 LF	Good	N/A	N/A	Assumed
2nd Floor, N wing, room N2-71						
Floor	12" X 12" floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	24 ft ²	N/A	N/A	N/A	Assumed
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, N wing, room N2-74						
Floor	Ceramic tile	N/A	N/A	N/A	8-039	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	8 ft ²	N/A	N/A	N/A	Assumed
Above ceiling & in chase	Pipe insulation	45 LF	Good	N/A	N/A	Assumed
2nd floor, N wing, room N2-75						
Floor	12" X 12' floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 44' ceiling tile (pinhole perforations & worm markings	N/A	N/A	N/A	2-123	None detected
Univents	Transite panels	32 ft ²	N/A	N/A	N/A	Assumed
Over ceiling tile	Duct insulation – removed	N/A	N/A	N/A	N/A	N/A
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						
2nd Floor, N wing, bathroom at E end of radiology hall (Labeled N2-66)						
Floor	12" X 12" floor tile (tan w/white and dk tan mottles) –Removed					
	Non-suspect concrete					
	Floor tile mastic - Removed					
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2" X 2' ceiling tile (off-white w/pinhole perforations & small crater)	36 ft ²	Good	2-127	N/A	None detected
Above ceiling tile	Duct insulation – removed	N/A	N/A	N/A	N/A	N/A



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, N wing, room N2-77 and N2-77A						
Floor	12" X 12" floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	Non-suspect
Univents	Transite panels (front panels missing)	16 ft ²	N/A	N/A	N/A	Assumed
In walls	Pipe insulation (Assume chases)	N/A	N/A	N/A	N/A	Assumed
2nd Floor, N wing, rooms N2-79 and N2-80						
Floor	12" X 12" floor tile (light green w/white & dk green mottles)	320 ft ²	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	320 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	24 ft ²	N/A	N/A	N/A	Assumed
Chase in N2-79	Pipe insulation	20-30 LF	N/A	N/A	N/A	Assumed
2nd Floor, N wing, room N2-83A						
Floor	12" X 12' floor tile(light green w/white & dark green mottles)	240 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	240 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

Ceilings	2'X4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32 ft ²	N/A	N/A	N/A	Assumed
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						
2nd Floor, N wing, rooms N2-84 and N2-84A						
Floor	12" X 12" floor tile	300 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	300 ft ²	N/A	N/A	7-59	10 % Chrysotile
Ceilings	2' X 4' ceiling tile (pinhole perforation & worm markings)	N/A	N/A	N/A	2-123	None detected
Univents	Transite panels	8 ft ² (N2-84) 16 ft ² (N2-84A)	N/A	N/A	N/A	Assumed
Above ceiling tile	Duct insulation (black mastic over cork)	7 LF	N/A	N/A	6-96	8%Chrysotile
Chase in N2-84	Pipe insulation	>40 LF	N/A	N/A	N/A	Assumed
2nd Floor, N wing, main hall (radiology area)						
Floor	12" X 12" floor tile (light green w/white and dk green mottles)	900 ft ²	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	900 ft ²	N/A	N/A	7-59	10% Chrysotile
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Duct insulation – removed	N/A	N/A	N/A	N/A	N/A



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, N wing, room N2-85 (files)						
Floor-most of floor tiles in this room are new	12" X 12" floor tile (chocolate w/white & dk brown marble effect)	126 ft ²	N/A	N/A	7-87T	None Detected
	Floor tile mastic	126 ft ²	N/A	N/A	7-87M	5% Chrysotile
Walls	Plaster/sheetrock/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing on some, present on others)	64-100 ft ²	Damaged	N/A	N/A	Assumed
	Pipe insulation	8 LF	Damaged	N/A	N/A	Assumed
Above ceiling tile	Duct insulation – removed	N/A	N/A	N/A	N/A	N/A
2nd Floor, N wing, room N2-95 and N2-96 – Newly renovated – no suspect asbestos materials observed						
2nd Floor, N wing, room N2-97A and N2-97B						
Floor	12" X 12" floor tile (green with mottles)	400 ft ² (97A) 220 ft ² (97B)	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	400 ft ² (97A) 220 ft ² (97B)	N/A	N/A	7-59	10% Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	36-72ft ² (97A) 24-48ft ² (97B)	Damaged	N/A	N/A	Assumed
NW Chase in 97A	Pipe insulation	>30 LF	N/A	N/A	N/A	Assumed



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, N wing, room N2-98 and N2-99						
Floor	9" x 9" floor tile (brown w/white & burnt sienna) (N2-98 only)	175 ft ²	Good	N/A	N/A	Assumed
	Floor tile mastic	175 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft ²	Damaged	N/A	N/A	Assumed
Above ceiling tile	Pipe insulation (aircell)	25 LF	Good	N/A	N/A	Assumed
2nd Floor, N wing, room N2-100 and N2-101						
Floor	9" X 9" floor tile (brown w/white marks and burnt sienna) - N2-101 only	175 ft ²	Good	N/A	N/A	Assumed
	Floor tile mastic	175 ft ²	N/A	N/A	N/A	Assumed
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
Assume pipes above plaster ceiling – >30 LF						



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, C-102, C2-103, C2-104, C2-105, C-105A, C2-105B and C2-106						
Floor – All floor tiles and mastic in these rooms are either new or tested negative for asbestos content	12" X 12" floor tile 9off-white w/blue mottles) –C2-106	N/A	N/A	2-129	N/A	<1% Chrysotile
	Floor tile mastic	N/A	N/A	2-130	N/A	None detected
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings) – C2-102, C2-103 & C2-104	525 ft ²	N/A	N/A	2-123	None detected
	2' X 4' ceiling tile (off-white w/pinhole perforations & craters)– C2-105 & adjoining room to S	400 ft ²	N/A	2-128	N/A	None detected
Above ceiling and in chases	Pipe insulation 4 LF above ceiling tiles, rest in chase	> 40 LF	Good	N/A	N/A	Assumed
Univents	Transite panels	88 ft ²	N/A	N/A	N/A	Assumed
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						
2nd Floor, room C2-108						
Univents	Transite panels	8 ft ²	N/A	N/A	N/A	Assumed
Above ceiling & in chases	Pipe insulation -	15 LF above plaster, 20-30 LF in chases	Good	N/A	N/A	Assumed
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						
2nd Floor, room C2-109						
Floor	12" X 12" floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Center chase	Pipe insulation	N/A	N/A	N/A	N/A	Assumed
2nd Floor, room C2-112						
Floor	12" X 12' floor tile (Chocolate w/white/brown & gray marbling)	180 ft ²	N/A	N/A	7-86	None detected
	Floor tile mastic	180 ft ²	N/A	N/A	7-87	5% Chrysotile
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling	N/A	N/A	N/A	N/A	Non-suspect
2nd Floor, room C2-113						
Floor	Rig over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
2nd Floor, room C2-115 (Part of Library)						
Floor	Rug over black mastic	N/A	N/A	N/A	N/A	Non-suspect
	Mastic	N/A	N/A	N/A	2-112	None detected
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x2' ceiling tile (rough faced)	1224 ft ²	N/A	N/A	2-228	None detected
Above ceiling tile	Pipe insulation	20 LF	Damaged ends exposed	N/A	N/A	Assumed



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, room C2-116 (Library)						
Floor	Rig over black mastic	N/A	N/A	N/A	N/A	Non-suspect
	Mastic	308 ft ²	N/A	2-112	N/A	None detected
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile (rough faced)	N/A	N/A	2-228	N/A	None detected
NW corner chase	Pipe insulation – can't see from above ceiling	8 LF	N/A	N/A	N/A	Assumed
Above ceiling and in south/center chase	Pipe insulation - can't see from above ceiling	>4LF	N/A	N/A	N/A	Assumed
2nd Floor, room C2-117						
Floor	Rug over black mastic	N/A	N/A	N/A	N/A	Non-suspect
	Mastic	168 ft ²	N/A	N/A	2-112	None detected
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile (rough faced)	N/A	N/A	N/A	2-288	None detected
Univents	Transite panels	32-64 ft ²	Damaged	N/A	N/A	Assumed
2nd Floor, electrical closet by stair #1						
Pipe riser	Pipe insulation (black mastic over cork)	12 LF	N/A	2-115	N/A	5% Chrysotile



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, room C2-119						
Floor	Rig over black mastic	N/A	N/A	N/A	N/A	Non-suspect
	Mastic	N/A	N/A	N/A	2-112	None detected
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 2' ceiling tile (rough faced)	288 ft ²	N/A	N/A	2-228	None detected
Univents	Transite panels	16-32 ft ²	Damaged	N/A	N/A	Assumed
2nd Floor, room C2-120						
Floor	12" X 12' floor tile(cream w/white & olive mottles)	300-400 ft ²	N/A	2-113	N/A	<1% Chrysotile
	Floor tile mastic	300-400 ft ²	N/A	2-114	N/A	3% Chrysotile
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	408 ft ²	N/A	N/A	2-228	None detected
Univents	Transite panels	64 - 128 ft ²	Significant damage	N/A	N/A	Assumed
2nd Floor, main hall						
Floor	12' X 12" floor tile (light green)	1600 ft ²	Good	N/A	7-58	15% Chrysotile
	Floor tile mastic	1600 ft ²	N/A	N/A	7-59	10% Chrysotile
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect



Building 1, Floor 2 - Specific Survey Findings
Project No. VAMC: 10013.00-IN

2nd Floor, rooms 2-130 and 2-129						
Floor	Composite	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/ pinhole & pockmarks)	96 ft ² /area	N/A	2-123	N/A	None detected

NOTE : No suspect asbestos-containing materials were observed in the following areas N2-73, N2-74, C2-43A, C2-106A and C2-106B.